# **Republic of the Philippines** ENERGY REGULATORY COMMISSION APProved

San Miguel Avenue, Pasig City

THE MATTER OF THE IN THE APPLICATION FOR APPROVAL OF THE PROPOSED FIVE (5) YEAR EXPENDITURE CAPITAL PROJECTS AND AUTHORITY TO SECURE LOAN FROM THE NATIONAL **ELECTRIFICATION ADMINISTRATION (NEA)** 

# ERC CASE NO. 2011-004 RC

| CEBU        | I    | ELECTRIC   |
|-------------|------|------------|
| COOPERAT    | IVE, | INC.       |
| (CEBECO I), |      |            |
|             |      | Applicant. |
| X           |      | <br>X      |

Www.erc.gov.ph

# DECISION

Before this Commission for resolution is the application filed on January 7, 2011 by Cebu I Electric Cooperative, Inc. (CEBECO I) for the approval of its proposed five (5) year capital expenditure projects and authority to secure loan from the National Electrification Administration (NEA).

Having found said application sufficient in form and in substance with the required fees having been paid, an Order and a Notice of Public Hearing, both dated January 18, 2011, were issued setting the case for jurisdictional hearing, expository presentation, pre-trial conference and evidentiary hearing on February 10, 2011.

In the same Order, CEBECO I was directed to cause the publication of the Notice of Public Hearing, at its own expense, twice (2x) for two (2) successive weeks in two (2) newspapers of general circulation in the Philippines, with the date of the last publication to be made not later than ten (10) days before the date of the scheduled initial hearing. It was also directed to inform the consumers, by any other means available and appropriate, of the filing of the instant

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 2 of 23

application, its reasons therefor and of the scheduled hearing thereon.

The Office of the Solicitor General (OSG), the Commission on Audit (COA) and the Committees on Energy of both Houses of Congress were furnished with copies of the Order and Notice of Public Hearing and were requested to have their respective duly authorized representatives present at the initial hearing.

Likewise, the Offices of the Mayors of the Municipalities and Cities within the franchise area of CEBECO I were furnished with copies of the Order and Notice of Public Hearing for the appropriate posting thereof on their respective bulletin boards.

On February 4, 2011, CEBECO I filed its "Pre-Trial Brief".

During the February 10, 2011 initial hearing, only CEBECO I appeared. No intervenor/oppositor appeared nor was there any intervention/opposition registered.

At the said hearing, CEBECO I presented proofs of its compliance with the Commission's posting and publication of notice requirements which were duly marked as Exhibits "D" to "DD-1", inclusive. Thereafter, it conducted an expository presentation of its application.

At the termination of the expository presentation, CEBECO I presented the following witnesses: 1) Engr. Getulio Z. Crodua, its Chief Engineer and designated Assistant General Manager for Operations; and 2) Mr. Juanito Gabales, Jr., its Finance Manager, who both testified in support of the application.

In the course of their direct examinations, additional documents were identified and duly marked as exhibits. Thereafter, the Commission propounded clarificatory questions on the said witnesses and directed the submission of various documents.

On February 25, 2011, CEBECO I filed its "Formal Offer of Exhibits".

On March 14, 2011, CEBECO I filed its "Manifestation of Compliance".

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 3 of 23

On May 16, 2011, CEBECO I wrote the Commission requesting for partial approval of its Capital Expenditure Projects.

On December 7, 2012, CEBECO I filed its "Urgent Motion for Partial Approval".

On April 21, 2014, CEBECO I filed its "Urgent Motion for Decision".

On November 17, 2014, the Commission issued an Order admitting CEBECO I's "*Formal Offer of Exhibits*" and declaring the case submitted for resolution.

# DISCUSSION

CEBECO I sought the Commission's approval of the following capital projects:

| PARTICULARS  | PROPOSED COST<br>(PhP) |
|--|------------------------|
| Substation Projects  |                        |
| Installation of 10MVA Substation in Argao  | 40,530,000.00          |
| Installation of 10MVA Substation in Badian   | 40,530,000.00          |
| Subtransmission Line Projects  |                        |
| Acquisition of Subtransmission Asset from the National<br>Transmission Corporation (TRANSCO) through a<br>Consortium with VECO | 3,500,000.00           |
| Construction of 70.5 km 69kV subtransmission line from<br>Suba, Samboan to Bito-on, Dumanjug                                   | 248,705,300.00         |
| Primary Distribution Projects  |                        |
| Installation of Recloser along Barili Feeder   | 700,000.00             |
| Installation of Recloser along Dumanjug Feeder   | 700,000.00             |
| Installation of Recloser along Sibonga Feeder1   | 700,000.00             |
| Installation of Recloser along Sibonga Feeder2   | 700,000.00             |
| Installation of Recloser along Dalaguete Feeder1   | 700,000.00             |
| Installation of Recloser along Dalaguete Feeder3   | 700,000.00             |
| Installation of Recloser along Dalaguete Feeder4   | 700,000.00             |
| Installation of Recloser along Carcar 2, Feeder1   | 700,000.00             |
| Installation of Recloser along Samboan Feeder1   | 700,000.00             |
| Installation of Recloser along Samboan Feeder2   | 700,000.00             |
| Installation of Capacitors   | 2,958,000.00           |
| Installation of Line AVRs along the feeders  | 16,800,000.00          |
| Installation of 15kVA Distribution Transformers  | 7,518,456.29           |

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 4 of 23

| Installation of 25kVA Distribution Transformers           | 12,139,382.30  |
|---|----------------|
| Installation of 37.5kVA Distribution Transformers         | 9,938,230.85   |
| Installation of 50kVA Distribution Transformers           | 6,277,914.72   |
| Secondary Distribution Projects                           |                |
| Open Secondary Low Voltage Distribution Lines             | 38,744,627.60  |
| Under Built Low Voltage Distribution Lines                | 6,147,068.47   |
| Other Network Projects                                    |                |
| Customer Service Drops                                    | 37,750,648.70  |
| 60A KWh meter for Customer Metering Equipment             | 31,738,205.83  |
| 100A KWh meter for Customer Metering Equipment            | 23,590,397.06  |
| 3-phase KWh meter for Customer Metering Equipment         | 2,487,113.13   |
| Installation of Circuit Breaker for two (2) existing      | 27,244,054.00  |
| substations and replacement of AVR and Reclosers          |                |
| Replacement of 60A KWh meters                             | 3,405,843.00   |
| Replacement of 100A KWh meters                            | 2,537,866.80   |
| Replacement of KWh meters with infrared reading features  | 19,630,144.80  |
| Replacement of 3-phase KWh meters with Load Profiling     |                |
| features  | 1,413,132.46   |
| Replacement of aging poles with Concrete poles preferably | 12,896,709.70  |
| along 3-phase system                                      |                |
| Replacement of aging poles with Steel poles preferably    | 6,141,137.45   |
| along 3-phase system                                      |                |
| Rural Electrification Projects                            | 91,397,000.00  |
| Non-Network Projects                                      |                |
| Communication System Equipment (VHF Radio & Repeater      | 862,500.00     |
| System)   |                |
| Geographical Information System (hardware & software)     | 300,000.00     |
| Meter Reading, Billing Collection System (hardware &      | 7,438,000.00   |
| software)   |                |
| Management Information System                             | 400,000.00     |
| Tools, Instruments & Test Equipment                       | 29,235,260.20  |
| Vehicles  | 53,055,000.00  |
| Computers & Other Equipment                               | 2,809,400.00   |
| Buildings & Lots  | 37,238,537.56  |
| TOTAL Project Cost per Application (PhP)                  | 832,359,930.93 |

# OVERVIEW OF CEBECO I'S SYSTEM


CEBECO I serves the eighteen (18) southern municipalities of the Province of Cebu, namely: Barili, Dumanjug, Ronda, Alcantara, Moalboal, Badian, Alegria, Malabuyoc, Ginatilan, Samboan, Santander, Carcar, Sibonga, Argao, Dalaguete, Alcoy, Boljoon, and Oslob. It is being classified by the National Electrification Administration (NEA) as an *"Extra Large"* cooperative considering ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 5 of 23

that CEBECO I serves 366 barangays from the seventeen municipalities and one city in the southern part of the province with a total of 95,000 registered customers.

As of the year 2009, CEBECO I's distribution lines have already reached far flung areas and continued to provide electricity up to the sitio levels due to the fact that local government units and barangays have prioritized electrification projects through subsidies. CEBECO I had already accumulated a total of 6,000 km of lines including service drops. It has a total capacity of 43.75 MVA including privately owned substation situated in different locations.


CEBECO I also owns and operates three Mini-Hydro plants with a combined plant capacity of 1,720 KW which are separately located. These Mini-Hydro plants have been operating since the mideighties as voltage support during peak hours and are presently situated in the areas of Barili and Badian.

The supply of power is presently being distributed through 15 feeders in the entire franchise area of CEBECO I. The figure below shows that CEBECO I's distribution lines comprise of more than 50% secondary lines, 32% single phase primary lines, and 11% 3-phase primary lines:






As shown in the figure below, approximately 87% of the connected customers are composed of residential customers, 10% are commercial customers, while the remaining 3% comprises of street lights, large loads, industrial and public buildings:



On the other hand, the chart below indicates that majority of the revenue of CEBECO I comes from the residential consumers which is equivalent to 54% for the year 2009. The commercial type of customers which include small business establishments, resorts, sarisari stores and other similar businesses in the coverage area, contributed 26% of the entire energy sales. Meanwhile, public buildings such as local government owned buildings and complexes have begun to upgrade their facilities like putting up air-conditioning units and more lighting fixtures contributed 8% of the entire energy sales, large load consumers contributed 7%, industrial consumers contributed 3% and street lights contributed 2% of the entire energy sales.



The relationship of both the energy purchases and sales for the past seven (7) years is directly proportional as shown in the figure below. An abrupt increase on both energy purchases and sales were observed from years 2003 to 2005 but a slim increase, with an average growth of 3%, for both parameters was encountered for the


ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 7 of 23

years 2006 to 2009. Hotels, commercial establishments, provincial and city development plans, tourism industry are good indicators of additional demand for electrical energy:

|        | 120,000       |        |        |        |        | . <u>.</u> |         |         |
|--------|---------------|--------|--------|--------|--------|------------|---------|---------|
| Ē      | 100,000       |        |        |        |        |            |         |         |
| (HWM)  | 80,000        |        |        |        |        |            |         |         |
|        | 60,000        |        |        |        |        |            |         |         |
| Energy | 40,000        |        |        |        |        |            |         |         |
| ш      | 20,000        |        |        |        |        |            |         |         |
|        | -             | 2003   | 2004   | 2005   | 2006   | 2007       | 2008    | 2009    |
| ■ Ene  | rgy Generated | 5,989  | 6,814  | 4,541  | 5,156  | 4,868      | 6,242   | 5,778   |
| * Ene  | rgy Purchased | 74,942 | 81,887 | 91,427 | 95,838 | 102,747    | 102,945 | 108,575 |
| ×Ene   | rgy Sales     | 74,288 | 80,819 | 87,503 | 91,976 | 97,436     | 99,023  | 103,757 |

#### Historical Energy Purchased & Sales

CEBECO I sustained its distribution system loss at a single digit level for the last ten (10) years. But at present, it is already approaching the 10% level, as reflected in the graph below. CEBECO I has to determine the major contributor of the increase through technical simulations of the distribution system data in order to prioritize projects that will correspondingly address the increasing system loss:



••

# FORECASTING

To determine the optimal project for a particular scenario, it is imperative to have an accurate forecast of the future energy, future demand and future customers of an electric cooperative. This forecast will ensure that the prescribed solution will redound to the benefit of the consumers.

CEBECO I simulated several forecasting models to get an accurate forecast of its future energy, demand requirement and future customers. The table shows the summary of the forecast used by CEBECO I in its distribution development planning:

|                             |                 | Forecasting   |                                 | Valio | lity Tests     |                | Accuracy Test | Annual Averag | je Growth Rate                        |  |
|-----------------------------|-----------------|---|---------------------------------|-------|----------------|----------------|---------------|---------------|---------------------------------------|--|
|                             |                 | Model   | Adj. R <sup>2</sup> (>0.99/0.8) | t-s   | stat ( t  > 2) | p-value (<0.1) | MAPE (<5%)    | Historical    | Forecast                              |  |
|                             |                 |   |                                 | а     | 133.3104       | 1.899E-08      |               |               |                                       |  |
|                             | Residential     | $a + bt^2 - ct^{-1}$                                | 0.9962                          | b     | 466.9852       | 1.2616E-10     | 0.69%         | 5.64%         | 6.39%                                 |  |
| 6                           |                 |   |                                 | c     | 8.5835         | 0.001012       |               |               |                                       |  |
| itati                       |                 |   |                                 | а     | 99.2436        | 2.2553E-06     |               |               |                                       |  |
| sqn                         | 0               | nmercial a - bt <sup>2</sup> + ct +<br>d*ln(t)      | 0.0040                          | b     | 2.9677         | 0.059177       | 0.500/        | c 070/        | 0.000/                                |  |
| Energy Sales per Substation | Commercial      |   | 0.9910                          | c     | 7.4647         | 0.004978       | 0.53%         | 5.37%         | 2.69%                                 |  |
| s pe                        |                 |   |                                 | d     | 2.9165         | 0.061672       |               |               |                                       |  |
| ale                         |                 | 2   |                                 | а     | 13.7634        | 0.00016148     |               |               |                                       |  |
| ŝ                           | Public Building | a + bt <sup>2</sup> +<br>c*ln(t)                    | 0.9961                          | b     | 144.2597       | 1.3849E-08     | 2.56%         | 16.20%        | 9.01%                                 |  |
| erg                         |                 |   |                                 | c     | 13.2005        | 0.00019026     |               |               |                                       |  |
| Ĕ                           |                 | 3   |                                 | а     | 15.8728        | 1.80609E-05    |               |               |                                       |  |
|                             | Street Lights   | a + bt + ct <sup>3</sup><br>w/horizon               | 0.9932                          | b     | 6.1506         | 0.001651802    | 3.33%         | 7.63%         | 6.39%                                 |  |
|                             |                 | whonzon   |                                 | С     | 5.4024         | 0.002936515    |               |               |                                       |  |
|                             |                 |   |                                 | а     | 5.5143         | 0.001494799    |               |               |                                       |  |
|                             | Dumanjug        | a + b*ln(t) +<br>ct <sup>-1</sup>                   | 0.9910                          | b     | 27.8815        | 1.408E-07      | 2.55%         | 4.39%         | 3.03%                                 |  |
|                             |                 |   |                                 | С     | 9.8085         | 6.46628E-05    |               |               |                                       |  |
|                             |                 |   |                                 | а     | 63.8807        | 8.45236E-06    |               |               | · · · · · · · · · · · · · · · · · · · |  |
| tion                        | C               | a + b*ln(t)+<br>ct <sup>-3</sup> + dt <sup>-2</sup> | 0.0000                          | b     | 14.8626        | 0.000660933    | 0.36%         | 4.049/        | 0.649/                                |  |
| Demand per Substation       | Carcar 1        | ' ct <sup>-3</sup> + dt <sup>-2</sup>               | 0.9960                          | С.    | 5.5880         | 0.011317678    | 0.30%         | 1.01%         | 0.61%                                 |  |
| Sub                         |                 |   |                                 | d     | 6.4850         | 0.007443356    |               |               |                                       |  |
| ē                           |                 |   |                                 | а     | 363.5017       | 0.001751349    |               |               |                                       |  |
| р                           | Sibonga         | $a + bt + ct^{-1}$                                  | 0.9996                          | b     | 215.2007       | 0.00295824     | 0.09%         | 3.52%         | 2.87%                                 |  |
| nan                         |                 |   |                                 | С     | 43.2872        | 0.014704252    |               |               |                                       |  |
| Den                         | Dalaguete       | a + bt  | 0.9934                          | а     | 77.0155        | 4.82472E-06    | 0.54%         | 6.20%         | 5.06%                                 |  |
| _                           | Dalaguete       | atol  | 0.5554                          | b     | 24.7224        | 0.000145093    | 0.54 %        | 0.2078        | 3.0078                                |  |
|                             |                 |   |                                 | а     | 33.5220        | 4.69083E-08    |               |               |                                       |  |
|                             | Entire System   | $a + bt + ct^2$                                     | 0.9982                          | b     | 19.0873        | 1.33723E-06    | 1.67%         | 3.69%         | 2.93%                                 |  |
|                             |                 |   |                                 | c     | 11.6676        | 2.38901E-05    |               |               |                                       |  |
|                             |                 |   |                                 | а     | 10.7293        | 0.00173        |               |               |                                       |  |
| ass                         | Residential     | $a + bt^2 + ct^{-1}$                                | 0.9920                          | b     | 132.0250       | 0.00000958     | 0.64%         | 6.98%         | 7.56%                                 |  |
| ö                           |                 | + d*ln(t)   | 0.0020                          | c     | 2.3534         | 0.1            | 0.0470        | 0.0070        | 7.0070                                |  |
| per                         |                 |   |                                 | d     | 5.1291         | 0.0144         |               |               |                                       |  |
| of Customers per Class      |                 | $a + bt + ct^3$                                     |                                 | а     | 32.8571        | 4.90748E-07    |               |               |                                       |  |
| Ĕ                           | Commercial      | a + bt + ct<br>w/horizon                            | 0.9915                          | b     | 5.7093         | 0.002302895    | 2.05%         | 4.50%         | 5.20%                                 |  |
| ust                         |                 |   |                                 | c     | 4.6345         | 0.005660857    | ····          |               |                                       |  |
| Ū,                          | Public Building | a + bt  | 0.9980                          | а     | 295.4234       | 8.43E-12       | 0.38%         | 6.57%         | 4.42%                                 |  |
| 。<br>。                      |                 |   |                                 | b     | 348.8262       | 3.67E-12       |               |               |                                       |  |
| No.                         | Street Lights   | a + bt  | 0.9915                          | а     | 78.9104        | 6.19E-09       | 1.33%         | 4.50%         | 4.24%                                 |  |
|                             |                 | l   |                                 | b     | 56.0021        | 3.43E-08       |               |               |                                       |  |

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 9 of 23

CEBECO I used the econometric method in determining the forecasted energy purchase. Other forecast such as entire system energy sale, customer sales, substation demand, and number of customer per class were determined using polynomial trend method. The sales from industrial and large load class customers do not exhibit a good trend due to its seasonal nature, thus, no valid model was formulated. The sale of these customer classes, however, increases with respect to the total sale. This was resolved by utilizing the percentage weight of customer class sale from the last historical year.


The entire distribution system and substation's forecasted peak demand were derived from the forecasted energy purchase using the system's load factor. Said parameters are crucial in determining the projected percent loading of the substation and the entire system.

### PERFORMANCE ASSESSMENT

Evaluating the performance of a distribution network will provide a complete picture of the needs of an electric cooperative in formulating project ideas. CEBECO I identified and quantified these problems and categorized these requirements to address safety, capacity (including customer requirements), reliability improvements and system loss reduction.

#### Safety

CEBECO I determined some portions within the distribution system that needs serious action due to safety problems. Through short circuit analysis, CEBECO I identified the primary lines/feeders that would basically need corrective measures to ensure safety within the distribution system, namely: DumF1; DumF2; SibF1; SibF2; DalF1; DalF3; DalF4; SamF1; SamF2; and Car2F1. The said analysis, represented in the graph below, only shows that the existing protective devices installed within these lines may not be able to sense the minimum fault current if in case fault occurred within the system considering that the computed minimum fault current is lower than the existing protection setting of these devices. In order to correct this problem, the said lines need additional protective device that will sense the minimum fault current even at the farthest end of the line during fault:



### Capacity

The existing maximum capacity of CEBECO I is 56.25 MVA which comprises the merged capacities of its six (6) substations. Based on the forecasted demand, as shown in the table below, the loading percentage of the entire distribution system is still within the 70% criteria for capacity margin. Moreover, each substation is within the said margin even until year 2015.

One of the six (6) substations, which is the Sibonga Substation, is presently owned by NGCP. CEBECO I plans to pull-out from the said substation and construct its own substation:

| No.  | Substation | Rated MVA | Power  | Max. MVA | Max. MW  | Capacity    | Historical |        |        | Forecasted | 1      |        |
|------|------------|-----------|--------|----------|----------|-------------|------------|--------|--------|------------|--------|--------|
| INQ. | Substation | Capacity  | Factor | Capacity | Capacity | Parameters  | 2010       | 2011   | 2012   | 2013       | 2014   | 2015   |
| 4    | Dumanium   | 10.00     | 90%    | 12.50    | 11.25    | Demand (MW) | 7.79       | 6.52   | 6.55   | 7.31       | 7.52   | 7.72   |
| I    | Dumanjug   | 10.00     | 90%    | 12.50    | 11.25    | % Loading   | 69.24%     | 57.94% | 58.24% | 64.96%     | 66.81% | 68.58% |
| 2    | Caroor 1   | 5.00      | 90%    | 6.25     | 5.63     | Demand (MW) | 4.83       | 4.40   | 3.30   | 3.16       | 3.18   | 3.20   |
| 2    | Carcar 1   | 5.00      | 90%    | 0.20     | 5.03     | % Loading   | 85.78%     | 78.15% | 58.74% | 56.25%     | 56.52% | 56.80% |
| 3    | Ciberre    | 5.00      | 90%    | 6.25     | 5.63     | Demand (MW) | 4.26       | 4.35   | 3.02   | 3.41       | 3.51   | 3.60   |
| ა    | Sibonga    | 5.00      | 90%    | 0.20     | 5.65     | % Loading   | 75.64%     | 77.35% | 53.76% | 60.62%     | 62.40% | 64.04% |
| 4    | Deleguete  | 10.00     | 90%    | 12.50    | 11.25    | Demand (MW) | 7.85       | 6.95   | 6.22   | 5.94       | 6.23   | 6.53   |
| 4    | Dalaguete  | 10.00     | 90%    | 12.50    | 11.23    | % Loading   | 69.76%     | 61.80% | 55.25% | 52.76%     | 55.40% | 58.02% |
| ~    | Comboon    | 5.00      | 000/   | C 05     | 5.00     | Demand (MW) | N/A        | 1.42   | 3.23   | 3.60       | 3.75   | 3.91   |
| 5    | Samboan    | 5.00      | 90%    | 6.25     | 5.63     | % Loading   | N/A        | 25.24% | 57.35% | 63.91%     | 66.65% | 69.53% |
| ^    | 0          | 40.00     | 0001   | 40.50    | 44.05    | Demand (MW) | N/A        | 1.54   | 3.52   | 4.00       | 4.46   | 4.92   |
| 6    | Carcar 2   | 10.00     | 90%    | 12.50    | 11.25    | % Loading   | N/A        | 13.69% | 31.30% | 35.59%     | 39.64% | 43.74% |
|      | Entire     | 45.00     | 0.00/  | 50.05    | 50.00    | Demand (MW) | 28.51      | 27.62  | 28.53  | 29.39      | 30.22  | 31.01  |
|      | System     | 45.00     | 90%    | 56.25    | 50.63    | % Loading   | 56.32%     | 54.56% | 56.35% | 58.06%     | 59.69% | 61.25% |

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 11 of 23

### **Power Quality**

At present, customers in some areas within the franchise of CEBECO I are experiencing low voltage during peak-load condition. Some of the existing feeders are also experiencing problems in terms of voltage unbalance. The Philippine Distribution Code (PDC) provides that the voltage levels at the customer's connection point must be within ±10% of the nominal voltage level of 230 volts. Further, the maximum voltage unbalance at the customer's connection point shall not exceed 2.5% during normal operating conditions. Voltage unbalances are harmful to consumers using 3-phase motors. Excessive heat caused by circulating currents may be produced on these motors if voltage unbalances are high or beyond the allowable limit discussed above.

In compliance with the above-mentioned standards, CEBECO I has included in its application some projects intended to address the power quality issues of the distribution system. The table below shows the forecasted voltage profile in per unit values and maximum voltage unbalance percentage of each feeder:

| No. | Substation | Feeder | V      | oltage Va | riation (p.u | ı.)    |       | Max. Ur | balance |       |
|-----|------------|--------|--------|-----------|--------------|--------|-------|---------|---------|-------|
| NO. | Substation | Name   | 2011   | 2012      | 2013         | 2014   | 2011  | 2012    | 2013    | 2014  |
| 4   | Dumenium   | DumF1  | 0.9296 | 0.9318    | 0.9406       | 0.8913 | 6.11% | 3.28%   | 2.68%   | 2.42% |
| 1   | Dumanjug   | DumF2  | 0.9000 | 0.9173    | 0.9295       | 0.8901 | 7.29% | 4.01%   | 2.41%   | 2.52% |
| 2   | Correct 1  | Car1F1 | 0.9013 | 0.9183    | 0.9367       | 0.9183 | 0.20% | 0.85%   | 1.83%   | 1.86% |
| 2   | Carcar 1   | Car1F2 | 0.9409 | 0.9477    | 0.8828       | 0.9302 | 0.31% | 1.73%   | 1.68%   | 2.09% |
|     | 3 Sibonga  | SibF1  | 0.9000 | 0.9283    | 0.9378       | 0.9361 | 3.54% | 2.38%   | 2.43%   | 2.35% |
| 3   |            | SibF2  | 0.8905 | 0.8397    | 0.9256       | 0.9308 | 5.28% | 4.98%   | 2.49%   | 2.38% |
|     |            | SibF3  | 0.9486 | 0.9527    | 0.9868       | 0.9853 | 1.17% | 1.74%   | 1.93%   | 2.38% |
|     |            | DalF1  | 0.9008 | 0.8862    | 0.9474       | 0.9517 | 4.34% | 3.28%   | 2.41%   | 2.40% |
|     | Deleguete  | DalF2  | 0.9761 | 0.9794    | 0.9801       | 0.9783 | 0.41% | 1.33%   | 1.92%   | 1.89% |
| 4   | Dalaguete  | DalF3  | 0.8823 | 0.9474    | 0.9418       | 0.9635 | 4.39% | 2.44%   | 2.30%   | 2.51% |
|     |            | DalF4  | 0.8787 | 0.9278    | 0.9307       | 0.9481 | 5.70% | 2.95%   | 2.35%   | 2.38% |
| 5   | Sambaan    | SamF1  | 0.9774 | 0.9129    | 0.9015       | 0.8727 | 1.75% | 1.98%   | 2.25%   | 2.25% |
| 5   | Samboan    | SamF2  | 0.9374 | 0.9120    | 0.8641       | 0.9188 | 1.82% | 2.06%   | 2.79%   | 2.38% |
| 6   | C          | Car2F1 | 0.8401 | 0.8836    | 0.9579       | 0.9628 | 3.84% | 3.04%   | 2.31%   | 2.31% |
| 6   | Carcar 2   | Car2F2 | 0.9359 | 0.9563    | 0.9494       | 0.9512 | 0.76% | 1.38%   | 2.04%   | 2.34% |

Note: Bold & Italic values are voltage values below the required minimum voltage level.

# System Efficiency

At the end of year 2009, the entire system loss of CEBECO I is **9.27%** which is within the 13% system loss cap for electric cooperatives. The said system loss comprises of technical loss (6.40%) and non-technical loss (2.86%). The data depicts that the technical losses contributed to the biggest share among the segregated losses, thus, CEBECO I included in the application some

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 12 of 23

projects that will improve the efficiency of the distribution system. Summary of the technical system loss being experienced in each feeder is shown in the table below:

| N   | Cubatatian | ConderName    | Historical |        | Foreca | asted  |        |
|-----|------------|---------------|------------|--------|--------|--------|--------|
| No. | Substation | Feeder Name   | 2010       | 2011   | 2012   | 2013   | 2014   |
| 4   | Querentium | DumF1         | 10.93%     | 6.93%  | 6.84%  | 6.84%  | 6.85%  |
| 1   | Dumanjug   | DumF2         | 16.19%     | 11.26% | 10.93% | 10.86% | 10.75% |
|     | 0          | Car1F1        | 9.04%      | 2.47%  | 2.47%  | 2.32%  | 2.26%  |
| 2   | 2 Carcar 1 | Car1F2        | 2.48%      | 2.32%  | 2.32%  | 2.21%  | 2.16%  |
|     |            | SibF1         | 5.07%      | 5.31%  | 5.31%  | 5.32%  | 5.35%  |
| 3   | Sibonga    | SibF2         | 7.60%      | 7.50%  | 7.50%  | 7.46%  | 7.76%  |
|     |            | SibF3         | 2.29%      | 2.27%  | 2.27%  | 2.45%  | 2.45%  |
|     |            | DalF1         | 12.50%     | 8.11%  | 8.08%  | 8.06%  | 8.29%  |
|     | Delessete  | DalF2         | 4.87%      | 4.53%  | 4.40%  | 4.29%  | 4.19%  |
| 4   | Dalaguete  | DalF3         | 11.41%     | 12.60% | 12.86% | 12.51% | 12.71% |
|     |            | DalF4         | 9.09%      | 8.39%  | 8.37%  | 8.36%  | 8.37%  |
|     | Combine    | SamF1         | N/A        | 4.95%  | 5.14%  | 3.75%  | 3.80%  |
| 5   | Samboan    | SamF2         | N/A        | 9.79%  | 9.79%  | 9.73%  | 11.11% |
| ~   | 0          | Car2F1        | N/A        | 3.45%  | 3.49%  | 3.38%  | 3.41%  |
| 6   | Carcar 2   | Car2F2        | N/A        | 2.77%  | 2.73%  | 2.69%  | 2.66%  |
|     |            | Entire System | 8.32%      | 6.18%  | 6.17%  | 6.02%  | 6.14%  |

# Reliability

The reliability performance of CEBECO I is being measured through indices namely, the System Average Interruption Frequency Index (SAIFI) and the System Average Interruption Duration Index (SAIDI). These indices are required as reliability indicators in the Electric Cooperatives Distribution Utility Planning Manual (ECDUPM) of which its value shall not exceed the interim criteria for SAIFI at 20 customer-interruptions per customer-year and for SAIDI at 45 hours per customer-year. CEBECO I's entire reliability performance index for SAIFI and SAIDI for the year 2009 are 11.40 and 21.48, respectively. These values are within the above-mentioned criteria. However, based on the reliability monitoring per feeder, there are some feeders that require improvement, as shown in the table below:

| No. | Substation | Feeder Name | SAIFI | SAIDI | MAIFI |
|-----|------------|-------------|-------|-------|-------|
| 1   | Dumenius   | DumF1       | 11.36 | 23.65 | -     |
| 1   | Dumanjug   | DumF2       | 23.61 | 40.90 | -     |
| 2   | Carcar 1   | Car1F1      | 10.15 | 20.39 | -     |
| 2   |            | Car1F2      | 11.79 | 35.39 | -     |
| ,   |            | SibF1       | 6.51  | 6.16  | -     |
| 3   | Sibonga    | SibF2       | 12.49 | 8.99  | -     |
|     |            | SibF3       | 10.78 | 32.45 | -     |
|     |            | DalF1       | 20.55 | 39.96 | 0.01  |
| 4   | Deleguete  | DalF2       | 1.62  | 1.77  | -     |
| 4   | Dalaguete  | DalF3       | 7.32  | 7.42  | -     |
|     |            | DalF4       | 9.23  | 19.15 | -     |
| 5   | Samboan    | SamF1       | 0.00  | 0.00  | -     |

# ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 13 of 23

|              |                   | SamF2  | 0.00 | 0.00  | -     |
|--------------|-------------------|--------|------|-------|-------|
| 6            | 6 Carcar 2        | Car2F1 | 0.00 | 0.00  | -     |
| <sup>b</sup> |                   | Car2F2 | 0.00 | 0.00  | -     |
|              | Entire System     |        |      | 21.48 | 0.01  |
|              | NGCP/Power Supply |        |      | 3.558 | 0.081 |

Note: Bold & Italic values are reliability indicators which exceeded the required maximum limit.

CEBECO I identified the main factors for the unreliability of these feeders which is the over-extended feeders with deficiency in protection equipment or disconnect switches. The existing subtransmission line's configuration and condition also contributed to the entire system's reliability issue. To address this problem, CEBECO I has included some reliability projects in the application.

# **Rural Electrification**

There are still several barangays within the franchise area of CEBECO I that needs to be energized. Since it is CEBECO I's mandate to provide rural electrification, the detailed plan in energizing the remaining barangays and sitios were conscientiously prepared and included in the CAPEX application.

# **PROJECT EVALUATION**

As provided in the ECDUPM, the power system model or electric circuits used to assess the distribution system's performance should be modified to reflect the proposed projects or solutions. Likewise, the conduct of appropriate technical analysis is necessary in order to predict the performance of the distribution system.

CEBECO I provided several alternative projects for each quantified problems and ranked the technically feasible projects in terms of technical effectiveness. Projects that were considered technically feasible were subjected to economic evaluation, wherein, the project that presented the least cost was selected.

Upon evaluation of all the proposed projects, the Commission determined that out of the forty-two (42) proposed capital projects of CEBECO I, thirty-six (36) projects are approved, twenty (20) of which have been revised as to costs. On the other hand, the Commission excludes one (1) project from the RFSC expense (as it should be realigned to "Other Revenue Income") and the remaining five (5) projects are deferred.

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 14 of 23

Accordingly, the proposed estimated total CAPEX cost, amounting to Eight Hundred Thirty-Two Million Three Hundred Fifty-Nine Thousand Nine Hundred Thirty and 93/100 Pesos (PhP832,359,930.93), should be reduced to Three Hundred Fifty-Four Million Eight Hundred Eighty-Six Thousand Eight Hundred Five and 84/100 Pesos (PhP354,886,805.84) only.

The summary of the projects with modification is shown in the table below:

|     |   | Project C      | ost (PhP)     | Commission's                          | Baanan   |
|-----|---|----------------|---------------|---------------------------------------|--|
| No. | Project Name  | Proposed       | Recommended   | Action                                | Reason   |
|     | Substation Projects   |                |               |                                       |  |
| 1   | Installation of 10MVA Substation in Argao   | 40,530,000.00  | -             | Deferment                             | Not least cost   |
| 2   | Installation of 10MVA Substation in Badian  | 40,530,000.00  | -             | Deferment                             | Lack of technical<br>justification                               |
|     | Subtransmission Line Projects   |                |               |                                       |  |
| 3   | Acquisition of subtransmission Asset from TransCo<br>through a Consortium with VECO       | 3,500,000.00   | · _           | Re-aligned to Other<br>Revenue Income | The proposed<br>asset is not a<br>capital expenditure<br>project |
| 4   | Construction of 70.5 km 69kV subtransmission line from Suba, Samboan to Bito-on, Dumanjug | 248,705,300.00 | -             | Deferment                             | B/C is less than 1   |
|     | Secondary Distribution Projects   |                |               |                                       |  |
| 15  | Installation of Capacitors  | 2,958,000.00   | 1,901,849.32  | Cost Revision                         | Revised unit cost and qty.                                       |
| 16  | Installation of Line AVRs along the feeders   | 16,800,000.00  | 9,600,000.00  | Cost Revision                         | Revised unit cost<br>and qty.                                    |
| 17  | Installation of 15kVA Distribution Transformers   | 7,518,456.29   | 4,472,874.75  | Cost Revision                         | Revised unit cost<br>and qty.                                    |
| 18  | Installation of 25kVA Distribution Transformers   | 12,139,382.30  | 7,351,100.00  | Cost Revision                         | Revised unit cost<br>and qty.                                    |
| 19  | Installation of 37.5kVA Distribution Transformers   | 9,938,230.85   | 5,762,487.00  | Cost Revision                         | Revised unit cost<br>and qty.<br>Revised unit cost               |
| 20  | Installation of 50kVA Distribution Transformers   | 6,277,914.72   | 3,975,660.00  | Cost Revision                         | and qty.<br>Revised unit cost                                    |
| 21  | Open Secondary Low Voltage Distribution Lines   | 38,744,627.60  | 19,823,782.32 | Cost Revision                         | and qty.   |
| 22  | Under Built Low Voltage Distribution Lines  | 6,147,068.47   | 3,270,438.19  | Cost Revision                         | Revised unit cost<br>and qty.                                    |
|     | Other Network Projects  |                |               |                                       |  |
| 23  | Customer Service Drops  | 37,750,648.70  | 26,350,484.60 | Cost Revision                         | Revised unit cost  |
| 24  | 60A KWh meter for Customer Metering Equipment   | 31,738,205.83  | 19,583,394.84 | Cost Revision                         | Revised unit cost  |
| 25  | 100A KWh meter for Customer Metering Equipment  | 23,590,397.06  | 22,851,280.89 | Cost Revision                         | Revised unit cost  |
| 26  | 3-phase KWh meter for Customer Metering Equipment   | 2,487,113.13   | -             | Deferment                             | Lack of technical<br>justification                               |
| 28  | Replacement of 60A KWh meters   | 3,405,843.00   | 2,101,403.00  | Cost Revision                         | Revised unit cost<br>and qty.                                    |
| 29  | Replacement of 100A KWh meters  | 2,537,866.80   | 2,405,566.80  | Cost Revision                         | Revised unit cost  |
| 30  | Replacement of KWh meters with infrared reading features                                  | 19,630,144.80  | 18,748,144.80 | Cost Revision                         | Revised unit cost  |
| 31  | Replacement of 3-phase KWh meters with Load<br>Profiling features                         | 1,413,132.46   | 700,549.78    | Cost Revision                         | Revised unit cost  |
| 32  | Replacement of aging poles with Concrete poles<br>preferably along 3-phase system         | 12,896,709.70  | 7,563,284.40  | Cost Revision                         | Revised unit cost  |
| 33  | Replacement of aging poles with Steel poles preferably<br>along 3-phase system            | 6,141,137.45   | 4,106,943.25  | Cost Revision                         | Revised unit cost  |
|     | Non-network Projects  |                |               |                                       |  |
| 39  | Tools, Instruments & Test Equipment   | 29,235,260.20  | 24,368,260.20 | Cost Revision                         | Revised unit cost and qty.                                       |
| 40  | Vehicles  | 53,055,000.00  | -             | Deferment                             | Lack of technical<br>justification                               |
| 41  | Computers & Other Equipment   | 2,809,400.00   | 1,390,000.00  | Cost Revision                         | Revised unit cost<br>and qty.                                    |
| 42  | Buildings & Lots  | 37,238,537.56  | 33,917,747.70 | Cost Revision                         | Revised unit cost  |

#### CAPEX Projects with Modification

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 15 of 23

# COST ANALYSIS

The cost estimates used by CEBECO I in its capital expenditure projects were based on the prevailing market price with the assistance of its Professional Engineering Consultants subject to public, transparent and competitive biddings.

The Commission, on the other hand, re-assessed the cost estimates of each proposed projects in reference with the ERC Valuation Handbook provided in Resolution No. 17, Series of 2010, entitled "A Resolution Adopting the Valuation Handbook for the Optimized Depreciated Replacement Cost Valuation of System Fixed Assets of Privately Owned Distribution Utilities Operating Under Performance-Based Regulation (PBR)" and the latest NEA Price Index for the year 2012. The proposed cost estimates that exceeded the benchmark provided in the said ERC Valuation Handbook or the NEA price index were reduced while the estimated costs that are close to the said benchmarks were retained.

Comparison of the proposed estimated cost, the ERC Price Benchmark and the 2012 NEA Price Index are shown in the table below. The proposed costs and the NEA price benchmark were based only on the material costs while the ERC valuation already includes all the necessary cost in establishing and installing such equipment or materials:

| Project | Na  | <b>F</b> aulinment  | Creation                | 11   | Un                    | it Cost (PhP/ur  | nit)             | Adopted   |
|---------|-----|---|-------------------------|------|-----------------------|------------------|------------------|-----------|
| No.     | No. | Equipment   | Specification           | Unit | Proposed <sup>1</sup> | ERC <sup>2</sup> | NEA <sup>2</sup> | Unit Cost |
|         | 1   | Power Transformer   | 10MVA                   | No.  | 12,361,734.00         | -                | 11,676,151.48    | NEA       |
|         | 2   | Conductors  | ACSR 336.4 MCM          | km   | 3,900,000.00          | -                | 106,270.00       | NEA       |
|         | 3   | Poles   | Concrete, 65 ft.        | No.  | -                     | -                | 72,009.60        | NEA       |
|         | 4   | Power Circuit Breaker   | 69kV, substation        | No.  | -                     | -                | 3,169,956.28     | NEA       |
|         | 5   | Potential Transformer   | 69kV, substation        | No.  | -                     | •                | 293,780.15       | NEA       |
|         | 6   | Current Transformer   | 69kV, substation        | No.  | -                     | -                | 275,377.12       | NEA       |
|         | 7   | Surge Arrester  | 69kV, substation        | No.  | -                     | -                | 58,414.95        | NEA       |
| 1&2     | 8   | Disconnect Switch   | 69kV, substation        | No.  | -                     | -                | 440,904.39       | NEA       |
|         | 9   | Power Circuit Breaker   | 15kV, substation        | No.  | -                     | -                | 1,252,986.90     | NEA       |
|         | 10  | Potential Transformer (PT)                                    | 15kV, substation        | No.  | -                     | -                | 71,194.30        | NEA       |
|         | 11  | Current Transformer (CT)                                      | 15kV, substation        | No.  | -                     | -                | 58,891.15        | NEA       |
|         | 12  | Surge Arrester, 15kV  | 15kV, substation        | No.  | -                     | -                | 26,745.40        | NEA       |
|         | 13  | Disconnect Switch, 15kV                                       | 15kV, substation        | No.  | -                     | -                | 16,284.16        | NEA       |
|         | 14  | Metering Equipment, Switchgear,<br>Protection & Control Panel | 69kV & 15kV, substation | No.  | -                     | -                | 2,356,644.64     | NEA       |
|         | 15  | Cable & other Accessories                                     | 15kV, substation        | No.  | -                     | -                | 17,022.50        | NEA       |
|         | 16  | Conductor   | 336.4 MCM ACSR          | km   | 123,489.79            | -                | -                | Proposed  |
| 4       | 17  | Pole  | 65 ft. concrete         | No.  | 112,263.44            | -                | -                | Proposed  |
| 4       | 18  | Power Circuit Breaker   | 69kV                    | No.  | 1,631,538.46          | -                | -                | Proposed  |
|         | 19  | Disconnect Switch   | Air Break, 69kV         | No.  | 1,090,384.62          | -                | -                | Proposed  |
| 5 to 14 | 20  | Automatic Recloser  | Vacuum, 630A            | No.  | 700,000.00            | 805,400.00       | -                | Proposed  |

<sup>&</sup>lt;sup>1</sup> The proposed unit cost does not include contingency rate factors and VAT

<sup>&</sup>lt;sup>2</sup> The ERC and NEA price benchmarks already includes contingency rate factors and VAT

# ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 16 of 23

| 45       | 21 | Capacitors                        | 50kVAR                              | No. | 35,000.00    | 35,400.00    | 12,465.46  | NEA      |
|----------|----|-----------------------------------|-------------------------------------|-----|--------------|--------------|------------|----------|
| 15       | 22 | Hanger                            | Cluster Type                        | No. | 5,000.00     | -            | 2,400.00   | NEA      |
| 4.0      | 23 | Automatic Voltage Regulator (AVR) | 167kVA                              | No. | 1,050,000.00 | -            | -          | Proposed |
| 16       | 24 | Automatic Voltage Regulator (AVR) | 333kVA                              | No. | 1,330,000.00 | -            |            | Proposed |
|          | 25 | Distribution Transformer          | 15kVA                               | No. | 80,843.62    | 75,000.00    | 59,638.33  | NEA      |
|          | 26 | Distribution Transformer          | 25kVA                               | No. | 102,011.62   | 95,000.00    | 77,380.00  | NEA      |
| 17 to 20 | 27 | Distribution Transformer          | 37.5kVA                             | No. | 127,413.22   | 107,000.00   | 94,467.00  | NEA      |
|          | 28 | Distribution Transformer          | 50kVA                               | No. | 139,509.22   | 124,000.00   | 110,435.00 | NEA      |
|          | 29 | Conductor                         | #1/0 AWG Bare ACSR                  | km  | 45,885.00    | 52,200.00    | 30,140.00  | NEA      |
| 21 & 22  | 30 | Poles                             | Steel, 30 ft.                       | No. | 9,879.22     | 16,100.00    | 10,204.05  | NEA      |
|          | 31 | Conductor                         | ACSR #6 TW                          | km  | 24,249.12    | 27,000.00    | 20,770.00  | NEA      |
| 23       | 32 | Compression Connector             | #6-#1/0 ACSR run to #6-<br>#2       | No. | 50.78        | -            | 39.35      | NEA      |
| 24 & 28  | 33 | KWh Meter                         | Class 10, 10/60A, 240V              | No. | 1,216.87     | -            | 818.57     | NEA      |
| 25 & 29  | 34 | KWh meter                         | Class 100, 15/100A, 240V            | No. | 1,581.72     | 2,300.00     | 1,768.69   | Proposed |
| 26 & 30  | 35 | KWh meter                         | Electronic 3-phase,<br>50A,120-480V | No. | 56,150.51    | 35,500.00    | 28,000.00  | NEA      |
|          | 36 | Automatic Voltage Regulator (AVR) | 167kVA, 1-ph, 7.62kV                | No. | 1,210,333.33 | -            |            | Proposed |
|          | 37 | AVR Control                       | Universal, digital                  | No. | 266,666.67   | -            | -          | Proposed |
|          | 38 | Power Circuit Breaker             | 69kV, 1-ph                          | No. | 1,950,180.00 | -            |            | Proposed |
| 27       | 39 | Current Transformer               | 69kV,1-phase, CT<br>substation      | No. | 870,000.00   | -            | -          | Proposed |
|          | 40 | Potential Transformer             | 69kV,1-phase, PT<br>substation      | No. | 750,000.00   | -            | -          | Proposed |
| 31       | 41 | KWh meter                         | Electronic 1-ph, 15A, 240V          | No. | 1,852.82     | 2,200.00     | -          | Proposed |
|          | 42 | Pole                              | 35 ft. concrete                     | No. | 21,168.00    | 18,000.00    | 12,303.89  | NEA      |
|          | 43 | Pole                              | 40 ft. concrete                     | No. | 25,872.00    | 21,500.00    | 19,622.00  | NEA      |
| 32       | 44 | Pole                              | 45 ft. concrete                     | No. | 31,620.29    | 27,700.00    | 20,420.75  | NEA      |
|          | 45 | Pole                              | 50 ft. concrete                     | No. | 33,122.17    | 37,300.00    | 24,522.32  | NEA      |
|          | 46 | Pole                              | 55 ft. concrete                     | No. | 38,205.89    | 43,000.00    | 26,843.44  | NEA      |
|          | 47 | Pole                              | 30 ft. steel                        | No. | 11,617.96    | 16,100.00    | 10,204.05  | NÉA      |
| 33       | 48 | Pole                              | 35 ft. steel                        | No. | 18,816.00    | 19,300.00    | 12,716.92  | NEA      |
|          | 49 | Pole                              | 40 ft. steel                        | No. | 20,456.81    | 27,800.00    | 17,395.25  | NEA      |
|          | 50 | Carcar Area Office                | 127.31 sq. m.                       | No. | 4,350,057.00 | 1,289,715.57 | -<br>-     | ERC      |
|          | 51 | Carcar, Cebu                      | 3,000 sq. m.                        | No. | 5,000.00     | -            |            | Proposed |
|          | 52 | Argao Area Office                 | 127.31 sq. m.                       | No. | 1,289,715.57 | 1,289,715.57 | -          | ERC      |
| 40       | 53 | Covered Storage Building          | 150 sq. m.                          | No. | 1,310,307.57 | -            | -          | Proposed |
| 42       | 54 | Ginatilan Area Office             | 127.31 sq. m.                       | No. | 1,550,164.00 | 1,289,715.57 |            | ERC      |
|          | 55 | Moalboal, Cebu                    | 2,000 sq. m.                        | No. | 3,000.00     | -            |            | Proposed |
|          | 56 | Mulit-purpose Building            | 960 sq. m.                          | No. | 6,448,577.85 | -            |            | Proposed |
|          | 57 | Moalboal Area Office              | 127.31 sg. m.                       | No. | 1,289,715.57 | 1,289,715.57 | -          | ERC      |

It can be observed that most of the proposed material costs are close if not lesser than the above-mentioned price benchmarks. However, the Commission reduced the rate factors, such as the contingency rate factor, that were used by CEBECO I as an additional cost in determining the project costs. These factors are adopted in order to cushion the effect of price differences in the different regions due to handling of such materials or equipment. The Commission only accepted an allocation cost spurred by these factors amounting to 5% of the material cost.

# **PROJECT DESIGN**

The acquisition of major equipment such as the distribution transformers are required to address the forecasted load growth while equipment such as circuit breakers, reclosers, disconnect switches,

•

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 17 of 23

fuse cut-outs and surge arresters are mainly for the protection and safety of the entire distribution system. Meanwhile, the acquisition of equipment for the substation control rooms and the acquisition of engineering hardware and software programs are appropriate in order to monitor the quality and reliability of the system and other parameters needed to provide efficient and reliable power service to the customers of CEBECO I. These parameters are also in compliance with the provisions of the Philippine Distribution Code (PDC).

Further, the design of the proposed electrical projects complies with the standards of the NEA Engineering Bulletin and the Philippine Electrical Code.

# PROJECT STATUS

The entire proposed capital projects have not yet been implemented as manifested during the initial hearing of this case and as verified by the Commission. CEBECO I submitted a report regarding the revised implementation of its capital expenditure projects considering that 2011 to 2013 had already lapsed.

# AUTHORITY TO SECURE LOAN

As per application, CEBECO I intends to avail of loans from the NEA to finance its entire network and other network capital expenditure projects, with a fixed annual interest rate of 10%, payable within 10 years, subject to the present lending policies on loan approval and releases. The probable mode of payment shall be in quarterly basis. CEBECO I shall then use its previous collection and the projected revenues from the Reinvestment Fund for Sustainable Capital Expenditures (RFSC) to remit the annual amortization gained from availing such loans and also to finance the entire non-network capital expenditure projects.

Funding for annual requirement is to be given on hand before the periodic implementation of the project. To be conservative and prudent, CEBECO I proposed a staggered scheme on the NEA loan releases. The release shall be on an annual basis as projected in the annual implementation of the projects (no drawdown yet). Considering the cost modifications and the revised schedule of capital expenditure projects, the projected annual NEA loan amount and the amount incurred from the RFSC collections intended for the non-network projects shall be as follows:

| Financiers based on |               | Projected Loan Amount (PhP) |               |               |               |                |  |  |  |
|---------------------|---------------|-----------------------------|---------------|---------------|---------------|----------------|--|--|--|
| the Application     | 2014          | 2015                        | 2016          | 2017          | 2018          | Total (PhP)    |  |  |  |
| NEA                 | 28,393,542.15 | 55,551,688.60               | 43,672,482.60 | 37,286,591.74 | 29,908,992.85 | 194,813,297.94 |  |  |  |
| RFSC                | 26,609,851.57 | 6,367,009.37                | 10,731,150.37 | 12,774,459.37 | 12,194,037.22 | 68,676,507.90  |  |  |  |
| Grand Total         | 55,003,393.72 | 61,918,697.97               | 54,403,632.97 | 50,061,051.11 | 42,103,030.07 | 263,489,805.84 |  |  |  |

The Commission made a simulation on the probable effect on CEBECO I's existing RFSC rate if it opts not to avail of any loan and will utilize its RFSC in financing the entire capital expenditure projects. The Commission further conducted several simulations to test the indicative effect on CEBECO I's existing RFSC rate using several financing scheme for the capital expense:

|  | 2014            | 2015            | 2016             | 2017             | 2018             | Entire 5-years   |
|--|-----------------|-----------------|------------------|------------------|------------------|------------------|
| Energy Sales Forecast, KWh                         | 114,658,910     | 120,302,540     | 126,392,250      | 132,933,210      | 139,929,220      | 634,216,130      |
| Approved RFSC Rate, PhP/KWh                        | 0.2904          | 0.2904          | 0.2904           | 0.2904           | 0.2904           | 0.2904           |
| Cash balance beginning, PhP,<br>excess/(shortfall) | 10,953,279.00   | (30,898,531.12) | (78,144,818.33)  | (116,051,225.76) | (147,640,461.54) | 10,953,279.00    |
| CASH INFLOWS                                       | ]               |                 |                  |                  |                  |                  |
| Current year RFSC Collection, PhP                  | 33,296,947.46   | 34,935,857.62   | 36,704,309.40    | 38,603,804.18    | 40,635,445.49    | 184,176,364.15   |
| 50% income on leased properties,<br>PhP            | 3,103,603.00    | 3,103,603.00    | 3,103,603.00     | 3,103,603.00     | 3,103,603.00     | 15,518,015.00    |
| Total Cash Inflows, PhP                            | 36,400,550.46   | 38,039,460.62   | 39,807,912.40    | 41,707,407.18    | 43,739,048.49    | 199,694,379.15   |
| Available cash for disbursement, PhP               | 47,353,829.46   | 7,140,929.50    | (38,336,905.93)  | (74,343,818.57)  | (103,901,413.06) | 210,647,658.15   |
| CASH OUTFLOWS                                      | ]               |                 |                  |                  |                  |                  |
| CAPEX Requirement, PhP                             | 55,003,393.72   | 61,918,697.97   | 54,403,632.97    | 50,061,051.11    | 42,103,030.07    | 263,489,805.84   |
| Previous Loan Amortization, PhP                    | 22,757,368.86   | 22,757,368.86   | 22,757,368.86    | 22,757,368.86    | 22,757,368.86    | 113,786,844.30   |
| ERC Permit Fees, PhP                               | 491,598.00      | 609,681.00      | 553,318.00       | 478,223.00       | 528,833.00       | 2,661,653.00     |
| Total Cash Outflows, PhP                           | 78,252,360.58   | 85,285,747.83   | 77,714,319.83    | 73,296,642.97    | 65,389,231.93    | 379,938,303.14   |
| Cash balance ending, PhP, excess/(shortfall)       | (30,898,531.12) | (78,144,818.33) | (116,051,225.76) | (147,640,461.54) | (169,290,644.99) | (169,290,644.99) |
| Rate Impact on RFSC, PhP/KWh, excess/(shortfall)   | (0.2695)        | (0.6496)        | (0.9182)         | (1.1106)         | (1.2098)         | (0.2669)         |

The results of the simulations showed that the revenues derived from CEBECO I's existing RFSC rate are not sufficient to finance the entire capital expenditure projects. There is a need to increase the RFSC rate by PhP0.2669/KWh if such financing scheme shall be pursued.

Based on the said simulations, CEBECO I's RFSC rate will be sufficient, provided that it shall avail of loans for the entire capital expenses.

Thus, CEBECO I is hereby directed to exert its best effort in negotiating for longer terms, lower interest rate, and reasonable loan amount in order to negate any possible increase in its RFSC rate without compromising the need of its distribution system and for the benefit of its consumers.

# After thorough evaluation, CEBECO I's prayer for authority to secure loan is hereby approved with the following modifications:

|   |               | Total (PhP)   |               |               |               |                |
|---|---------------|---------------|---------------|---------------|---------------|----------------|
| Approved Financiers                                   | 2014          | 2015          | 2016          | 2017          | 2018          |                |
| NEA / other banks with better loan terms & conditions | 55,003,393.72 | 61,918,697.97 | 54,403,632.97 | 50,061,051.11 | 42,103,030.07 | 263,489,805.84 |

The Commission believes that there will still be a reduction in the overall rate, due to improved efficiency, reliability (less ENS) and system loss reduction caused by the implementation of the proposed projects. The DSM component and the overall rate impact will still be subjected to further review in the rate adjustment application on the regulatory reset period of CEBECO I as indicated in the Tariff Glide Path (TGP) Guidelines.

The detailed discussion of the Commission's resolution of CEBECO I's proposed capital expenditures is embodied in a separate document attached as Annexes "A", "B", "C", and "D" and made as an integral part of this Decision.

A perusal of the evidence presented herein showed that the approval of CEBECO I's proposed five (5) year capital expenditure projects and authority to secure loan from the National Electrification Administration (NEA) is in accordance with the provisions of R.A. 9136, the Commission's "*Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects*", Section 20 (e)<sup>3</sup> of Commonwealth Act No. 146 (C.A. 146) or the "*Public Service Act*", as amended and will redound to the benefit of the consumers in terms of continuous, reliable and efficient power supply as mandated by R.A. 9136, or the Electric Power Industry Reform Act of 2001 (Section 2. Declaration of Policy – (b) "to ensure the quality, reliability, security and affordability of the supply of electric power").

<sup>&</sup>lt;sup>3</sup> "Sec. 20. Acts requiring the approval of the Commission. - Subject to established limitations and exceptions and saving provisions to the contrary, it shall be unlawful for any public service or for the owner, lessee or operator thereof, without the approval and authorization of the Commission previously had - Xxx

<sup>(</sup>e) Hereafter to issue any stock or stock certificates representing an increase of capital; or issue any share of stock without par value; or issue any bonds or other evidence of indebtedness payable in more than one year from the issuance thereof, provided that it shall be the duty of the Commission, after hearing, to approve any such issue maturing in more than one year from the date thereof, when satisfied that the same is to be made in accordance with law, and the purpose of such issue be approved by the Commission."

WHEREFORE, the foregoing premises considered, the application filed by the Cebu I Electric Cooperative, Inc. (CEBECO I) for approval of its proposed five (5) year capital expenditure projects and authority to secure loan from the National Electrification Administration (NEA) is hereby **APPROVED with MODIFICATION**, subject to the following conditions:

- The modified 5-year capital expenditure projects amounting to Three Hundred Fifty-Four Million Eight Hundred Eighty-Six Thousand Eight Hundred Five and 84/100 Pesos (PhP354,886,805.84) are APPROVED;
- 2. The following capital expenditure projects are DEFERRED which may be included in its next capital expenditure application with additional justification:
  - a. Installation of 10 MVA Substation in Argao;
  - b. Installation of 10 MVA Substation in Badian;
  - c. Construction of 70.5 km 69 kV Subtransmission Line from Suba, Samboan to Bito-on, Dumanjug;
  - d. 3-phase KWh meter for Customer Metering Equipment; and
  - e. Acquisition of vehicles.
- 3. The application to secure loan from NEA to finance its capital expenditure projects is APPROVED with modification, as provided below:

|  | Recommended Financiers                                |               | Total (PhP)   |               |               |               |                |
|--|---|---------------|---------------|---------------|---------------|---------------|----------------|
|  | Recommended Financiers                                | 2014          | 2015          | 2016          | 2017          | 2018          |                |
|  | NEA / other banks with better loan terms & conditions | 55,003,393.72 | 61,918,697.97 | 54,403,632.97 | 50,061,051.11 | 42,103,030.07 | 263,489,805.84 |

4. The acquisition of subtransmission asset from the National Transmission Corporation (TRANSCO) through a Consortium, as approved under ERC Case No. 2007-492 MC, should not be charged to its RFSC;

Relative thereto, CEBECO I is hereby directed to remit to the Commission, within fifteen (15) days from receipt hereof, a total permit fee in the amount of Two Million Six Hundred Sixty-One Thousand Six Hundred Fifty-Three Pesos (PhP2,661,653.00), computed as follows:

#### PhP354,886,805.84

#### ------ × PhP0.75 = PhP2,661,653.00

PhP100.00

# **Breakdown of Permit Fees**

| Year        | Project Cost (PhP) | Permit Fees (PhP) | Due Date                 |  |  |  |
|-------------|--------------------|-------------------|--------------------------|--|--|--|
|             |                    | -                 | Within fifteen (15) days |  |  |  |
| 2014        | 65,546,393.72      | 491,598.00        | from receipt hereof      |  |  |  |
| 2015        | 81,290,697.97      | 609,681.00        | December 15, 2015        |  |  |  |
| 2016        | 73,775,632.97      | 553,318.00        | December 15, 2016        |  |  |  |
| 2017        | 63,763,051.11      | 478,223.00        | December 15, 2017        |  |  |  |
| 2018        | 70,511,030.07      | 528,833.00        | December 15, 2018        |  |  |  |
| Total (PhP) | 354,886,805.84     | 2,661,653.00      | -                        |  |  |  |

Further, CEBECO I is hereby directed to: 1) submit a progress report with an indication of any variance in the implementation of the project and time schedule; 2) conduct a competitive bidding for the purchase of major materials in the implementation of the proposed project; and 3) exert best efforts in negotiating/refinancing its loan with reasonable term and lower interest rate.

#### SO ORDERED.

Pasig City, December 1, 2014.

NO. 2011-004 RC CEBECO I-DECISION

NAIDA G. CRUZ-DU Chairperson pu

ALFREDØ J. NON Commissioner

AP-TARUC Commissióner

JOSEFINA PATRICIA A. MAGPALE-ASIRIT Commissioner

# Copy Furnished:

- Atty. Alan C. Gaviola
   A.C. Gaviola Law Office
   Counsel for Applicant CEBECO I
   Rm. 203, 2/F Crown Plaza Bldg.,
   3<sup>rd</sup> Avenue, North Reclamation Area, Cebu City
- Mr. Marlou M. Rendon General Manager Cebu I Electric Cooperative, Inc. (CEBECO I) Bito-on, Dumanjug, Cebu
- Office of the Solicitor General (OSG)
   134 Amorsolo Street, Legaspi Village, City of Makati 1229
- 4. Commission on Audit (COA) Commonwealth Avenue, Quezon City 1121
- 5. Senate Committee on Energy GSIS Building, Roxas Boulevard, Pasay City 1300
- 6. House of Representatives Committee on Energy Batasan Hills, Quezon City 1126
- 7. The Office of the Governor Province of Cebu
- 8. The Office of the City Mayor City of Carcar, Cebu
- 9. The Office of the Municipal Mayor Sibonga, Cebu
- 10. The Office of the Municipal Mayor Argao, Cebu
- 11. The Office of the Municipal Mayor Dalaguete, Cebu
- 12. The Office of the Municipal Mayor Alcoy, Cebu

ERC Case No. 2011-004 RC DECISION/December 1, 2014 Page 23 of 23

- 13. The Office of the Municipal Mayor Boljoon, Cebu
- 14. The Office of the Municipal Mayor Oslob, Cebu
- **15.** The Office of the Municipal Mayor Santander, Cebu
- 16. The Office of the Municipal Mayor Samboan, Cebu
- **17.** The Office of the Municipal Mayor Ginatilan, Cebu
- **18. The Office of the Municipal Mayor** Malabuyoc, Cebu
- **19. The Office of the Municipal Mayor** Alegria, Cebu
- 20. The Office of the Municipal Mayor Badian, Cebu
- 21. The Office of the Municipal Mayor Moalboal, Cebu
- 22. The Office of the Municipal Mayor Alcantara, Cebu
- 23. The Office of the Municipal Mayor Ronda, Cebu
- 24. The Office of the Municipal Mayor Dumanjug, Cebu
- 25. The Office of the Municipal Mayor Barili, Cebu
- 26. Mr. Edgardo G. Lacson Office of the President Philippine Chamber of Commerce and Industry (PCCI) 3<sup>rd</sup> Floor, Chamber and Industry Plaza (CIP) 1030 Campus Avenue corner Park Avenue McKinley Town Center, Fort Bonifacio, Taguig City

# ANNEX A

# Proposed 5-year CAPEX Projects of CEBECO I

|     |   |               | Propos        | ed Project Cost | (PhP)                                  |                |                |
|-----|---|---------------|---------------|-----------------|--|----------------|----------------|
| No. | Project Name  | 2011          | 2012          | 2013            | 2014                                   | 2015           | Total (PhP)    |
|     | Substation Projects   |               |               |                 |  |                |                |
| 1   | Installation of 10MVA Substation in Argao   | -             | 40,530,000.00 |                 | -                                      | -              | 40,530,000.00  |
| 2   | Installation of 10MVA Substation in Badian  | -             | -             | -               | -                                      | 40,530,000.00  | 40,530,000.00  |
|     | Subtransmission Line Projects   |               |               |                 |  |                |                |
| 3   | Acquisition of subtransmission Asset from<br>TransCo through a Consortium with<br>VECO                      | 3,500,000.00  | -             | _               | -                                      | -              | 3,500,000.00   |
| 4   | Construction of 70.5 km 69kV<br>subtransmission line from Suba, Samboan<br>to Bito-on, Dumanjug             | -             | -             | -               | -                                      | 248,705,300.00 | 248,705,300.00 |
|     | Primary Distribution Projects   |               |               |                 |  |                |                |
| 5   | Installation of Recloser along Barili Feeder  | 700,000.00    | -             | -               | -                                      | -              | 700,000.00     |
| 6   | Installation of Recloser along Dumanjug<br>Feeder   | 700,000.00    | -             | -               | -                                      | -              | 700,000.00     |
| 7   | Installation of Recloser along Sibonga<br>Feeder1   | 700,000.00    | -             | -               | -                                      | -              | 700,000.00     |
| 8   | Installation of Recloser along Sibonga<br>Feeder2   | 700,000.00    | -             | -               | -                                      | -              | 700,000.00     |
| 9   | Installation of Recloser along Dalaguete<br>Feeder1   | 700,000.00    |               | -               | -                                      | -              | 700,000.00     |
| 10  | Installation of Recloser along Dalaguete<br>Feeder3   | 700,000.00    | -             | -               | -                                      | -              | 700,000.00     |
| 11  | Installation of Recloser along Dalaguete<br>Feeder4   | -             | -             | 700,000.00      | -                                      | -              | 700,000.00     |
| 12  | Installation of Recloser along Carcar 2<br>Feeder1  | 700,000.00    | -             | -               | -                                      | -              | 700,000.00     |
| 13  | Installation of Recloser along Samboan<br>Feeder1   | -             | -             | 700,000.00      | -                                      | -              | 700,000.00     |
| 14  | Installation of Recloser along Samboan<br>Feeder2   | 700,000.00    | -             | -               | -                                      | -              | 700,000.00     |
| 15  | Installation of Capacitors  | 845,000.00    | 845,000.00    | 423,000.00      | 845,000.00                             | -              | 2,958,000.00   |
| 16  | Installation of Line AVRs along the feeders   | 7,200,000.00  | 3,200,000.00  | 3,200,000.00    | 3,200,000.00                           | -              | 16,800,000.00  |
| 17  | Installation of 15kVA Distribution<br>Transformers  | 1,293,497.86  | 1,374,341.47  | 1,536,028.70    | 1,616,872.32                           | 1,697,715.94   | 7,518,456.29   |
| 18  | Installation of 25kVA Distribution<br>Transformers  | 2,040,232.32  | 2,244,255.55  | 2,448,278.78    | 2,652,302.02                           | 2,754,313.63   | 12,139,382.30  |
| 19  | Installation of 37.5kVA Distribution<br>Transformers  | 1,656,371.81  | 1,783,785.02  | 2,038,611.46    | 2,166,024.67                           | 2,293,437.89   | 9,938,230.85   |
| 20  | Installation of 50kVA Distribution<br>Transformers  | 1,116,073.73  | 1,116,073.73  | 1,255,582.94    | 1,395,092.16                           | 1,395,092.16   | 6,277,914.72   |
| r   | Secondary Distribution Projects   |               |               |                 |  | ГТ             |                |
| 21  | Open Secondary Low Voltage Distribution<br>Lines  | 6,632,580.23  | 7,178,121.89  | 7,737,914.86    | 8,308,512.27                           | 8,887,498.35   | 38,744,627.60  |
| 22  | Under Built Low Voltage Distribution Lines  | 1,052,298.79  | 1,138,852.26  | 1,227,666.79    | 1,318,195.50                           | 1,410,055.13   | 6,147,068.47   |
|     | Other Network Projects  |               |               |                 | ······································ | ·······        |                |
| 23  | Customer Service Drops  | 6,469,954.43  | 6,995,487.13  | 7,537,327.93    | 8,091,765.03                           | 8,656,114.18   | 37,750,648.70  |
| 24  | 60A KWh meter for Customer Metering<br>Equipment  | 5,424,643.07  | 5,873,705.07  | 6,336,702.16    | 6,810,462.65                           | 7,292,692.88   | 31,738,205.83  |
| 25  | 100A KWh meter for Customer Metering<br>Equipment   | 4,061,134.26  | 4,380,754.75  | 4,710,293.56    | 5,047,493.23                           | 5,390,721.26   | 23,590,397.06  |
| 26  | 3-phase KWh meter for Customer<br>Metering Equipment  | 395,677.09    | 452,202.39    | 508,727.69      | 565,252.98                             | 565,252.98     | 2,487,113.13   |
| 27  | Installation of Circuit Breaker for two (2)<br>existing substations and replacement of<br>AVR and Reclosers | 10,162,000.00 | 17,082,054.00 | -               | -                                      | -              | 27,244,054.00  |
| 28  | Replacement of 60A KWh meters   | 681,168.60    | 681,168.60    | 681,168.60      | 681,168.60                             | 681,168.60     | 3,405,843.00   |
| 29  | Replacement of 100A KWh meters  | 507,573.36    | 507,573.36    | 507,573.36      | 507,573.36                             | 507,573.36     | 2,537,866.80   |

| 30 | Replacement of KWh meters with infrared reading features                          | -              | 9,815,072.40   | -             | 9,815,072.40  | -              | 19,630,144.80  |
|----|---|----------------|----------------|---------------|---------------|----------------|----------------|
| 31 | Replacement of 3-phase KWh meters with<br>Load Profiling features                 | 282,626.49     | 282,626.49     | 282,626.49    | 282,626.49    | 282,626.49     | 1,413,132.46   |
| 32 | Replacement of aging poles with Concrete<br>poles preferably along 3-phase system | 2,579,341.94   | 2,579,341.94   | 2,579,341.94  | 2,579,341.94  | 2,579,341.94   | 12,896,709.70  |
| 33 | Replacement of aging poles with Steel<br>poles preferably along 3-phase system    | 1,228,227.49   | 1,228,227.49   | 1,228,227.49  | 1,228,227.49  | 1,228,227.49   | 6,141,137.45   |
| 34 | Rural Electrification Projects  | 10,543,000.00  | 19,372,000.00  | 19,372,000.00 | 13,702,000.00 | 28,408,000.00  | 91,397,000.00  |
|    | Non-network Projects  |                |                |               |               |                |                |
| 35 | Communication System Equipment (VHF<br>Radio & Repeater System)                   | 334,500.00     | 112,500.00     | 112,500.00    | 226,500.00    | 76,500.00      | 862,500.00     |
| 36 | Geographical Information System<br>(hardware & software)                          | 180,000.00     | -              | -             | 120,000.00    | -              | 300,000.00     |
| 37 | Meter Reading, Billing Collection System<br>(hardware & software)                 | 1,392,900.00   | 1,989,600.00   | 620,500.00    | 771,000.00    | 2,664,000.00   | 7,438,000.00   |
| 38 | Management Information System   | -              | -              | 400,000.00    | -             | -              | 400,000.00     |
| 39 | Tools, Instruments & Test Equipment   | 9,203,736.00   | 3,882,693.80   | 8,911,342.80  | 5,116,743.80  | 2,120,743.80   | 29,235,260.20  |
| 40 | Vehicles  | 13,170,000.00  | 9,050,000.00   | 15,705,000.00 | 10,080,000.00 | 5,050,000.00   | 53,055,000.00  |
| 41 | Computers & Other Equipment   | 600,000.00     | 530,850.00     | 530,850.00    | 575,850.00    | 571,850.00     | 2,809,400.00   |
| 42 | Buildings & Lots  | 19,350,057.00  | 1,289,715.57   | 1,310,307.57  | 7,550,164.00  | 7,738,293.42   | 37,238,537.56  |
|    | Grand Total (PhP)   | 117,502,594.47 | 145,516,002.92 | 92,601,573.13 | 95,253,240.91 | 381,486,519.50 | 832,359,930.93 |

# ANNEX B

# Revised Schedule of the 5-year CAPEX Projects of CEBECO I

.

|     | _ ·   |               | Propos        | sed Project Cost ( | PhP)         | I            |                |
|-----|---|---------------|---------------|--------------------|--------------|--------------|----------------|
| No. | Project Name  | 2014          | 2015          | 2016               | 2017         | 2018         | ,Total (PhP)   |
|     | Substation Projects   | <b>_</b>      |               |                    |              | I            |                |
| 1   | Installation of 10MVA Substation in Argao   | 40,530,000.00 | -             | -                  | -            | - [          | 40,530,000.00  |
| 2   | Installation of 10MVA Substation in Badian  | -             | 40,530,000.00 | -                  | -            | -            | 40,530,000.00  |
|     | Subtransmission Line Projects   |               |               | ·                  |              |              |                |
| 3   | Acquisition of subtransmission Asset from<br>TransCo through a Consortium with VECO                         | 3,500,000.00  | -             | -                  | -            | -            | 3,500,000.00   |
| 4   | Construction of 70.5 km 69kV<br>subtransmission line from Suba, Samboan<br>to Bito-on, Dumanjug             | -             | -             | 248,705,300.00     | -            | -            | 248,705,300.00 |
|     | Primary Distribution Projects   |               |               |                    |              |              |                |
| 5   | Installation of Recloser along Barili Feeder  | 700,000.00    |               | -                  | -            | -            | 700,000.00     |
| 6   | Installation of Recloser along Dumanjug Feeder  | 700,000.00    | -             | -                  | -            | -            | 700,000.00     |
| 7   | Installation of Recloser along Sibonga<br>Feeder1   | 700,000.00    | -             | -                  | -            | -            | 700,000.00     |
| 8   | Installation of Recloser along Sibonga<br>Feeder2   | 700,000.00    | -             | -                  | -            | -            | 700,000.00     |
| 9   | Installation of Recloser along Dalaguete<br>Feeder1   | 700,000.00    | -             | -                  | -            | -            | 700,000.00     |
| 10  | Installation of Recloser along Dalaguete<br>Feeder3   | 700,000.00    | -             | -                  | -            | -            | 700,000.00     |
| 11  | Installation of Recloser along Dalaguete<br>Feeder4   | -             | 700,000.00    | -                  | -            | -            | 700,000.00     |
| 12  | Installation of Recloser along Carcar 2<br>Feeder1  | 700,000.00    | -             | -                  | -            | -            | 700,000.00     |
| 13  | Installation of Recloser along Samboan<br>Feeder1   | -             | 700,000.00    | -                  | -            | -            | 700,000.00     |
| 14  | Installation of Recloser along Samboan<br>Feeder2   | 700,000.00    | -             | -                  | -            | -            | 700,000.00     |
| 15  | Installation of Capacitors  | -             | 845,000.00    | 845,000.00         | 423,000.00   | 845,000.00   | 2,958,000.00   |
| 16  | Installation of Line AVRs along the feeders   | -             | 16,800,000.00 | -                  | -            | -            | 16,800,000.00  |
| 17  | Installation of 15kVA Distribution<br>Transformers  | 1,293,497.86  | 1,374,341.47  | 1,536,028.70       | 1,616,872.32 | 1,697,715.94 | 7,518,456.29   |
| 18  | Installation of 25kVA Distribution<br>Transformers  | 2,040,232.32  | 2,244,255.55  | 2,448,278.78       | 2,652,302.02 | 2,754,313.63 | 12,139,382.30  |
| 19  | Installation of 37.5kVA Distribution<br>Transformers  | 1,656,371.81  | 1,783,785.02  | 2,038,611.46       | 2,166,024.67 | 2,293,437.89 | 9,938,230.85   |
| 20  | Installation of 50kVA Distribution<br>Transformers  | 1,116,073.73  | 1,116,073.73  | 1,255,582.94       | 1,395,092.16 | 1,395,092.16 | 6,277,914.72   |
|     | Secondary Distribution Projects   |               |               |                    |              |              | <u> </u>       |
| 21  | Open Secondary Low Voltage Distribution<br>Lines  | 6,632,580.23  | 7,178,121.89  | 7,737,914.86       | 8,308,512.27 | 8,887,498.35 | 38,744,627.60  |
| 22  | Under Built Low Voltage Distribution Lines  | 1,052,298.79  | 1,138,852.26  | 1,227,666.79       | 1,318,195.50 | 1,410,055.13 | 6,147,068.47   |
|     | Other Network Projects  |               |               |                    |              |              |                |
| 23  | Customer Service Drops  | 6,469,954.43  | 6,995,487.13  | 7,537,327.93       | 8,091,765.03 | 8,656,114.18 | 37,750,648.70  |
| 24  | 60A KWh meter for Customer Metering<br>Equipment  | 5,424,643.07  | 5,873,705.07  | 6,336,702.16       | 6,810,462.65 | 7,292,692.88 | 31,738,205.83  |
| 25  | 100A KWh meter for Customer Metering<br>Equipment   | 4,061,134.26  | 4,380,754.75  | 4,710,293.56       | 5,047,493.23 | 5,390,721.26 | 23,590,397.06  |
| 26  | 3-phase KWh meter for Customer<br>Metering Equipment  | 395,677.09    | 452,202.39    | 508,727.69         | 565,252.98   | 565,252.98   | 2,487,113.13   |
| 27  | Installation of Circuit Breaker for two (2)<br>existing substations and replacement of<br>AVR and Reclosers | -             | 10,162,000.00 | 17,082,054.00      | -            | •            | 27,244,054.00  |
| 28  | Replacement of 60A KWh meters   | 681,168.60    | 681,168.60    | 681,168.60         | 681,168.60   | 681,168.60   | 3,405,843.00   |
| 29  | Replacement of 100A KWh meters  | 507,573.36    | 507,573.36    | 507,573.36         | 507,573.36   | 507,573.36   | 2,537,866.80   |
| 30  | Replacement of KWh meters with infrared<br>reading features   | -             | 9,815,072.40  | -                  | 9,815,072.40 | -            | 19,630,144.80  |

|    |  |                |                |                |               | -             |                |
|----|--|----------------|----------------|----------------|---------------|---------------|----------------|
|    |  |                |                |                |               |               |                |
|    |  |                |                |                |               |               |                |
|    |  |                |                |                |               |               |                |
| 31 | Replacement of 3-phase KWh meters with<br>Load Profiling features              | 282,626.49     | 282,626.49     | 282,626.49     | 282,626.49    | 282,626.49    | 1,413,132.46   |
| 32 | Replacement of aging poles with Concrete poles preferably along 3-phase system | 2,579,341.94   | 2,579,341.94   | 2,579,341.94   | 2,579,341.94  | 2,579,341.94  | 12,896,709.70  |
| 33 | Replacement of aging poles with Steel<br>poles preferably along 3-phase system | 1,228,227.49   | 1,228,227.49   | 1,228,227.49   | 1,228,227.49  | 1,228,227.49  | 6,141,137.45   |
| 34 | Rural Electrification Projects   | 10,543,000.00  | 19,372,000.00  | 19,372,000.00  | 13,702,000.00 | 28,408,000.00 | 91,397,000.00  |
|    | Non-network Projects   |                |                |                |               |               |                |
| 35 | Communication System Equipment (VHF<br>Radio & Repeater System)                | 334,500.00     | 112,500.00     | 112,500.00     | 226,500.00    | 76,500.00     | 862,500.00     |
| 36 | Geographical Information System (hardware & software)                          | 180,000.00     | 120,000.00     | -              | -             | -             | 300,000.00     |
| 37 | Meter Reading, Billing Collection System<br>(hardware & software)              | 1,392,900.00   | 1,989,600.00   | 620,500.00     | 771,000.00    | 2,664,000.00  | 7,438,000.00   |
| 38 | Management Information System  | -              | -              | 400,000.00     |               | -             | 400,000.00     |
| 39 | Tools, Instruments & Test Equipment  | 9,203,736.00   | 3,882,693.80   | 8,911,342.80   | 5,116,743.80  | 2,120,743.80  | 29,235,260.20  |
| 40 | Vehicles   | 13,170,000.00  | 9,050,000.00   | 15,705,000.00  | 10,080,000.00 | 5,050,000.00  | 53,055,000.00  |
| 41 | Computers & Other Equipment  | 600,000.00     | 530,850.00     | 530,850.00     | 575,850.00    | 571,850.00    | 2,809,400.00   |
| 42 | Buildings & Lots   | 19,350,057.00  | 1,289,715.57   | 1,310,307.57   | 7,550,164.00  | 7,738,293.42  | 37,238,537.56  |
|    | Grand Total (PhP)  | 139,825,594.47 | 153,715,948.92 | 354,210,927.13 | 91,511,240.91 | 93,096,219.50 | 832,359,930.93 |

.

· 4

# ANNEX C

# Approved 5-year CAPEX Projects of CEBECO I

|     | Decision ( No. 1)   |               | Recomm        | ended Project C | ost (PhP)     |               | Total (PhP)   |
|-----|---|---------------|---------------|-----------------|---------------|---------------|---------------|
| No. | Project Name  | 2014          | 2015          | 2016            | 2017          | 2018          | Iotal (PhP)   |
|     | Primary Distribution Projects   | ]             |               |                 |               |               |               |
| 5   | Installation of Recloser along Barili Feeder  | 700,000.00    | -             | -               | -             | -             | 700,000.00    |
| 6   | Installation of Recloser along Dumanjug<br>Feeder   | 700,000.00    | -             | -               | -             | -             | 700,000.00    |
| 7   | Installation of Recloser along Sibonga<br>Feeder1   | 700,000.00    | -             | -               | -             | -             | 700,000.00    |
| 8   | Installation of Recloser along Sibonga<br>Feeder2   | 700,000.00    | -             | -               | -             | -             | 700,000.00    |
| 9   | Installation of Recloser along Dalaguete<br>Feeder1   | 700,000.00    | -             | -               | -             | -             | 700,000.00    |
| 10  | Installation of Recloser along Dalaguete<br>Feeder3   | 700,000.00    | -             | -               | -             | -             | 700,000.00    |
| 11  | Installation of Recloser along Dalaguete<br>Feeder4   | -             | 700,000.00    | -               | -             | -             | 700,000.00    |
| 12  | Installation of Recloser along Carcar 2<br>Feeder1  | 700,000.00    | -             | -               | -             | -             | 700,000.00    |
| 13  | Installation of Recloser along Samboan<br>Feeder1   | -             | 700,000.00    | -               | -             | -             | 700,000.00    |
| 14  | Installation of Recloser along Samboan<br>Feeder2   | 700,000.00    | -             | -               | -             | · -           | 700,000.00    |
| 15  | Installation of Capacitors  | -             | 543,385.52    | 543,385.52      | 271,692.76    | 543,385.52    | 1,901,849.32  |
| 16  | Installation of Line AVRs along the feeders   | -             | 9,600,000.00  | -               | -             | -             | 9,600,000.00  |
| 17  | Installation of 15kVA Distribution<br>Transformers  | 775,298.29    | 834,936.62    | 894,574.95      | 954,213.28    | 1,013,851.61  | 4,472,874.75  |
| 18  | Installation of 25kVA Distribution<br>Transformers  | 1,238,080.00  | 1,392,840.00  | 1,470,220.00    | 1,547,600.00  | 1,702,360.00  | 7,351,100.00  |
| 19  | Installation of 37.5kVA Distribution<br>Transformers  | 1,039,137.00  | 1,039,137.00  | 1,133,604.00    | 1,228,071.00  | 1,322,538.00  | 5,762,487.00  |
| 20  | Installation of 50kVA Distribution<br>Transformers  | 662,610.00    | 773,045.00    | 773,045.00      | 883,480.00    | 883,480.00    | 3,975,660.00  |
|     | Secondary Distribution Projects   | 7             |               |                 |               |               |               |
| 21  | Open Secondary Low Voltage Distribution Lines   | 3,343,614.24  | 3,693,555.84  | 4,019,264.88    | 4,209,426.24  | 4,557,921.12  | 19,823,782.32 |
| 22  | Under Built Low Voltage Distribution Lines  | 562,151.90    | 612,122.64    | 646,541.14      | 702,719.33    | 746,903.18    | 3,270,438.19  |
|     | Other Network Projects  | ]             |               |                 |               |               |               |
| 23  | Customer Service Drops  | 4,516,083.00  | 4,883,124.40  | 5,261,394.60    | 5,648,086.40  | 6,041,796.20  | 26,350,484.60 |
| 24  | 60A KWh meter for Customer Metering<br>Equipment  | 3,347,114.70  | 3,624,499.89  | 3,910,290.70    | 4,201,965.44  | 4,499,524.10  | 19,583,394.84 |
| 25  | 100A KWh meter for Customer Metering<br>Equipment   | 3,933,903.57  | 4,243,419.84  | 4,562,558.36    | 4,889,715.45  | 5,221,683.67  | 22,851,280.89 |
| 27  | Installation of Circuit Breaker for two (2)<br>existing substations and replacement of<br>AVR and Reclosers | -             | 10,162,000.00 | 17,082,054.00   | -             | -             | 27,244,054.00 |
| 28  | Replacement of 60A KWh meters   | 420,280.60    | 420,280.60    | 420,280.60      | 420,280.60    | 420,280.60    | 2,101,403.00  |
| 29  | Replacement of 100A KWh meters  | 481,113.36    | 481,113.36    | 481,113.36      | 481,113.36    | 481,113.36    | 2,405,566.80  |
| 30  | Replacement of KWh meters with infrared<br>reading features   | -             | 9,374,072.40  | -               | 9,374,072.40  |               | 18,748,144.80 |
| 31  | Replacement of 3-phase KWh meters with<br>Load Profiling features   | 140,109.96    | 140,109.96    | 140,109.96      | 140,109.96    | 140,109.96    | 700,549.78    |
| 32  | Replacement of aging poles with Concrete<br>poles preferably along 3-phase system                           | 1,512,656.88  | 1,512,656.88  | 1,512,656.88    | 1,512,656.88  | 1,512,656.88  | 7,563,284.40  |
| 33  | Replacement of aging poles with Steel poles preferably along 3-phase system                                 | 821,388.65    | 821,388.65    | 821,388.65      | 821,388.65    | 821,388.65    | 4,106,943.25  |
| 34  | Rural Electrification Projects  | 10,543,000.00 | 19,372,000.00 | 19,372,000.00   | 13,702,000.00 | 28,408,000.00 | 91,397,000.00 |
|     | Non-Network Projects  |               |               |                 |               |               |               |
| 35  | Communication System Equipment (VHF Radio & Repeater System)  | 334,500.00    | 112,500.00    | 112,500.00      | 226,500.00    | 76,500.00     | 862,500.00    |
| 36  | Geographical Information System (hardware & software)   | 180,000.00    | 120,000.00    | -               | -             | -             | 300,000.00    |

.

| 37 | Meter Reading, Billing Collection System (hardware & software) | 1,392,900.00  | 1,989,600.00  | 620,500.00    | 771,000.00    | 2,664,000.00  | 7,438,000.00   |
|----|--|---------------|---------------|---------------|---------------|---------------|----------------|
| 38 | Management Information System                                  | -             | -             | 400,000.00    | -             | -             | 400,000.00     |
| 39 | Tools, Instruments & Test Equipment                            | 8,142,736.00  | 2,574,693.80  | 8,007,342.80  | 4,206,743.80  | 1,436,743.80  | 24,368,260.20  |
| 41 | Computers & Other Equipment                                    | 270,000.00    | 280,500.00    | 280,500.00    | 280,500.00    | 278,500.00    | 1,390,000.00   |
| 42 | Buildings & Lots   | 16,289,715.57 | 1,289,715.57  | 1,310,307.57  | 7,289,715.57  | 7,738,293.42  | 33,917,747.70  |
|    | Grand Total (PhP)  | 65,546,393.72 | 81,290,697.97 | 73,775,632.97 | 63,763,051.11 | 70,511,030.07 | 354,886,805.84 |

,

6

# DETAILED PROJECT DISCUSSION

# I. NETWORK PROJECTS

| Project No.      | 1  |
|------------------|--|
| Project Title    | Installation of 10 MVA Substation in Argao |
| Project Code     | DSC-01                                     |
| Project Type     | Capacity                                   |
| Priority Rank    | 2  |
| Project Category | Substation Project                         |

| Project Description  | Duration |
|--|----------|
| <ul> <li>Construction of a new 69/13.2 kV, 10 MVA power</li> </ul> | 2012     |
| substation at Lamacan, Argao.                                      | 2012     |

| Proposed C | APEX Cost (   | PhP) |      |      |               |
|------------|---------------|------|------|------|---------------|
| 2011       | 2012          | 2013 | 2014 | 2015 | Total         |
| -          | 40,530,000.00 | -    | -    | -    | 40,530,000.00 |

# **Project Justification**

 Based on the application, the project is intended to address the impending capacity problem within areas presently being served by the existing NGCP owned Sibonga substation on year 2012. The proposed substation shall replace the said NGCP substation.

# **Technical Analysis**

- The 5 MVA Sibonga Substation is presently owned by the National Grid Corporation of the Philippines (NGCP). CEBECO I intends to have its own substation that would cater the existing loads of the said substation either by acquiring the said substation from NGCP or by constructing a new one.
- Based on the cooperative analysis, the construction of a new substation and upgrading its capacity to 10 MVA is appropriate considering that the existing loading percentage of the combined capacities of Sibonga and Dalaguete substations is above the 70% loading criterion that would trigger substation capacity augmentation planning, as shown in the table below.

| Substation          | Rated MVA | Rated MVA Max. MVA |           | Forecast Years |        |        |        |        |
|---------------------|-----------|--------------------|-----------|----------------|--------|--------|--------|--------|
|                     | Capacity  | Capacity           |           | 2011           | 2012   | 2013   | 2014   | 2015   |
| Sibonga             | 5         | 6.25               | MW Demand | 4.86           | 5.01   | 5.15   | 5.30   | 5.44   |
|                     |           |                    | % Loading | 86.39%         | 89.02% | 91.61% | 94.18% | 96.73% |
| Dalaguete           | 10        | 12.5               | MW Demand | 6.52           | 6.88   | 7.23   | 7.59   | 7.95   |
|                     |           |                    | % Loading | 57.98%         | 61.14% | 64.31% | 67.47% | 70.63% |
| Sibonga & Dalaguete | 15        | 18.75              | MW Demand | 11.38          | 11.89  | 12.39  | 12.89  | 13.39  |
|                     |           |                    | % Loading | 67.45%         | 70.43% | 73.41% | 76.37% | 79.33% |

- The Commission, on the other hand, reviewed the present loading situation of the Sibonga and Dalaguete substations considering that there are 2 substations that were not included in the submitted technical analysis. The 2 substations namely, the Samboan and the Carcar2, were the previous approved CAPEX projects prior to this application. The supposed additional forecasted demands of the Sibonga and Dalaguete prior to the construction of the Samboan and Carcar2 substations shall be catered by the 2 latter substations after its construction. It is therefore necessary to re-evaluate the present loading assessment of the existing substations of CEBECO I.
- Based on the said review, the individual loading percentages of the Sibonga and Dalaguete substations, as well as the combined capacities of both substations, did not exceed 70%, as shown in the table below. The computation was based on the submitted additional data containing demand forecast of the entire substations of CEBECO I and using the maximum capacities of each substations with 90% power factor.

| Substation          | Rated MVA | Max. MVA | ן         |        | Forecast Years |        |        |        |
|---------------------|-----------|----------|-----------|--------|----------------|--------|--------|--------|
|                     | Capacity  | Capacity |           | 2011   | 2012           | 2013   | 2014   | 2015   |
| Sibonga             | 5         | 6.25     | MW Demand | 4.351  | 3.024          | 3.410  | 3.510  | 3.602  |
|                     |           |          | % Loading | 77.35% | 53.76%         | 60.62% | 62.40% | 64.04% |
| Dalaguete           | 10        | 12.5     | MW Demand | 6.952  | 6.216          | 5.936  | 6.232  | 6.527  |
|                     |           |          | % Loading | 70.68% | 55.25%         | 52.76% | 55.40% | 58.02% |
| Sibonga & Dalaguete | 15        | 18.75    | MW Demand | 11.30  | 9.24           | 9.35   | 9.74   | 10.13  |
|                     |           |          | % Loading | 72.91% | 54.76%         | 55.38% | 57.73% | 60.02% |

- The findings above would only limit the discussion on whether it is practical for CEBECO I to provide the following alternative projects:
  - a) Maintain with the existing NGCP 5MVA Sibonga Substation;
  - b) Acquire the NGCP 5MVA Sibonga Substation; and
  - c) Construct a new 5MVA Substation.

# Economic and Cost Analysis

 Based on the review made by the Commission, the first option is the most practical approach considering that it presented the least cost among the alternatives. Summary of the analysis is shown in the table below.

| Project Name                              | Effective<br>Years | Initial Cost<br>(PhP) | O&M Expense<br>(PhP) | Annual CC/RST<br>Charges (PhP) | Lifetime Cost<br>NPV (PhP) |
|---|--------------------|-----------------------|----------------------|--------------------------------|----------------------------|
| a) Maintain with NGCP 5MVA<br>Sibonga SS  | 10                 | -                     | -                    | 959,396.76                     | 6,437,630.35               |
| b) Acquisition of NGCP 5MVA<br>Sibonga SS | 10                 | 17,230,197.00         | 516,905.91           | -                              | 20,698,677.73              |
| c) 5MVA Argao Substation                  | 10                 | 21,767,033.25         | 217,670.33           | -                              | 23,227,618.89              |

 The computation of lifetime cost was based on the assumption that the assets are technically effective within 10 years, the O&M cost for options b and c having 3% and 1% of its estimated costs, respectively, and a discount rate of 8%, which is the existing interest rate for NEA loans.  The estimated cost for the construction of a new 5MVA substation was based on the NEA price benchmark while the cost for acquiring the existing NGCP 5MVA Sibonga Substation was based on the additional data submitted by the cooperative.

| Approved   | Remarks |
|--|---------|
| Project to continue as proposed  |         |
| Project to continue with REVISED Capital Expenditure   |         |
| Project to continue with Technical Amendments  |         |
| Project to be deferred which may be included in its next application with additional justification | ✓       |

| Approved C | APEX Cost | (PhP) |      |      |       |
|------------|-----------|-------|------|------|-------|
| 2011       | 2012      | 2013  | 2014 | 2015 | Total |
| -          | -         | -     | -    | -    | -     |

9

| Project No.      | 2  |
|------------------|--|
| Project Title    | Installation of 10MVA Substation in Badian |
| Project Code     | DSC-02                                     |
| Project Type     | Capacity                                   |
| Priority Rank    | 2  |
| Project Category | Substation Project                         |

| Project Description  | Duration  |
|--|-----------|
| <ul> <li>Construction of a new 69/13.2 kV, 10 MVA point</li> </ul> | ower 2015 |
| substation in Badian. Cebu.  | 2013      |

| Proposed C | APEX Cost ( | PhP) |      |               |               |
|------------|-------------|------|------|---------------|---------------|
| 2011       | 2012        | 2013 | 2014 | 2015          | Total         |
| -          | -           | -    | -    | 40,530,000.00 | 40,530,000.00 |

# **Project Justification**

 Based on the application, the project is intended to address the impending capacity problem and the existing power quality problem within areas presently being served by the Dumanjug substation on year 2015.

### **Technical Analysis**

Based on CEBECO I's analysis, the construction of a new 10 MVA power substation is appropriate not only because it will address the alleged capacity issue but it will also solve the existing and the impending power quality issue being experienced in some areas being catered by the Dumanjug Substation. The said loading assessment is above the 70% loading criterion that would trigger substation capacity augmentation planning, as shown in the table below.

| Substation Rated MVA Capacity | Rated MVA | Max. MVA | ]         | Forecast Years |        |        |        |        |
|-------------------------------|-----------|----------|-----------|----------------|--------|--------|--------|--------|
|                               | Capacity  |          | 2011      | 2012           | 2013   | 2014   | 2015   |        |
| Dumajug 10                    | 10        | 10 12.5  | MW Demand | 7.91           | 8.18   | 8.44   | 8.68   | 8.91   |
|                               | 10        |          | % Loading | 70.28%         | 72.73% | 75.02% | 77.17% | 79.19% |

- The loading assessment of CEBECO I, however, needs re-evaluation considering that the Samboan and Carcar 2 substations was not yet included in the said analysis, as previously discussed in Project No. 1. ROS included the Samboan Substation in the loading performance reevaluation since some of its existing load shall be transferred to the proposed substation.
- Based on the review made by the Commission, the individual loading percentages of the Dumanjug and Samboan substations, as well as the combined capacities of both substations, did not exceed 70%, as manifested in the table below. The computation was based on the submitted additional data containing demand forecast of the entire substations of CEBECO I and using the maximum capacities of each substations with 90% power factor.

| 0.1               | Rated MVA Max. M |           |           | Forecast Years |        |        |        |        |
|-------------------|------------------|-----------|-----------|----------------|--------|--------|--------|--------|
| Substation        | Capacity         | Capacity  |           | 2011           | 2012   | 2013   | 2014   | 2015   |
| Dumajug           | 10               | 12.5      | MW Demand | 6.52           | 6.55   | 7.31   | 7.52   | 7.72   |
|                   |                  |           | % Loading | 57.94%         | 58.24% | 64.96% | 66.81% | 68.58% |
| Samboan           | 5 6.25           | 0.05      | MW Demand | 1.42           | 3.23   | 3.60   | 3.75   | 3.91   |
|                   |                  | 0.25      | % Loading | 25.24%         | 57.35% | 63.91% | 66.65% | 69.53% |
| Dumajug & Samboan | Samboan 15 18.75 | 40.75     | MW Demand | 7.94           | 9.78   | 10.90  | 11.27  | 11.63  |
|                   |                  | % Loading | 47.04%    | 57.94%         | 64.61% | 66.76% | 68.89% |        |

 The proposed project will no longer be needed considering that the existing and impending power quality issues of the Dumanjug and Samboan substations will be addressed by Project Nos. 15 & 16.

# Economic and Cost Analysis

 The economic assessment of the proposed project is already irrelevant considering the findings discussed above.

| Approved   | Remarks |
|--|---------|
| Project to continue as proposed  |         |
| Project to continue with REVISED Capital Expenditure   |         |
| Project to continue with Technical Amendments  |         |
| Project to be deferred which may be included in its next application with additional justification | ~       |

| Approved C | APEX Cost ( | PhP) |      |      |       |
|------------|-------------|------|------|------|-------|
| 2011       | 2012        | 2013 | 2014 | 2015 | Total |
| -          | -           | -    | -    | -    | -     |

| Project No.      | 3   |  |  |
|------------------|---|--|--|
| Project Title    | Acquisition of subtransmission Asset from TransCo<br>through a Consortium with VECO |  |  |
| Project Code     | STR-01  |  |  |
| Project Type     | Reliability   |  |  |
| Priority Rank    | 3   |  |  |
| Project Category | Subtransmission Line Project  |  |  |

| Project Description   | Duration |
|---|----------|
| The proposed amount shall be used as a capital<br>investment of CEBECO I on the newly created<br>entity/consortium with Visayas Electric Corporation<br>(VECO) named as "CEBECO I-VECO South Sub-<br>transmission Company, Inc." which was registered<br>with Securities and Exchange Commission (SEC) as<br>another private corporation. | 2011     |

| Proposed CAPEX Cost (PhP) |      |      |      |      |              |  |
|---------------------------|------|------|------|------|--------------|--|
| 2011                      | 2012 | 2013 | 2014 | 2015 | Total        |  |
| 3,500,000.00              | -    | -    | -    | -    | 3,500,000.00 |  |

# **Project Justification**

 CEBECO I perceived that it is necessary for them to recover the amount through the RFSC collections which will be used as stockholder's share to the abovementioned company.

# Technical / Economic and Cost Analysis

- On September 6, 2010, the Commission approved the application regarding the sale of subtransmission assets of TransCo/NGCP to be acquired by CEBECO I and VECO through a Consortium. The said application was filed on October 30, 2007 under ERC Case No. 2007-492 MC. The approved purchased cost for the said assets amounted to PhP50,446,849.58. The following are the approved subtransmission assets to be acquired by CEBECO I and VECO I and VECO:
  - a) Naga–Sibonga–Dumanjug 69kV line; and
  - b) Sibonga–Alcoy 69kV line.
- CEBECO I and VECO executed an Amended and Restated Shareholders' Agreement to define and regulate the rights and duties as shareholders of the Consortium. The agreement is requiring CEBECO I to provide a share amounting to PhP3,500,000.00 as its share of stock in the consortium wherein said amount is 70% of the total capital stock. It is the intention of the cooperative to recover the said share of CEBECO I through this project.
- The proposed project is not a capital expenditure project since capital expenditure is an amount spent to acquire or upgrade productive assets in order to increase the capacity or efficiency of a company for

more than one (1) accounting period. Moreover, the said expense (share of stocks) is not included in the list of assets or Operation and Maintenance (O&M) expense that could be capitalized as specified in the CAPEX Guidelines.

- Based on the letter by CEBECO I dated September 3, 2013, that it already paid the required proportionate share of the price of the subtransmission asset amounting to more than PhP35 Million using its general fund as investment to the consortium in acquiring the said asset. CEBECO I also stated that it does not intend to recover from its consumers the investment in acquiring the assets since any income by the consortium will be treated as other revenue item. In this regard, the Commission deems that it is only reasonable that the proposed project should come from the Other Revenue Income (ORI) or charged to Investment in accordance to its Accounting and Cost Allocation Manual (ACAM).
- The Commission, thereby, approves that the funding of the project be charged to CEBECO I's general fund as investment.

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed                          |              |
| Project to continue with REVISED Capital Expenditure     |              |
| Project to continue with Technical Amendments            |              |
| Project to be deferred which may be included in its next |              |
| application with additional justification                |              |
| Project to be disapproved                                | $\checkmark$ |

| Approved CAPEX Cost (PhP) |      |      |      |      |       |  |
|---------------------------|------|------|------|------|-------|--|
| 2011                      | 2012 | 2013 | 2014 | 2015 | Total |  |
| -                         | -    | -    | -    | -    | -     |  |

| Project No.      | 4   |
|------------------|---|
| Ducio et Title   | Construction of 70.5 km, 69 kV subtransmission line |
| Project Title    | from Suba, Samboan to Bito-on, Dumajug              |
| Project Code     | STR-02  |
| Project Type     | Reliability   |
| Priority Rank    | 3   |
| Project Category | Subtransmission Line Project                        |

| Project Description  | Duration |
|--|----------|
| <ul> <li>The project consists of constructing a 70.5km, 69 kV<br/>subtransmission line from Suba, Samboan to Bito-on,<br/>Dumanjug.</li> </ul> | 2015     |

| Proposed CAPEX Cost (PhP) |      |      |      |                |                |  |  |  |
|---------------------------|------|------|------|----------------|----------------|--|--|--|
| 2011                      | 2012 | 2013 | 2014 | 2015           | Total          |  |  |  |
| -                         | -    | -    | -    | 248,705,300.00 | 248,705,300.00 |  |  |  |


The proposed project intends to improve the reliability performance of the entire distribution system by focusing on the 69 kV voltage-level lines. The proposed 69 kV line shall serve as a tie line between the Dumanjug Substation, the proposed Badian Substation, and the Samboan Substation.

#### **Technical Analysis**

- Several alternative projects were developed by CEBECO I in order to attain reliability performance improvement. The proposed project was selected since it has the shortest route and it shall provide the least cost among the alternative projects.
- The forecasted benefit derived from the project was based on the avoided Expected Energy Not Served (EENS) with the project's implementation. The forecasted annual benefit for at least five years is shown in the table below.

| Year   | EENS         | EENS (KWh)   |                 |  |
|--------|--------------|--------------|-----------------|--|
| · rear | Existing     | With Project | (KWh) - Benefit |  |
| 2015   | 6,806,347.87 | 213,388.71   | 6,592,959.16    |  |
| 2016   | 6,997,265.84 | 219,374.26   | 6,777,891.58    |  |
| 2017   | 7,178,684.92 | 225,062.01   | 6,953,622.92    |  |
| 2018   | 7,350,605.12 | 230,451.95   | 7,120,153.17    |  |
| 2019   | 7,513,026.43 | 235,544.09   | 7,277,482.34    |  |

 The existing line configuration and the proposed line configuration with the project are shown in figures 4.1 and 4.2, respectively.



#### Economic and Cost Analysis

- Based on CEBECO I's analysis, the proposed project is economically viable considering that the computed benefit/cost (B/C) ratio is more than 1. The B/C ratio was determined based on the probable monetary savings derived from the avoided EENS with the project and using the existing generation, transmission and distribution charges.
- The Commission finds that the said rates, except for distribution, should not be used in the computation for the project's projected annual benefits since these rates are just pass-on charges. It is essential that the existing distribution, supply, metering, and RFSC rates should be used in the analysis thus, reassessment of the project was made.
- Based on the review made by the Commission, the project is not economically feasible since the computed benefit/cost ratio is less than 1. Summary of the analysis is shown in the table below:

| B/C                  | 0.43               |   |
|----------------------|--------------------|---|
| Discount Rate        | 8%                 | - |
| PV of Benefits       | PhP140,437,189.71  |   |
| PV of Cost           | PhP328,351,502.43  |   |
| Total Benefits (NPV) | -PhP187,914,312.72 |   |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed  |              |
| Project to continue with REVISED Capital Expenditure   |              |
| Project to continue with Technical Amendments  |              |
| Project to be deferred which may be included in its next application with additional justification | $\checkmark$ |

| Approved CAPEX Cost (PhP) |      |      |      |      |       |  |  |  |  |
|---------------------------|------|------|------|------|-------|--|--|--|--|
| 2011                      | 2012 | 2013 | 2014 | 2015 | Total |  |  |  |  |
| -                         | -    | · –  | -    | -    | -     |  |  |  |  |

| Project Nos.     | 5 to 14                                |
|------------------|--|
| Project Title    | Installation of Recloser along feeders |
| Project Code     | PDS-01 to PDS-10                       |
| Project Type     | Safety                                 |
| Priority Rank    | 1                                      |
| Project Category | Primary Distribution Line Project      |

| Project Description   | Duration    |
|---|-------------|
| <ul> <li>Installation of 630A, Automatic Recloser within<br/>several backbone lines of the entire system. These<br/>devices shall be installed along the mid-range part of<br/>the primary distribution lines.</li> </ul> | 2011 & 2013 |

| Proposed CAPEX Cost (PhP) |      |              |      |      |              |  |  |
|---------------------------|------|--------------|------|------|--------------|--|--|
| 2011                      | 2012 | 2013         | 2014 | 2015 | Total        |  |  |
| 5,600,000.00              | -    | 1,400,000.00 | -    | -    | 7,000,000.00 |  |  |

Based on the result of CEBECO I's short circuit simulation study, there
is a need to install 3-phase reclosers along several identified feeders in
order to maintain a safe electric power system and service.

#### **Technical Analysis**

- Some of the existing feeders of CEBECO I were found to have a minimum fault below the existing protection setting of the protection devices designated along these feeder lines. Based on CEBECO I's short-circuit analysis, the existing substation recloser cannot sense the minimum fault current in the farthest end of the line in the event fault occurred within the area. This situation poses danger to the safety of the consumers living nearby these lines or any passers-by.
- Summary of the short circuit analysis and the existing minimum setting of the feeders involve for additional back-up protection is shown in the table below:

| Substation Feeder<br>Name |        | substation |        | Safety<br>Margin | Feeder<br>Status |  |
|---------------------------|--------|------------|--------|------------------|------------------|--|
| Dumanius                  | DumF1  | 122.97     | 267.00 | 217.13%          | inadequate       |  |
| Dumanjug                  | DumF2  | 76.57      | 685.00 | 894.61%          | inadequate       |  |
| Sibonga                   | SibF1  | 131.49     | 185.00 | 140.70%          | inadequate       |  |
|                           | SibF2  | 103.33     | 172.00 | 166.46%          | inadequate       |  |
| Dalaguete                 | DalF1  | 95.06      | 212.00 | 223.02%          | inadequate       |  |
|                           | DalF3  | 107.94     | 329.00 | 304.80%          | inadequate       |  |
|                           | DalF4  | 101.42     | 104.00 | 102.54%          | inadequate       |  |
| Samboan                   | SamF1  | 89.80      | 91.00  | 101.34%          | inadequate       |  |
| Samuoan                   | SamF2  | 111.94     | 210.00 | 187.60%          | inadequate       |  |
| Carcar 2                  | Car2F1 | 132.76     | 263.00 | 198.10%          | inadequate       |  |

#### **Economic and Cost Analysis**

The EC has come up with an alternative solution to address the problem by installing single phase fuse for each phase of the distribution line. However, said solution is not technically feasible considering that the equipment's capability is limited only for single phase lines. Its feature, particularly its incapability to switch each phase of the three-phase distribution lines simultaneously, is unsafe for three-phase customers. Moreover, the said equipment is incapable of detecting zero-sequence component which only adds to its disadvantage.

- The only technically feasible solution to address the existing problem of the distribution system, without having disadvantages as mentioned above, is to install an additional backup recloser nearby the affected areas not being sensed by the main substation recloser during minimum fault.
- The proposed project cost is recommended considering that the equipment is unavailable in both the NEA Price Index and the ERC Valuation Handbook. Moreover, the said cost of equipment is within the available price inquired in the internet as well as the previous applications of the Commission.
- Shown in the table below is the proposed project cost breakdown:

| No. | Materials          | Specifications | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Material Cost<br>(PhP) | Project Cost<br>(PhP) |  |
|-----|--------------------|----------------|-----------------|-------------------------|------|------------------------|-----------------------|--|
| 1   | Automatic Recloser | Vacuum, 630A   | 8               | 700,000.00              | 2011 | 5,600,000.00           | 7.000.000.00          |  |
| 2   | Automatic Recloser | Vacuum, 630A   | 2               | 700,000.00              | 2013 | 1,400,000.00           | 7,000,000.00          |  |

| Approved   | Remarks                 |
|--|-------------------------|
| Project to continue as proposed                          | <ul> <li>✓ .</li> </ul> |
| Project to continue with REVISED Capital Expenditure     |                         |
| Project to continue with Technical Amendments            |                         |
| Project to be deferred which may be included in its next |                         |
| application with additional justification                |                         |

| Approved C   | APEX Cost | (PhP)        |      |      |              |
|--------------|-----------|--------------|------|------|--------------|
| 2011         | 2012      | 2013         | 2014 | 2015 | Total        |
| 5,600,000.00 | -         | 1,400,000.00 | -    | -    | 7,000,000.00 |

| Project Nos.     | 15 & 16  |
|------------------|--|
| Draiget Title    | Installation of Capacitors and Line AVRs along |
| Project Title    | feeders  |
| Project Code     | PDQ-01 & PDQ-02                                |
| Project Type     | Power Quality                                  |
| Priority Rank    | 2  |
| Project Category | Primary Distribution Line Project              |

| Project Description  | Duration     |
|--|--------------|
| <ul> <li>The project will require forty two (42) units of 50kVAR<br/>capacitors and fifteen (15) units of AVR. Six (6) units<br/>of capacitors, which are accompanied by a timer<br/>switch, and three (3) units of AVR to be installed in<br/>each feeder.</li> </ul> | 2011 to 2014 |
| <ul> <li>It also includes load balancing or transferring of loads<br/>from one phase to another.</li> </ul>  |              |

| Proposed C   | APEX Cost (  | PhP)         |              |      |               |
|--------------|--------------|--------------|--------------|------|---------------|
| 2011         | 2012         | 2013         | 2014         | 2015 | Total         |
| 8,045,000.00 | 4,045,000.00 | 3,623,000.00 | 4,045,000.00 | -    | 19,758,000.00 |

 CEBECO I proposed the installation of capacitors and Automatic Voltage Regulator (AVR) and balancing of loads within these feeders in order to address the power quality problem within the distribution system.

#### **Technical Analysis**

 Several primary distribution lines of CEBECO I have power quality problem as shown in the table below.

|                    | Feeder   | Year     | Existing          | g Condition      |           | With the Project  |                  |  |
|--------------------|----------|----------|-------------------|------------------|-----------|-------------------|------------------|--|
| Substation         | Name     | Affected | Voltage<br>(p.u.) | Unbalance<br>(%) | Solution  | Voltage<br>(p.u.) | Unbalance<br>(%) |  |
| Dumonius           | DumF1    | 2014     | 0.8913            | 2.42             | Capacitor | 0.9323            | 2.40             |  |
| Dumanjug           | DumF2    | 2014     | 0.8901            | 2.52             | Capacitor | 0.9219            | 2.40             |  |
| Carcar 1           | Car1F2   | 2013     | 0.8828            | 1.68             | Capacitor | 0.9408            | 0.30             |  |
| Sibonga            | SibF2    | 2011     | 0.8905            | 5.28             | Capacitor | 0.9064            | 2.34             |  |
|                    | DalF1    | 2012     | 0.8862            | 3.28             | Capacitor | 0.9031            | 2.26             |  |
| Dalaguete          | DalF3    | 2011     | 0.8787            | 4.39             | Capacitor | 0.9311            | 2.25             |  |
|                    | DalF4    | 2011     | 0.8787            | 5.70             | AVR       | 0.9552            | 2.30             |  |
| Carebaar           | SamF1    | 2014     | 0.8727            | 2.25             | AVR       | 0.9773            | 1.75             |  |
| Samboan            | SamF2    | 2013     | 0.8641            | 2.79             | AVR       | 0.9374            | 1.82             |  |
| Carcar 2           | Car2F1   | 2012     | 0.8836            | 3.04             | Capacitor | 0.9744            | 2.40             |  |
| Carcar 2-Totalizer | Car2-Tot | -        | -                 | -                | AVR       | -                 | -                |  |
| Argao              | ArgF4    | -        | -                 | -                | AVR       | -                 | -                |  |

The phase voltage magnitudes and the deviation of phase voltage magnitudes (voltage unbalance) of these feeders are beyond the power quality standards provided in the PDC. The said provision is requiring distribution utilities to maintain a voltage magnitude within ±10% of the nominal voltage level of 230 volts or per unit values ranging from 0.9 to 1.1 at the customer's connection point and a maximum voltage unbalance not exceeding 2.5% during normal operating conditions.

- There were several alternative solutions that were prepared by CEBECO I for each deficient feeder however, the proposed project presented the only technically feasible solution to address the problem. There is no other recourse but to implement these projects considering that such problem is mandatory to resolve.
- All of the proposed locations/feeders for the AVR projects were supported with technical justification and performance assessment, except for feeders Car2-totalizer and ArgF4. The Commission therefore approves the deferment of the supposed AVR project intended for the said two (2) feeders.

nomic and Cost Analysis

|     |                | n the follov<br>ns, to wit: | ving tables    | s are           | the pr                  | opos | ed project         |
|-----|----------------|-----------------------------|----------------|-----------------|-------------------------|------|--------------------|
|     | CAP            | ACITOR PRO.                 | JECTS          | ]               |                         |      |                    |
| No. | Feeder<br>Name | Materials                   | Specifications | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost (PhP) |
|     |                | Capacitors                  | 50kVAR         | 12              | 35,000.00               |      | 420,000.00         |
| 4   | SibF2<br>&     | Hanger                      | Cluster Type   | 12              | 5,000.00                | 2011 | 60,000.00          |
| 1   | DalF3          | Oil Switch                  | -              | 8               | 45,000.00               | 2011 | 360,000.00         |
|     |                | Capacitor Switch            | -              | 2               | 2,500.00                |      | 5,000.00           |
|     |                | Capacitors                  | 50kVAR         | 12              | 35,000.00               |      | 420,000.00         |
| 2   | DalF1          | Hanger                      | Cluster Type   | 12              | 5,000.00                | 2012 | 60,000.00          |
| 2   | &<br>Car2F1    | Oil Switch                  | -              | 8               | 45,000.00               |      | 360,000.00         |
|     | 00.2.1         | Capacitor Switch            | -              | 2               | 2,500.00                |      | 5,000.00           |
|     |                | Capacitors                  | 50kVAR         | 6               | 35,000.00               |      | 210,000.00         |
| 3   | Car1F2         | Hanger                      | Cluster Type   | 6               | 5,000.00                |      | 30,000.00          |
| 3   | Cariez         | Oil Switch                  | -              | 4               | 45,000.00               | 2013 | 180,000.00         |
|     |                | Capacitor Switch            | -              | 1               | 3,000.00                |      | 3,000.00           |
|     |                | Capacitors                  | 50kVAR         | 12              | 35,000.00               |      | 420,000.00         |
|     | DumF1          | Hanger                      | Cluster Type   | 12              | 5,000.00                | 2044 | 60,000.00          |
| 4   | o<br>DumF2     | Oil Switch                  | -              | 8               | 45,000.00               | 2014 | 360,000.00         |
|     |                | Capacitor Switch            | -              | 2               | 2,500.00                |      | 5,000.00           |

|     |                |            |                |                 | Granu 10                | tai  | 2,958,000.00       |
|-----|----------------|------------|----------------|-----------------|-------------------------|------|--------------------|
|     | ļ              | AVR PROJEC | TS             |                 |                         |      |                    |
| No. | Feeder<br>Name | Materials  | Specifications | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost (PhP) |
|     | DalF4          | AVR        | 167kVA         | 3               | 1,050,000.00            |      | 3,150,000.00       |
| 1   | Dair4          | AVR        | Accessories    | 1 set           | 50,000.00               | 2011 | 50,000.00          |
| 1   | Car2-          | AVR        | 333kVA         | 3               | 1,330,000.00            |      | 3,990,000.00       |
|     | totalizer      | AVK        | Accessories    | 1 set           | 10,000.00               |      | 10,000.00          |
| 2   | AraEd          | AVR        | 167kVA         | 3               | 1,050,000.00            | 2012 | 3,150,000.00       |
| 2   | ArgF4          | AVK        | Accessories    | 1 set           | 50,000.00               | 2012 | 50,000.00          |
| 3   | SamF2          | AVR        | 167kVA         | 3               | 1,050,000.00            | 2013 | 3,150,000.00       |
| 3   | Samrz          |            | Accessories    | 1 set           | 50,000.00               | 2013 | 50,000.00          |
| 4   | SamF1          | AVR        | 167kVA         | 3               | 1,050,000.00            | 2014 | 3,150,000.00       |
| 4   | Samri          |            | Accessories    | 1 set           | 50,000.00               | 2014 | 50,000.00          |
|     |                |            |                |                 | Grand To                | tal  | 16,800,000.00      |
|     |                |            |                | Cumu            | lative Project          | Cost | 19,758,000.00      |

Note: Highlighted rows are feeders with unavailable analysis and was not discussed in the application

- The Commission reviewed the proposed costs of the approved projects and determined that such costs be reduced. The Commission cost assessment involves adjustment of the unit costs of equipment and materials required for the capacitor projects in reference with the 2012 NEA price index. Moreover, the proposed unit costs of the materials and equipment required for the AVR projects were then used, however, the project costs intended for the Car2-totalizer and ArgF2 feeders were no longer included, considering the basis discussed in the technical analysis.
- Breakdown of the approved project cost are shown in the following tables.

|     |                |                        | <u> </u>       | ļ               |                         |      |                    |
|-----|----------------|------------------------|----------------|-----------------|-------------------------|------|--------------------|
| No. | Feeder<br>Name | Materials              | Specifications | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost (PhP) |
|     |                | Capacitors             | 50kVAR         | 12              | 12,465.46               |      | 149,585.5          |
| 1   | SibF2 &        | Hanger                 | Cluster Type   | 12              | 2,400.00                | 2011 | 28,800.0           |
| 1   | DalF3          | Oil Switch             | -              | 8               | 45,000.00               | 2011 | 360,000.0          |
|     |                | Capacitor Switch/Timer | -              | 2               | 2,500.00                |      | 5,000.0            |
|     |                | Capacitors             | 50kVAR         | 12              | 12,465.46               |      | 149,585.5          |
| 2   | DalF1 &        | Hanger                 | Cluster Type   | 12              | 2,400.00                | 2012 | 28,800.0           |
| 2   | Car2F1         | Oil Switch             | -              | 8               | 45,000.00               | 2012 | 360,000.0          |
|     |                | Capacitor Switch/Timer | -              | 2               | 2,500.00                |      | 5,000.0            |
|     |                | Capacitors             | 50kVAR         | 6               | 12,465.46               |      | 74,792.7           |
| 3   | Car1F2         | Hanger                 | Cluster Type   | 6               | 2,400.00                | 2013 | 14,400.0           |
| 3   |                | Oil Switch             | -              | 4               | 45,000.00               | 2013 | 180,000.0          |
|     |                | Capacitor Switch/Timer | •              | 1               | 2,500.00                |      | 2,500.0            |
|     | _              | Capacitors             | 50kVAR         | 12              | 12,465.46               |      | 149,585.5          |
| 4   | DumF1          | Hanger                 | Cluster Type   | 12              | 2,400.00                | 2014 | 28,800.0           |
| 4   | ox<br>DumF2    | Oil Switch             | •              | 8               | 45,000.00               | 2014 | 360,000.0          |
|     |                | Capacitor Switch/Timer | -              | 2               | 2,500.00                |      | 5,000.0            |
|     |                |                        |                |                 | Grand To                | tal  | 1,901,849.3        |
|     |                | AVR PROJECTS           |                | ]               |                         |      |                    |
| No. | Feeder<br>Name | Materials              | Specifications | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost (PhP) |
| 1   | DalF4          | AVR                    | 167kVA         | 3               | 1,050,000.00            | 2011 | 3,150,000.0        |
| 1   | Dair4          |                        | Accessories    | 1 set           | 50,000.00               | 2011 | 50,000.0           |
| 2   | SamF2          | AVR                    | 167kVA         | 3               | 1,050,000.00            | 2013 | 3,150,000.0        |
| 2   | Samrz          |                        | Accessories    | 1 set           | 50,000.00               | 2013 | 50,000.0           |
| 3   | SamF1          | AVR                    | 167kVA         | 3               | 1,050,000.00            | 2014 | 3,150,000.0        |
| 5   |                |                        | Accessories    | 1 set           | 50,000.00               | 2014 | 50,000.0           |
|     |                |                        |                |                 | Grand To                | tal  | 9,600,000.0        |
|     |                |                        |                | Cumu            | lative Project          | Cost | 11,501,849.32      |

#### CAPACITOR PROJECTS

application with additional justification

| 1   |          |             | 7.00000001100                          | 1 1 5 6 1 | 00,000.00                               |      | 00,000.00     |
|---|----------|-------------|--|-----------|---|------|---------------|
| 3   | SamF1    | AVR         | 167kVA                                 | 3         | 1,050,000.00                            | 2014 | 3,150,000.00  |
|   | Jainer   |             | Accessories                            | 1 set     | 50,000.00                               | 2014 | 50,000.00     |
|   |          |             |  |           | Grand To                                | tal  | 9,600,000.00  |
|   |          |             |  | Cumu      | lative Project                          | Cost | 11,501,849.32 |
| Appr  | oved     |             |  |           |   | ĺ    | Remarks       |
|   |          | ontinue as  | proposed                               |           |   |      |               |
| Proje   | ect to c | ontinue wit | h REVISED Cap                          | oital Ex  | penditure                               | Э    | ~             |
| Project to continue with Technical Amendments |          |             |  |           |   |      | $\checkmark$  |
| <sup>-</sup> roje                             | ect to b | e deferred  | which may be ir                        | nclude    | d in its ne                             | xt   |               |
|   |          |             | ······································ |           | ••••••••••••••••••••••••••••••••••••••• |      |               |

| Approved C   | APEX Cost ( | PhP)         |              |      |               |
|--------------|-------------|--------------|--------------|------|---------------|
| 2011         | 2012        | 2013         | 2014         | 2015 | Total         |
| 3,743,385.52 | 543,385.52  | 3,471,692.76 | 3,743,385.52 | -    | 11,501,849.32 |

| Project Nos.     | 17 to 20                                  |
|------------------|---|
| Project Title    | Installation of Distribution Transformers |
| Project Code     | DTX-01 to DTX-04                          |
| Project Type     | Capacity                                  |
| Priority Rank    | 2   |
| Project Category | Primary Distribution Line Project         |

| Project Description  | Duration     |
|--|--------------|
| <ul> <li>The following are the required specifications of the proposed DTs, to wit:         <ul> <li>a) The transformer ratings are 15, 25, 37.5 and 50 KVA;</li> <li>b) All transformers are of conventional type, oil immersed and pole-mounted;</li> <li>c) With primary voltage of 13.2 / 7.62 KV; and</li> <li>d) And secondary voltage of 120 / 240 or 240/480 V.</li> </ul> </li> </ul> | 2011 to 2015 |

| Proposed C   | APEX Cost (  | PhP)         |              |              |               |
|--------------|--------------|--------------|--------------|--------------|---------------|
| 2011         | 2012         | 2013         | 2014         | 2015         | Total         |
| 6,106,175.71 | 6,518,455.78 | 7,278,501.89 | 7,830,291.17 | 8,140,559.62 | 35,873,984.16 |

 The installation of additional distribution transformers (DT) to the network is a continuing process in the distribution utility to address the increase of additional loads. Additional loads require additional capacity in the distribution network assets.

## **Technical Analysis**

- The DT requirement was predicted by CEBECO I based on a 7-year historical trend of the installed communal transformers in the distribution system. The historical and forecasted number of customers and energy sales are used as the regressor to predict the annual DT requirement. The forecasted model used to determine the quantity of DT requirement is represented by the equation: DT = (5.9254x10<sup>-3</sup> x (Consumers)) + (3.6720x10<sup>-6</sup> x (Sales)). However, the necessary data using this regression model is unacceptable considering that it did not meet the required criteria to validate the accuracy of the forecasted model. The said model has an Adjusted R<sup>2</sup> of 0.6952 and a MAPE of 33.14%.
- The Commission conducted its own simulations to determine the most acceptable quantity of the DT's per rated capacity to be acquired by CEBECO I. Based on the said simulations, the proposed quantity of the DT's should be reduced.
- Summary of the computation are shown in the tables below:

| Year | Load Growth | Required     | Catered ca | pacity of DT p | per rated capa | acity (KVA) |
|------|-------------|--------------|------------|----------------|----------------|-------------|
| rear | (KW)        | Demand (KVA) | 15 KVA     | 25 KVA         | 37.5 KVA       | 50 KVA      |
| 2011 | 1,121.06    | 1,245.63     | 186.57     | 395.09         | 378.63         | 285.34      |
| 2012 | 1,215.57    | 1,350.63     | 202.30     | 428.39         | 410.54         | 309.39      |
| 2013 | 1,311.64    | 1,457.38     | 218.29     | 462.25         | 442.99         | 333.85      |
| 2014 | 1,408.84    | 1,565.38     | 234.46     | 496.51         | 475.82         | 358.59      |
| 2015 | 1,506.85    | 1,674.28     | 250.77     | 531.05         | 508.92         | 383.54      |

| Year | Load Growth | Required     | Forecasted | I no. of units | of DT per rate | ed capacity |
|------|-------------|--------------|------------|----------------|----------------|-------------|
| rear | (KW)        | Demand (KVA) | 15 KVA     | 25 KVA         | 37.5 KVA       | 50 KVA      |
| 2011 | 1,121.06    | 1,245.63     | 13         | 16             | 11             | 6           |
| 2012 | 1,215.57    | 1,350.63     | 14         | 18             | 11             | 7           |
| 2013 | 1,311.64    | 1,457.38     | 15         | 19             | 12             | 7           |
| 2014 | 1,408.84    | 1,565.38     | 16         | 20             | 13             | 8           |
| 2015 | 1,506.85    | 1,674.28     | 17         | 22             | 14             | 8           |

- The said simulation involves the following procedure:
  - 1. Determine the annual load growth of the entire DU through the demand forecast;
  - 2. Convert the annual demand forecast to apparent power (KVA);
  - 3. Determine the required KVA demand per DT rating using the annual forecasted KVA demand and the submitted percentage load sharing of each DT ratings presently installed within the distribution system; and
  - 4. Determine the required units for each DT rating by dividing the KVA demand per DT rating and the particular rating capacity of the DT.

### Cost Analysis

Shown below is the proposed project cost breakdown:

| No. | Materials    | Specifications | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-----|--------------|----------------|-----------------|-------------------------|------|-----------------------|
|     |              | 15kVA          | 16              | 80,843.62               |      | 1,293,497.86          |
| 1   | Distribution | 25kVA          | 20              | 102,011.62              | 0044 | 2,040,232.32          |
| 1   | Transformer  | 37.5kVA        | 13              | 127,413.22              | 2011 | 1,656,371.81          |
|     |              | 50kVA          | 8               | 139,509.22              | 1    | 1,116,073.73          |
|     |              | 15kVA          | 17              | 80,843.62               |      | 1,374,341.47          |
| 2   | Distribution | 25kVA          | 22              | 102,011.62              | 0040 | 2,244,255.55          |
| 2   | Transformer  | 37.5kVA        | 14              | 127,413.22              | 2012 | 1,783,785.02          |
|     |              | 50kVA          | 8               | 139,509.22              |      | 1,116,073.73          |
|     |              | 15kVA          | 19              | 80,843.62               |      | 1,536,028.70          |
| 3   | Distribution | 25kVA          | 24              | 102,011.62              | 2012 | 2,448,278.78          |
| 3   | Transformer  | 37.5kVA        | 16              | 127,413.22              | 2013 | 2,038,611.46          |
|     |              | 50kVA          | 9               | 139,509.22              |      | 1,255,582.94          |
|     |              | 15kVA          | 20              | 80,843.62               |      | 1,616,872.32          |
| 4   | Distribution | 25kVA          | 26              | 102,011.62              | 2014 | 2,652,302.02          |
|     | Transformer  | 37.5kVA        | 17              | 127,413.22              | 2014 | 2,166,024.67          |
|     |              | 50kVA          | 10              | 139,509.22              |      | 1,395,092.16          |
|     |              | 15kVA          | 21              | 80,843.62               |      | 1,697,715.94          |
| 5   | Distribution | 25kVA          | 27              | 102,011.62              | 2015 | 2,754,313.63          |
| 5   | Transformer  | 37.5kVA        | 18              | 127,413.22              | 2015 | 2,293,437.89          |
|     |              | 50kVA          | 10              | 139,509.22              |      | 1,395,092.16          |
|     |              |                |                 | Grand To                | otal | 35,873,984.16         |

 The Commission, on the other hand, approved the reduction of the proposed project cost primarily because the quantities of DTs to be acquired are to be adjusted. The basis for the project cost reduction also involved adjusting the unit costs of the DT per rating capacity in

# reference with the 2012 NEA price index.

Breakdown of the approved project cost is shown in the table below:

| No. | Materials                   | Specifications | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year   | Project Cost<br>(PhP) |
|-----|-----------------------------|----------------|-----------------|-------------------------|--------|-----------------------|
|     |                             | 15kVA          | 13              | 59,638.33               |        | 775,298.29            |
|     | Distribution                | 25kVA          | 16              | 77,380.00               | 2011   | 1,238,080.00          |
| 1   | Transformer                 | 37.5kVA        | 11              | 94,467.00               | 2011   | 1,039,137.00          |
|     |                             | 50kVA          | 6               | 110,435.00              |        | 662,610.00            |
|     |                             | 15kVA          | 14              | 59,638.33               |        | 834,936.62            |
| ~   | Distribution                | 25kVA          | 18              | 77,380.00               | 2012   | 1,392,840.00          |
| 2   | Transformer                 | 37.5kVA        | 11              | 94,467.00               | 2012   | 1,039,137.00          |
|     |                             | 50kVA          | 7               | 110,435.00              |        | 773,045.00            |
|     |                             | 15kVA          | 15              | 59,638.33               |        | 894,574.95            |
| •   | Distribution<br>Transformer | 25kVA          | 19              | 77,380.00               | 2013   | 1,470,220.00          |
| 3   |                             | 37.5kVA        | 12              | 94,467.00               |        | 1,133,604.00          |
|     |                             | 50kVA          | 7               | 110,435.00              |        | 773,045.00            |
|     |                             | 15kVA          | 16              | 59,638.33               |        | 954,213.28            |
|     | Distribution                | 25kVA          | 20              | 77,380.00               | 2014   | 1,547,600.00          |
| 4   | Transformer                 | 37.5kVA        | 13              | 94,467.00               | 2014   | 1,228,071.00          |
|     |                             | 50kVA          | 8               | 110,435.00              | 1      | 883,480.00            |
|     |                             | 15kVA          | 17              | 59,638.33               |        | 1,013,851.61          |
| ~   | Distribution                | 25kVA          | 22              | 77,380.00               | 1 2015 | 1,702,360.00          |
| 5   | Transformer                 | 37.5kVA        | 14              | 94,467.00               | 2015   | 1,322,538.00          |
|     |                             | 50kVA          | 8               | 110,435.00              | 1      | 883,480.00            |
|     |                             |                |                 | Grand To                | otal   | 21,562,121.75         |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed  |              |
| Project to continue with REVISED Capital Expenditure   | $\checkmark$ |
| Project to continue with Technical Amendments  | $\checkmark$ |
| Project to be deferred which may be included in its next application with additional justification |              |

| Approved C   | APEX Cost (  | (PhP)        |              |              |               |
|--------------|--------------|--------------|--------------|--------------|---------------|
| 2011         | 2012         | 2013         | 2014         | 2015         | Total         |
| 3,715,125.29 | 4,039,958.62 | 4,271,443.95 | 4,613,364.28 | 4,922,229.61 | 21,562,121.75 |

| Project Nos.     | 21 & 22                                    |
|------------------|--|
| Ducio et Title   | Open Secondary and Under Built Low Voltage |
| Project Title    | Distribution Lines                         |
| Project Code     | LVD-01 & LVD-02                            |
| Project Type     | Capacity                                   |
| Priority Rank    | 2  |
| Project Category | Secondary Distribution Line Project        |

| Project Description   | Duration     |
|---|--------------|
| <ul> <li>The following are the required specifications of the projects, to wit:         <ul> <li>a) The low voltage distribution lines are line to ground system with the nominal voltage of 240 volts;</li> <li>b) Open secondary lines are to be installed with 30 or 35 footer steel poles; and</li> <li>c) The secondary lines will be installed with either bare or insulated conductors.</li> </ul> </li> </ul> | 2011 to 2015 |

| Proposed C   | APEX Cost (  | PhP)         |              |               |               |
|--------------|--------------|--------------|--------------|---------------|---------------|
| 2011         | 2012         | 2013         | 2014         | 2015          | Total         |
| 7,684,879.02 | 8,316,974.15 | 8,965,581.64 | 9,626,707.77 | 10,297,553.48 | 44,891,696.07 |

 To accommodate the expected additional loads, CEBECO I proposed the expansion of its secondary network. This will provide secondary lines for the expected new residential consumers and other 230-volt customers.

#### **Technical Analysis**

- The forecasted secondary line expansions were based on the clustering analysis conducted by CEBECO I. The said analysis includes the following procedures, to wit:
  - 1. The secondary lines are classified into under-built lines and open secondary lines;
  - 2. They are further classified according to its location whether in the urban or rural areas;
  - 3. The average circuit-length of secondary lines for each capacity of the installed transformers and the assumed ratio for each line configuration in a specified area were based on its existing distribution line configuration, as shown in table 8.1; and
  - 4. The length of the secondary lines were then determined based on the forecasted number of transformers and using the ratio of capacities.

Table 8.1. Existing Low Voltage Distribution Data

| Capacity<br>(KVA) | Length<br>(km) |
|-------------------|----------------|
| 15                | 0.8            |
| 25                | 0.9            |
| 37.5              | 0.4            |
| 50                | 0.6            |

| Rural (existin | ng ratio/percentage) | Urban (existing ratio/percentage |                |  |  |
|----------------|----------------------|----------------------------------|----------------|--|--|
| Under-built    | Open Secondary       | Under-built                      | Open Secondary |  |  |
| 30%            | 70%                  | 80%                              | 20%            |  |  |

 The submitted forecasted secondary line length requirement which was determined based on the procedures discussed above is shown in the table below:

|      | Length Requirement (km) |       |  |  |  |
|------|-------------------------|-------|--|--|--|
| Year | Under-built             | Open  |  |  |  |
| 2011 | 17.24                   | 23.75 |  |  |  |
| 2012 | 18.66                   | 25.70 |  |  |  |
| 2013 | 20.12                   | 27.71 |  |  |  |
| 2014 | 21.60                   | 29.75 |  |  |  |
| 2015 | 23.11                   | 31.82 |  |  |  |

 Based on the review made by the Commission, however, said line length requirement should be reduced considering that the forecasted distribution transformers were reduced, as discussed in project nos. 17 to 20. The table below shows the approved line requirement for the projects:

| Veer | Length Requirement (km) |       |  |  |
|------|-------------------------|-------|--|--|
| Year | Under-built             | Open  |  |  |
| 2011 | 13.84                   | 18.96 |  |  |
| 2012 | 15.10                   | 20.90 |  |  |
| 2013 | 15.93                   | 22.17 |  |  |
| 2014 | 17.24                   | 23.56 |  |  |
| 2015 | 18.34                   | 25.46 |  |  |

#### Cost Analysis

- The determination by CEBECO I of the proposed project costs includes contingency factor of 5% and 7% of the material cost for the open secondary line project and under-built secondary line project, respectively. It also includes labor costs allotting 35% and 20% of the material cost for the open secondary line project and under-built secondary line project, respectively. It can also be noted that the required length for the open secondary line project was doubled considering that said configuration allegedly requires 2 main conductors.
- Shown in the table below is the proposed cumulative project cost breakdown:

| No | Project           | Materials   | Specifications        | Length<br>(km) | No. of<br>Units | Unit Cost<br>(PhP/unit/km) | Year | Project Cost<br>(PhP) |
|----|-------------------|-------------|-----------------------|----------------|-----------------|----------------------------|------|-----------------------|
| _  | Open              | Conductor   | #1/0 AWG Bare<br>ACSR | 47.50          | -               | 45,885.00                  | 0044 | 2,950,582.66          |
|    |                   | Poles       | 30 ft.                | -              | 240             | 9,879.22                   | 2011 | 3,209,820.97          |
| 4  | Secondary         | Accessories | -                     | -              | 240             | 1,453.27                   |      | 472,176.60            |
| I  | Line<br>Extension | Conductor   | #1/0 AWG Bare<br>ACSR | 51.41          | -               | 45,885.00                  | 2040 | 3,191,502.84          |
|    |                   | Poles       | 30 ft.                | -              | 260             | 9,879.22                   | 2012 | 3,475,378.02          |
|    |                   | Accessories | -                     | -              | 260             | 1,453.27                   |      | 511,241.03            |

|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 55.42 | -        | 45,885.00 | 2013       | 3,442,280.43 |
|---|----------------------------------|-------------|-----------------------|-------|----------|-----------|------------|--------------|
|   |                                  | Poles       | 30 ft.                | -     | 280      | 9,879.22  | 2013       | 3,744,765.50 |
|   |                                  | Accessories | -                     | -     | 280      | 1,453.27  |            | 550,868.93   |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 59.50 | -        | 45,885.00 | 2014       | 3,700,538.97 |
|   |                                  | Poles       | 30 ft.                | -     | 300      | 9,879.22  | 2014       | 4,017,050.27 |
|   | Accessories                      | -           | -                     | 300   | 1,453.27 |           | 590,923.03 |              |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 63.65 | -        | 45,885.00 | 2015       | 3,964,620.55 |
|   |                                  | Poles       | 30 ft.                | -     | 320      | 9,879.22  | 2013       | 4,291,571.65 |
|   |                                  | Accessories | -                     | -     | 320      | 1,453.27  |            | 631,306.15   |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 17.24 | -        | 46,759.00 | 2011       | 972,696.58   |
|   |                                  | Accessories | -                     | -     | 180      | 366.59    |            | 79,602.2     |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 18.66 | -        | 46,759.00 | 2012       | 1,054,670.62 |
|   |                                  | Accessories | -                     | -     | 190      | 366.59    |            | 84,181.64    |
| 2 | Under-built<br>Secondary<br>Line | Conductor   | #1/0 AWG Bare<br>ACSR | 20.12 | -        | 46,759.00 | 2013       | 1,134,797.63 |
|   | Extension                        | Accessories | -                     | -     | 210      | 366.59    |            | 92,869.1     |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 21.60 | -        | 46,759.00 | 2014       | 1,220,724.6  |
|   |                                  | Accessories | -                     | -     | 220      | 366.59    |            | 97,470.8     |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 23.11 | -        | 46,759.00 | 2015       | 1,303,879.0  |
|   |                                  | Accessories | -                     | -     | 240      | 366.59    |            | 106,176.1    |
|   |                                  |             |                       |       |          | Grand Tot |            | 44,891,696.0 |

The Commission approved the reduction of the proposed costs of the projects primarily due to the reduction of quantities for the forecasted additional DTs to be acquired, as previously discussed. The said assessment also involved the adjustment of the required major materials' unit costs in reference with the 2012 NEA price index and allowing only one (1) set of main conductor for both underbuilt and open secondary lines considering that the said line configurations only requires as such. The said lines also require one (1) set of ground wire but said material was already included in the accessories. Moreover, the labor cost was adjusted by allotting an acceptable margin of 20% of the material cost for consistency considering that both projects are similar in nature.

| No. | Project           | Materials   | Specifications        | Length<br>(km) | No. of<br>Units | Unit Cost<br>(PhP/unit/km) | Year | Project Cost<br>(PhP) |
|-----|-------------------|-------------|-----------------------|----------------|-----------------|----------------------------|------|-----------------------|
|     |                   | Conductor   | #1/0 AWG Bare<br>ACSR | 18.96          | -               | 30,140.00                  | 0011 | 685,745.28            |
|     |                   | Poles       | Steel, 30 ft.         | -              | 190             | 10,204.05                  | 2011 | 2,326,523.40          |
|     |                   | Accessories | -                     | -              | 190             | 1,453.27                   |      | 331,345.56            |
|     |                   | Conductor   | #1/0 AWG Bare<br>ACSR | 20.90          | -               | 30,140.00                  | 2012 | 755,911.20            |
|     | Open              | Poles       | Steel, 30 ft.         | -              | 210             | 10,204.05                  |      | 2,571,420.6           |
|     | Secondary         | Accessories | -                     | -              | 210             | 1,453.27                   |      | 366,224.0             |
| 1   | Line<br>Extension | Conductor   | #1/0 AWG Bare<br>ACSR | 22.17          | -               | 30,140.00                  |      | 801,844.5             |
|     |                   | Poles       | Steel, 30 ft.         | -              | 230             | 10,204.05                  | 2013 | 2,816,317.8           |
|     |                   | Accessories | -                     | -              | 230             | 1,453.27                   |      | 401,102.5             |
|     |                   | Conductor   | #1/0 AWG Bare<br>ACSR | 23.56          | -               | 30,140.00                  |      | 852,118.0             |
|     |                   | Poles       | Steel, 30 ft.         | -              | 240             | 10,204.05                  | 2014 | 2,938,766.4           |
|     | ]                 | Accessories |                       | -              | 240             | 1,453.27                   | ]    | 418,541.7             |

Breakdown of the approved project cost is shown in the table below:

|   |                                  |             |                       |       |     | Grand Tot | al   | 23,094,220.51 |
|---|----------------------------------|-------------|-----------------------|-------|-----|-----------|------|---------------|
|   | <u> </u>                         | Accessories | -                     | -     | 190 | 366.59    | 2015 | 83,582.06     |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 18.34 | -   | 30,140.00 | 2015 | 663,321.12    |
|   |                                  | Accessories | -                     | -     | 180 | 366.59    | 2014 | 79,183.01     |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 17.24 | -   | 30,140.00 | 2014 | 623,536.32    |
|   | Extension                        | Accessories | -                     | -     | 160 | 366.59    | 2013 | 70,384.90     |
| 2 | Under-built<br>Secondary<br>Line | Conductor   | #1/0 AWG Bare<br>ACSR | 15.93 | -   | 30,140.00 | 2013 | 576,156.24    |
|   |                                  | Accessories | •                     | -     | 150 | 366.59    | 2012 | 65,985.84     |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 15.10 | -   | 30,140.00 | 2012 | 546,136.80    |
|   | 1                                | Accessories | -                     |       | 140 | 366.59    | 2011 | 61,586.78     |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 13.84 | -   | 30,140.00 | 2011 | 500,565.12    |
|   |                                  | Accessories | -                     | -     | 260 | 1,453.27  |      | 453,420.24    |
|   |                                  | Poles       | Steel, 30 ft.         | -     | 260 | 10,204.05 | 2010 | 3,183,663.60  |
|   |                                  | Conductor   | #1/0 AWG Bare<br>ACSR | 25.46 | -   | 30,140.00 | 2015 | 920,837.28    |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed                          |              |
| Project to continue with REVISED Capital Expenditure     | $\checkmark$ |
| Project to continue with Technical Amendments            | $\checkmark$ |
| Project to be deferred which may be included in its next |              |
| application with additional justification                |              |

| Approved CAPEX Cost (PhP) |              |              |              |              |               |  |
|---------------------------|--------------|--------------|--------------|--------------|---------------|--|
| 2011                      | 2012         | 2013         | 2014         | 2015         | Total         |  |
| 3,905,766.14              | 4,305,678.48 | 4,665,806.02 | 4,912,145.57 | 5,304,824.30 | 23,094,220.51 |  |

# **II. OTHER NETWORK PROJECTS**

| Project Nos.     | 23 to 26                                       |
|------------------|--|
| Project Title    | Customer Service Drops and 60A, 100A & 3-phase |
|                  | KWh meters for Customer Metering Equipment     |
| Project Code     | SDM  |
| Project Type     | Capacity                                       |
| Priority Rank    | 2  |
| Project Category | Secondary Distribution Line Project            |

| Project Description  | Duration     |
|--|--------------|
| <ul> <li>The following are the required specifications of the projects, to wit:         <ul> <li>a) The service drop wire is a twisted bare and insulated duplex AWG #6 ACSR conductor. Consumers at low voltage have the same service drop wire size;</li> <li>b) The single phase KWH meters are rated 60A and 100A at 240V which are either bottom or socket connected type. The meters are either solid state or electromechanical with infrared communicator for specified meters; and</li> <li>c) Three-phase KWH meters are rated 20 up to 200A at 120-480V, bottom-connected type, with load profile and power quality monitoring features.</li> </ul> </li> </ul> | 2011 to 2015 |

| Proposed CAPEX Cost (PhP) |               |               |               |               |               |  |
|---------------------------|---------------|---------------|---------------|---------------|---------------|--|
| 2011                      | 2012          | 2013          | 2014          | 2015          | Total         |  |
| 16,351,408.84             | 17,702,149.34 | 19,093,051.34 | 20,514,973.90 | 21,904,781.30 | 95,566,364.72 |  |

## **Project Justification**

The DU is mandated to provide its customers the distribution services and connections in its distribution system consistent with the distribution code. As load growth dictates the addition of new equipments and assets, it is therefore necessary to forecast the number of new connections to determine the quantity of metering equipment and other materials the cooperative needs to prepare.

# **Technical Analysis**

The forecasting of the new customers were based on the 7-year historical customer data of CEBECO I. The customer types are forecasted separately to capture the best model fitted to each customer type. CEBECO I mainly focused on residential, commercial and industrial customer types for these particular projects. The chosen models passed and met all the criteria necessary to validate the accuracy of the forecasted model. Details of the forecast are discussed in item 3.2 of this memorandum.  The annual additional number of customers will then be identified by subtracting the forecasted number of customer in a year from the total number of customers of the previous year. Shown in the table below are the forecasted additional customer requirement of CEBECO I.

| Customer                      |        | Foi    | ecasted N | o. of Custo | mers    |         | L     | oad grov | wth / Red | quireme | nt    |
|-------------------------------|--------|--------|-----------|-------------|---------|---------|-------|----------|-----------|---------|-------|
| Class                         | 2010   | 2011   | 2012      | 2013        | 2014    | 2015    | 2011  | 2012     | 2013      | 2014    | 2015  |
| Residential                   | 75,861 | 81,550 | 87,709    | 94,354      | 101,495 | 109,142 | 5,689 | 6,159    | 6,645     | 7,141   | 7,647 |
| Commercial /<br>Public Bldgs. | 10,786 | 11,533 | 12,332    | 13,184      | 14,090  | 15,053  | 746   | 799      | 852       | 907     | 962   |
| Industrial                    | 28     | 28     | 28        | 28          | 28      | 28      | -     | -        | -         | -       | -     |
| Large Load                    | 2      | 2      | 2         | 2           | 2       | 2       | -     | -        | -         | -       | -     |
| Entire System                 | 86,677 | 93,113 | 100,071   | 107,568     | 115,615 | 124,225 | 6,435 | 6,958    | 7,497     | 8,048   | 8,609 |

The additional metering equipment and service drop wires required within the entire system were based on the forecasted load growth. The required metering equipment was then classified into three (3) based on specifications, as manifested in the table below. The quantity for the 60A KWh meters were based on 70% of the additional residential customers while the quantity for the 100A KWh meters were based on 30% of the additional residential customers and the commercial and public building customers.

|                                   | AS                  | PER AP | PLICAT   |       |       |       |       |          |       |       |       |
|-----------------------------------|---------------------|--------|----------|-------|-------|-------|-------|----------|-------|-------|-------|
|                                   | Motor Specification |        | Quantity |       |       |       |       | Quantity |       |       |       |
| Meter Specification               |                     | 2011   | 2012     | 2013  | 2014  | 2015  | 2011  | 2012     | 2013  | 2014  | 2015  |
| Single Phase, 60A,<br>mechanical  |                     | 3,982  | 4,312    | 4,652 | 4,999 | 5,353 | 3,982 | 4,312    | 4,652 | 4,999 | 5,353 |
| Single Phase, 100A,<br>mechanical |                     | 2,453  | 2,646    | 2,845 | 3,049 | 3,256 | 2,453 | 2,646    | 2,845 | 3,049 | 3,256 |
| _                                 | Sub-total           | 6,435  | 6,958    | 7,497 | 8,048 | 8,609 | 6,435 | 6,958    | 7,497 | 8,048 | 8,609 |
| 3-phase, electronic               |                     | 7      | 8        | 9     | 10    | 10    | -     | -        | -     | -     | -     |
|                                   | Grand Total         | 6,442  | 6,966    | 7,506 | 8,058 | 8,619 | 6,435 | 6,958    | 7,497 | 8,048 | 8,609 |

 There is no basis for the proposed quantity of 3-phase KWh meters as per perusal of the application. The proposed 60A and 100A KWh already covers 100% of the forecasted additional customers. It is therefore deferred.

#### Cost Analysis

- The determination of the proposed project costs by CEBECO I includes contingency factor and VAT of 5% and 12%, respectively. It also includes labor costs allotting 21%, 7%, 3% and 1% of the material costs for the service drop wires, 60A, 100A, and 3-phase KWh meter projects, respectively.
- The following is the cumulative proposed project cost breakdown:

| No. | Activity                     | Materials                | Specifications               | Length<br>(km) | No. of<br>Units | Unit Cost<br>(PhP/unit/km) | Year | Project Cost<br>(PhP) |
|-----|------------------------------|--------------------------|------------------------------|----------------|-----------------|----------------------------|------|-----------------------|
|     |                              | Conductor                | ACSR #6 TW                   | 193            | -               | 24,249.12                  |      | 5,677,362.98          |
| 1   | Customer<br>Service<br>Drops | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2 | -              | 12,870          | 50.78                      | 2011 | 792,591.44            |
|     |                              | Conductor                | ACSR #6 TW                   | 209            | -               | 24,249.12                  | 2012 | 6,138,516.14          |

|   |                     |                          |                                     |     | r      |           |      |              |
|---|---------------------|--------------------------|-------------------------------------|-----|--------|-----------|------|--------------|
|   |                     | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2        | -   | 13,916 | 50.78     |      | 856,970.99   |
|   |                     | Conductor                | ACSR #6 TW                          | 225 | -      | 24,249.12 | 0040 | 6,613,979.60 |
|   |                     | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2        | -   | 14,994 | 50.78     | 2013 | 923,348.33   |
|   |                     | Conductor                | ACSR #6 TW                          | 241 | -      | 24,249.12 | 0014 | 7,100,496.26 |
|   |                     | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2        | -   | 16,096 | 50.78     | 2014 | 991,268.76   |
|   |                     | Conductor                | ACSR #6 TW                          | 258 | -      | 24,249.12 | 0045 | 7,595,710.72 |
|   |                     | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2        | -   | 17,218 | 50.78     | 2015 | 1,060,403.46 |
|   |                     | KWh Meter                | Class 10, 10/60A,<br>240V           | -   | 3,982  | 1,216.87  |      | 5,180,810.76 |
|   |                     | Cooperative<br>Seal      | -                                   | -   | 7,964  | 2.18      | 2011 | 18,525.25    |
|   |                     | ERC Seal                 | -                                   | _   | 11,946 | 17.64     |      | 225,307.0    |
|   |                     | KWh Meter                | Class 10, 10/60A,<br>240V           | -   | 4,312  | 1,216.87  |      | 5,609,687.8  |
|   |                     | Cooperative<br>Seal      | -                                   | -   | 8,624  | 2.18      | 2012 | 20,058.8     |
|   |                     | ERC Seal                 | -                                   | -   | 12,936 | 17.64     |      | 243,958.4    |
|   | 2 60A KWh<br>meters | KWh Meter                | Class 10, 10/60A,<br>240V           | -   | 4,652  | 1,216.87  |      | 6,051,873.7  |
| 2 |                     | Cooperative<br>Seal      | -                                   | -   | 9,304  | 2.18      | 2013 | 21,639.9     |
|   |                     | ERC Seal                 | -                                   | -   | 13,956 | 17.64     |      | 263,188.5    |
|   |                     | KWh Meter                | Class 10, 10/60A,<br>240V           | -   | 4,999  | 1,216.87  |      | 6,504,339.1  |
|   |                     | Cooperative<br>Seal      | -                                   | -   | 9,998  | 2.18      | 2014 | 23,257.8     |
|   |                     | ERC Seal                 | -                                   | -   | 14,997 | 17.64     |      | 282,865.6    |
|   |                     | KWh Meter                | Class 10, 10/60A,<br>240V           | -   | 5,353  | 1,216.87  |      | 6,964,893.5  |
|   |                     | Cooperative<br>Seal      | -                                   | -   | 10,706 | 2.18      | 2015 | 24,904.6     |
|   |                     | ERC Seal                 | -                                   | -   | 16,059 | 17.64     | l    | 302,894.6    |
|   |                     | KWh meter                | Class 100, 15/100A,<br>240V         | -   | 2,453  | 1,581.72  |      | 4,005,445.1  |
|   |                     | Cooperative<br>Seal      | -                                   | -   | 4,906  | 2.18      | 2011 | 11,018.7     |
|   |                     | ERC Seal                 | -                                   | -   | 2,453  | 17.64     |      | 44,670.3     |
|   |                     | KWh meter                | Class 100, 15/100A,<br>240V         | -   | 2,646  | 1,581.72  |      | 4,320,682.8  |
|   |                     | Cooperative<br>Seal      | -                                   | -   | 5,292  | 2.18      | 2012 | 11,885.8     |
|   |                     | ERC Seal                 | -                                   | -   | 2,646  | 17.64     | 1    | 48,186.0     |
|   | 100A                | KWh meter                | Class 100, 15/100A, 240V            | -   | 2,845  | 1,581.72  |      | 4,645,702.7  |
| 3 | KWh<br>meters       | Cooperative<br>Seal      | -                                   | -   | 5,690  | 2.18      | 2013 | 12,780.0     |
|   |                     | ERC Seal                 | -                                   | -   | 2,845  | 17.64     | ĺ    | 51,810.8     |
|   |                     | KWh meter                | Class 100, 15/100A,<br>240V         | -   | 3,049  | 1,581.72  |      | 4,978,278.5  |
|   |                     | Cooperative<br>Seal      | -                                   | -   | 6,098  | 2.18      | 2014 | 13,694.8     |
|   |                     | ERC Seal                 | -                                   | -   | 3,049  | 17.64     |      | 55,519.8     |
|   | 9<br>2<br>2         | KWh meter                | Class 100, 15/100A,<br>240V         | -   | 3,256  | 1,581.72  |      | 5,316,799.9  |
|   |                     | Cooperative<br>Seal      | -                                   | -   | 6,512  | 2.18      | 2015 | 14,626.1     |
|   |                     | ERC Seal                 | -                                   | -   | 3,256  | 17.64     |      | 59,295.1     |
|   |                     | KWh meter                | electronic 3-phase,<br>50A,120-480V | -   | 7      | 56,150.51 |      | 395,522.1    |
| 4 | 3-phase<br>KWh      | Cooperative<br>Seal      | -                                   | -   | 14     | 2.18      | 2011 | 30.6         |
|   | meters              | ERC Seal                 | -                                   | -   | 7      | 17.64     |      | 124.2        |
|   |                     | KWh meter                | electronic 3-phase,                 |     | 8      | 56,150.51 | 2012 | 452,025.3    |

|  |                     | ·                                   |   |    | Grand To  | tal  | 95,566,364.72 |
|--|---------------------|-------------------------------------|---|----|-----------|------|---------------|
|  | ERC Seal            | -                                   | - | 10 | 17.64     |      | 177.51        |
|  | Cooperative<br>Seal | -                                   | - | 20 | 2.18      | 2015 | 43.79         |
|  | KWh meter           | electronic 3-phase,<br>50A,120-480V | - | 10 | 56,150.51 |      | 565,031.69    |
|  | ERC Seal            | -                                   | - | 10 | 17.64     |      | 177.51        |
|  | Cooperative<br>Seal | -                                   | - | 20 | 2.18      | 2014 | 43.79         |
|  | KWh meter           | electronic 3-phase,<br>50A,120-480V | - | 10 | 56,150.51 |      | 565,031.69    |
|  | ERC Seal            | •                                   | - | 9  | 17.64     |      | 159.76        |
|  | Cooperative<br>Seal | -                                   | - | 18 | 2.18      | 2013 | 39.41         |
|  | KWh meter           | electronic 3-phase,<br>50A,120-480V | - | 9  | 56,150.51 |      | 508,528.52    |
|  | ERC Seal            | -                                   | - | 8  | 17.64     |      | 142.01        |
|  | Cooperative<br>Seal | -                                   | - | 16 | 2.18      |      | 35.03         |

- The Commission approved the reduction of the proposed costs of the projects primarily due to the disapproval of the 3-phase electronic KWh meter project. The said assessment also involved the adjustment of the required major materials' unit costs in reference with the 2012 NEA price index. The said NEA price benchmark already included 5% contingency and 12% Value Added Tax (VAT). Moreover, the assessment also excluded the associated manpower or labor costs considering that the activity should be done by the EC.
- The following is the approved cumulative project cost breakdown:

| No. | Activity         | Materials                | Specifications               | Length<br>(km) | No. of<br>Units | Unit Cost<br>(PhP/unit/km) | Year      | Project Cost<br>(PhP) |
|-----|------------------|--------------------------|------------------------------|----------------|-----------------|----------------------------|-----------|-----------------------|
|     |                  | Conductor                | ACSR #6 TW                   | 193            |                 | 20,770.00                  |           | 4,009,648.50          |
|     |                  | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2 | -              | 12,870          | 39.35                      | 2011      | 506,434.5             |
|     |                  | Conductor                | ACSR #6 TW                   | 209            | -               | 20,770.00                  |           | 4,335,529.8           |
|     |                  | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2 | -              | 13,916          | 39.35                      | 2012      | 547,594.6             |
|     | Customer         | Conductor                | ACSR #6 TW                   | 225            | -               | 20,770.00                  |           | 4,671,380.7           |
| 1   | Service<br>Drops | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2 | - 14,994 39.35 |                 | 2013                       | 590,013.9 |                       |
|     |                  | Conductor                | ACSR #6 TW                   | 241            | -               | 20,770.00                  |           | 5,014,708.8           |
|     |                  | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2 | -              | 16,096          | 39.35                      | 2014      | 633,377.6             |
|     |                  | Conductor                | ACSR #6 TW                   | 258            | -               | 20,770.00                  |           | 5,364,267.9           |
|     |                  | Compression<br>Connector | #6-#1/0 ACSR run<br>to #6-#2 | -              | 17,218          | 39.35                      | 2015      | 677,528.3             |
|     |                  | KWh Meter                | Class 10, 10/60A,<br>240V    | -              | 3,982           | 818.57                     |           | 3,259,545.7           |
|     |                  | Cooperative<br>Seal      | -                            | -              | 7,964           | 2.18                       | 2011      | 17,326.4              |
|     |                  | ERC Seal                 | -                            | -              | 11,946          | 17.64                      |           | 70,242.4              |
| 2   | 60A KWh          | KWh Meter                | Class 10, 10/60A,<br>240V    | -              | 4,312           | 818.57                     |           | 3,529,673.8           |
| 2   | meters           | Cooperative<br>Seal      | -                            | -              | 8,624           | 2.18                       | 2012      | 18,762.3              |
|     |                  | ERC Seal                 | -                            | -              | 12,936          | 17.64                      |           | 76,063.6              |
|     |                  | KWh Meter                | Class 10, 10/60A,<br>240V    | -              | 4,652           | 818.57                     | 2013      | 3,807,987.6           |
|     |                  | Cooperative<br>Seal      | -                            | -              | 9,304           | 2.18                       | 2013      | 20,241.7              |

|   |                     | ERC Seal            | -                                      | -     | 13,956 | 17.64     |          | 82,061.28    |
|---|---------------------|---------------------|--|-------|--------|-----------|----------|--------------|
|   |                     | KWh Meter           | Class 10, 10/60A,<br>240V              | -     | 4,999  | 818.57    |          | 4,092,031.4  |
|   |                     | Cooperative<br>Seal | -                                      | -     | 9,998  | 2.18      | 2014     | 21,751.6     |
|   |                     | ERC Seal            | -                                      | -     | 14,997 | 17.64     |          | 88,182.3     |
|   |                     | KWh Meter           | Class 10, 10/60A,<br>240V              | -     | 5,353  | 818.57    |          | 4,381,805.2  |
|   |                     | Cooperative<br>Seal | -                                      | -     | 10,706 | 2.18      | 2015     | 23,291.9     |
|   |                     | ERC Seal            | -                                      | -     | 16,059 | 17.64     |          | 94,426.9     |
|   |                     | KWh meter           | Class 100,<br>15/100A, 240V            | -     | 2,453  | 1,581.72  |          | 3,879,959.1  |
|   | Cooperative<br>Seal | -                   | -                                      | 4,906 | 2.18   | 2011      | 10,673.4 |              |
|   | ERC Seal            | -                   | -                                      | 2,453 | 17.64  |           | 43,270.9 |              |
|   |                     | KWh meter           | Class 100,<br>15/100A, 240V            | -     | 2,646  | 1,581.72  |          | 4,185,231.1  |
|   |                     | Cooperative<br>Seal | -                                      | -     | 5,292  | 2.18      | 2012     | 11,513.2     |
|   |                     | ERC Seal            | •                                      | -     | 2,646  | 17.64     |          | 46,675.4     |
|   | 100A                | KWh meter           | Class 100,<br>15/100A, 240V            | -     | 2,845  | 1,581.72  |          | 4,499,993.4  |
| 3 | KWh<br>meters       | Cooperative<br>Seal | -                                      | -     | 5,690  | 2.18      | 2013     | 12,379.1     |
|   |                     | ERC Seal            | -                                      | -     | 2,845  | 17.64     |          | 50,185.8     |
|   |                     | KWh meter           | Class 100,<br>15/100A, 240V            | -     | 3,049  | 1,581.72  |          | 4,822,664.2  |
|   |                     | Cooperative<br>Seal | -                                      | -     | 6,098  | 2.18      | 2014     | 13,266.8     |
|   |                     | ERC Seal            | -                                      | -     | 3,049  | 17.64     |          | 53,784.3     |
|   |                     | KWh meter           | Class 100,<br>15/100A, 240V            | -     | 3,256  | 1,581.72  |          | 5,150,080.3  |
|   |                     | Cooperative<br>Seal | -                                      | -     | 6,512  | 2.18      | 2015     | 14,167.5     |
|   |                     | ERC Seal            | -                                      | -     | 3,256  | 17.64     |          | 57,435.8     |
|   |                     |                     | ······································ |       |        | Grand Tot |          | 68,785,160.3 |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed  |              |
| Project to continue with REVISED Capital Expenditure   | $\checkmark$ |
| Project to continue with Technical Amendments  | $\checkmark$ |
| Project to be deferred which may be included in its next application with additional justification |              |

| Approved C    | Approved CAPEX Cost (PhP) |               |               |               |               |  |  |  |  |  |
|---------------|---------------------------|---------------|---------------|---------------|---------------|--|--|--|--|--|
| 2011          | 2012                      | 2013          | 2014          | 2015          | Total         |  |  |  |  |  |
| 11,797,101.27 | 12,751,044.13             | 13,734,243.67 | 14,739,767.29 | 15,763,003.97 | 68,785,160.33 |  |  |  |  |  |

| Project No.      | 27  |
|------------------|---|
| Project Title    | Installation of Circuit Breaker for two (2) existing substations and replacement of AVR and Reclosers |
| Project Code     | OCR-01  |
| Project Type     | Safety  |
| Priority Rank    | 1   |
| Project Category | Primary Distribution Line Project   |

| Project Description  | Duration    |
|--|-------------|
| <ul> <li>The project intends to replace the existing protection<br/>equipment of both Dumanjug and Carcar1<br/>Substations from power fuse to power circuit<br/>breakers. The said equipment shall include protection<br/>relays and monitoring equipment.</li> </ul>  |             |
| <ul> <li>The project also includes replacement and upgrading<br/>the existing Reclosers. The said protective devices<br/>shall be installed along the midrange part of the<br/>primary distribution of the feeder.</li> </ul>  |             |
| <ul> <li>The project also includes replacement of the existing aged AVR.</li> </ul>  | 2011 & 2012 |
| <ul> <li>The said Reclosers and AVRs shall have the following specifications:         <ul> <li>a) Reclosers are three-phase at different ratings and a rated voltage of 13.2 kV with digital monitoring and controls;</li> <li>b) AVRs are rated 167 KVA single-phase at a rated voltage of 7.62 kV complete with digital control and monitoring; and</li> <li>c) The digital controls for the AVRs are universal with digital monitor.</li> </ul> </li> </ul> |             |

| Proposed CAPEX Cost (PhP) |               |      |      |      |               |  |  |  |  |
|---------------------------|---------------|------|------|------|---------------|--|--|--|--|
| 2011                      | 2012          | 2013 | 2014 | 2015 | Total         |  |  |  |  |
| 10,162,000.00             | 17,082,054.00 | -    | -    | -    | 27,244,054.00 |  |  |  |  |

- The installation of power circuit breaker shall comply with the safety standards required by the Philippine Grid and Distribution Codes.
- The replacement of the existing installed Reclosers and AVRs shall maintain a safe, reliable and efficient electric power service considering that these equipments are already beyond its standard asset life.

#### Technical Analysis

- The existing high voltage primary side protection of both the Dumanjug and Carcar1 Substations, which is power fuses, is not compliant with the safety provisions of the PGC. In order to comply with such requirement, CEBECO I shall install power circuit breaker and replace the existing power fuses. The presence of the proposed equipment will eliminate the possibility of exploding fuses during faults, thus, improving the standards of safety as well as reliability of the entire distribution system.
- At present, there are six (6) AVRs and (8) eight Reclosers installed with the system that requires replacement due to its condition. Based on CEBECO I inventories and inspection, the accounted equipments are already worn out and beyond their asset lives. These equipments could no longer provide the optimum performance needed in the operation.
- Consumers are subjected to unwanted outages and receiving poor power quality service due to failure of the said equipments. The distribution system is at risk in times when worn out Recloser failed to isolate the faulted lines.

#### **Cost Analysis**

 The proposed project cost is approved considering that the price for the required equipments are unavailable in both the NEA Price Index and the ERC Valuation Handbook. Moreover, the said cost of equipment is within the available price inquired in the internet as well as the previous applications of the Commission.

| No. | Materials                      | Specifications              | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-----|--------------------------------|-----------------------------|-----------------|-------------------------|------|-----------------------|
|     | Automatic Voltage Regulator    | 167kVA, 1-ph, 7.62kV        | 6               | 1,210,333.33            |      | 7,262,000.00          |
| 1   | AVR Control                    | Universal, digital          | 6               | 266,666.67              | 2011 | 1,600,000.00          |
|     | Automatic Recloser             | Vacuum, 630A                | 2               | 650,000.00              |      | 1,300,000.00          |
|     | Automatic Voltage Regulator    | 167kVA, 1-ph, 7.62kV        | 3               | 1,210,333.33            |      | 3,631,000.00          |
|     | AVR Control                    |                             | 3               | 266,666.67              |      | 800,000.00            |
|     | Automatic Recloser             | Vacuum, 630A                | 6               | 650,000.00              |      | 3,900,000.00          |
|     | Battery Charger                | with Battery Storage        | 2               | 558,481.00              |      | 1,116,962.00          |
| 2   | Multifunction Protection Relay | -                           | 2               | 237,211.00              | 2012 | 474,422.00            |
|     | Power Circuit Breaker          | 69kV, 1-ph                  | 2               | 1,950,180.00            |      | 3,900,360.00          |
|     | Transformer Differential Relay | -                           | 2               | 384,655.00              |      | 769,310.00            |
|     | Current Transformer            | 69kV,1-phase, CT substation | 2               | 870,000.00              |      | 1,740,000.00          |
|     | Potential Transformer          | 69kV,1-phase, PT substation | 1               | 750,000.00              |      | 750,000.00            |
|     |                                |                             |                 | Grand To                | tal  | 27,244,054.00         |

• The following is the proposed project cost breakdown:

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed                          | $\checkmark$ |
| Project to continue with REVISED Capital Expenditure     |              |
| Project to continue with Technical Amendments            |              |
| Project to be deferred which may be included in its next |              |
| application with additional justification                |              |

| Approved C    | APEX Cost (   | (PhP) |      |      |               |
|---------------|---------------|-------|------|------|---------------|
| 2011          | 2012          | 2013  | 2014 | 2015 | Total         |
| 10,162,000.00 | 17,082,054.00 | -     | -    | -    | 27,244,054.00 |

| Project Nos.     | 28 to 31  |
|------------------|---|
| Project Title    | Replacement of 60A KWh meter, 100A KWh meter,<br>KWh meter with infrared reading features and 3-<br>phase KWh meters with load profiling features |
| Project Code     | OCR-02 to OCR-05  |
| Project Type     | Efficiency  |
| Priority Rank    | 3   |
| Project Category | Secondary Distribution Line Project   |

#### **Project Description**

| Project Description   | Duration     |
|---|--------------|
| <ul> <li>The following are the required specifications of the proposed projects, to wit:         <ul> <li>a) The single phase KWH meters are rated 60A and 100A at 240V which are either bottom or socket connected type. The meters are either solid state or electromechanical with infrared communicator for specified meters; and</li> <li>b) Three-phase KWH meters are rated up to 50A at 120-480V, bottom-connected type, with load profile and power quality monitoring.</li> </ul> </li> </ul> | 2011 to 2015 |

# Proposed CAPEX Cost (PhP) 2011 2012 2013 2014 20

| 2011         | 2012          | 2013         | 2014          | 2015         | Total         |
|--------------|---------------|--------------|---------------|--------------|---------------|
| 1,471,368.45 | 11,286,440.85 | 1,471,368.45 | 11,286,440.85 | 1,471,368.45 | 26,986,987.06 |
|              |               |              |               |              |               |

#### **Project Justification**

 CEBECO I intends to replace the existing old and dilapidated KWh meters of various specifications in order to improve the efficiency of the distribution system.

#### Technical Analysis

- Based on CEBECO I site survey, some of its existing installed KWh meters have exceeded their operational life which leads to the ineffectiveness of the meters and can no longer operate reliably. The presence of these meters contributes to the continuous amplification of unaccounted losses or high non-technical losses of the distribution utility.
- In order to reduce technical system losses, CEBECO I proposed to purchase new KWh meters to replace these assets with brand new meters with the same specifications accordingly. The probable advantage in terms of the entire system efficiency is shown in the table below. The energy saved was based on the probable accuracy improvement brought about by replacing each defective/aged KWh meter which will then be multiplied by the total number of proposed KWh meters.

| Vaar | Technical Syste | em Loss (KWh) | No. of | Energy Saved |
|------|-----------------|---------------|--------|--------------|
| Year | Existing        | With Project  | meters | (KWh)        |
| 2011 | 7,888,412.01    | 7,834,129.93  | 805    | 54,282.08    |
| 2012 | 8,156,544.06    | 7,765,106.24  | 5,805  | 391,437.82   |
| 2013 | 8,365,738.54    | 8,311,456.46  | 805    | 54,282.08    |
| 2014 | 8,981,291.68    | 8,589,853.86  | 5,805  | 391,437.82   |
| 2015 | 9,522,128.83    | 9,467,846.75  | 805    | 54,282.08    |

#### Economic and Cost Analysis

Based on CEBECO I's assessment, the proposed project is viable considering that the project's Net Present Value (NPV) is positive and the Benefit-Cost Ratio is greater than one (1), as manifested in the determined usina table below. The assessment was the abovementioned technical benefits while incorporating some significant variables such as its asset life and discount rate of 10 years and 8%, respectively. The discount rate shall be the NEA interest rate considering that the projects will be funded through NEA loan.

| B/C                          | 1.20          |
|------------------------------|---------------|
| Discount Rate (cost of debt) | 8%            |
| PV of Benefits               | 30,388,884.22 |
| PV of Cost                   | 25,283,333.62 |
| Total Benefits (NPV)         | 5,105,550.59  |

- CEBECO I determined the proposed project costs by including contingency factor and VAT of 5% and 12%, respectively. It also includes labor costs allotting 7%, 5.5%, 4.7% and 1% of the material costs for the 60A, 100A, electronic single-phase and 3-phase KWh meter projects, respectively.
- The following is the proposed cumulative project cost breakdown wit:

| Activity          | Materials        | Specifications           | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-------------------|------------------|--------------------------|-----------------|-------------------------|------|-----------------------|
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 1,216.87                |      | 650,550.75            |
|                   | Cooperative Seal | -                        | 1,000           | 2.18                    | 2011 | 2,326.20              |
|                   | ERC Seal         | -                        | 1,500           | 17.64                   |      | 28,291.65             |
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 1,216.87                |      | 650,550.75            |
|                   | Cooperative Seal | -                        | 1,000           | 2.18                    | 2012 | 2,326.20              |
|                   | ERC Seal         | -                        | 1,500           | 17.64                   |      | 28,291.65             |
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 1,216.87                |      | 650,550.75            |
| 60A KWh<br>meters | Cooperative Seal | -                        | 1,000           | 2.18                    | 2013 | 2,326.20              |
| meters            | ERC Seal         | -                        | 1,500           | 17.64                   |      | 28,291.6              |
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 1,216.87                |      | 650,550.7             |
|                   | Cooperative Seal | -                        | 1,000           | 2.18                    | 2014 | 2,326.20              |
|                   | ERC Seal         | -                        | 1,500           | 17.64                   |      | 28,291.6              |
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 1,216.87                |      | 650,550.7             |
|                   | Cooperative Seal | -                        | 1,000           | 2.18                    | 2015 | 2,326.2               |
|                   | ERC Seal         | -                        | 1,500           | 17.64                   |      | 28,291.6              |
|                   | KWh meter        | Class 100, 15/100A, 240V | 300             | 1,581.72                | •    | 500,613.1             |
|                   | Cooperative Seal | -                        | 600             | 2.18                    | 2011 | 1,377.1               |
|                   | ERC Seal         | -                        | 300             | 17.64                   |      | 5,583.0               |
| 100A              | KWh meter        | Class 100, 15/100A, 240V | 300             | 1,581.72                |      | 500,613.1             |
| KWh               | Cooperative Seal | -                        | 600             | 2.18                    | 2012 | 1,377.1               |
| meters            | ERC Seal         | -                        | 300             | 17.64                   |      | 5,583.0               |
|                   | KWh meter        | Class 100, 15/100A, 240V | 300             | 1,581.72                |      | 500,613.1             |
|                   | Cooperative Seal | •                        | 600             | 2.18                    | 2013 | 1,377.1               |
|                   | ERC Seal         | -                        | 300             | 17.64                   |      | 5,583.0               |

|                       |                               |                                       |            | Grand To  | otal | 26,986,987.00        |
|-----------------------|-------------------------------|---------------------------------------|------------|-----------|------|----------------------|
|                       | ERC Seal                      | -                                     | 5          | 17.64     |      | 88.7                 |
|                       | Cooperative Seal              | -                                     | 10         | 2.18      | 2015 | 21.89                |
|                       | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5          | 56,150.51 |      | 282,515.8            |
|                       | ERC Seal                      | -                                     | 5          | 17.64     |      | 88.7                 |
|                       | Cooperative Seal              | -                                     | 10         | 2.18      | 2014 | 21.8                 |
|                       | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5          | 56,150.51 |      | 282,515.8            |
| meters                | ERC Seal                      | -                                     | 5          | 17.64     |      | 88.7                 |
| electronic<br>KWh     | Cooperative Seal              | -                                     | 10         | 2.18      | 2013 | 21.8                 |
| 3-phase               | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5          | 56,150.51 |      | 282,515.8            |
|                       | ERC Seal                      | -                                     | 5          | 17.64     |      | 88.7                 |
|                       | Cooperative Seal              | •                                     | 10         | 2.18      | 2012 | 21.8                 |
|                       | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5          | 56,150.51 |      | 282,515.8            |
|                       | ERC Seal                      | -                                     | 5          | 17.64     | 1    | 88.7                 |
|                       | Cooperative Seal              | -                                     | 10         | 2.18      | 2011 | 21.8                 |
|                       | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5          | 56,150.51 |      | 282,515.8            |
|                       | ERC Seal                      | •                                     | 5,000      | 17.64     | 1    | 92,349.3             |
| meters                | Cooperative Seal              | -                                     | 10,000     | 2.18      | 2014 | 22,779.5             |
| KWh                   | KWh meter                     | Electronic 1-ph, 15A, 240V            | 5,000      | 1,852.82  |      | 9,699,943.5          |
| 1-phase<br>electronic | ERC Seal                      | -                                     | 5,000      | 17.64     |      | 92,349.3             |
| 1-nhaca               | Cooperative Seal              | • • • • • • • • • • • • • • • • • • • | 10,000     | 2.18      | 2012 | 22,779.5             |
|                       | KWh meter                     | Electronic 1-ph, 15A, 240V            | 5,000      | 1,852.82  |      | 9,699,943.5          |
|                       | ERC Seal                      | -                                     | 300        | 17.64     |      | 5,583.0              |
|                       | Cooperative Seal              | -                                     | 600        | 2.18      | 2015 | 1,377.1              |
|                       | KWh meter                     | Class 100, 15/100A, 240V              | 300        | 1,581.72  |      | 500,613.1            |
|                       | ERC Seal                      | -                                     | 300        | 17.64     |      | 5,583.0              |
|                       | KWh meter<br>Cooperative Seal | Class 100, 15/100A, 240V              | 300<br>600 | 1,581.72  | 2014 | 500,613.1<br>1,377.1 |

- The Commission approved the reduction of the proposed costs of the projects based on its review. The said assessment involves adjusting of the required major materials' unit costs in reference with the 2012 NEA price index. The said NEA price benchmark already included 5% contingency and 12% Value Added Tax (VAT). Moreover, the assessment also excluded the associated manpower or labor costs considering that the activity should be done by the EC.
- The following is the approved cumulative project cost breakdown:

| Activity          | Materials        | Specifications           | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-------------------|------------------|--------------------------|-----------------|-------------------------|------|-----------------------|
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 818.57                  |      | 409,285.00            |
|                   | Cooperative Seal | -                        | 1,000           | 2.18                    | 2011 | 2,175.60              |
|                   | ERC Seal         | -                        | 500             | 17.64                   |      | 8,820.00              |
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 818.57                  |      | 409,285.00            |
|                   | Cooperative Seal | -                        | 1,000           | 2.18                    | 2012 | 2,175.60              |
|                   | ERC Seal         | -                        | 500             | 17.64                   |      | 8,820.00              |
| 004 1044          | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 818.57                  |      | 409,285.00            |
| 60A KWh<br>meters | Cooperative Seal | -                        | 1,000           | 2.18                    | 2013 | 2,175.60              |
| metera            | ERC Seal         | -                        | 500             | 17.64                   |      | 8,820.00              |
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 818.57                  |      | 409,285.00            |
|                   | Cooperative Seal | -                        | 1,000           | 2.18                    | 2014 | 2,175.60              |
|                   | ERC Seal         | •                        | 500             | 17.64                   |      | 8,820.00              |
|                   | KWh Meter        | Class 10, 10/60A, 240V   | 500             | 818.57                  |      | 409,285.00            |
|                   | Cooperative Seal | -                        | 1,000           | 2.18                    | 2015 | 2,175.60              |
|                   | ERC Seal         | -                        | 500             | 17.64                   |      | 8,820.00              |
|                   | KWh meter        | Class 100, 15/100A, 240V | 300             | 1,581.72                |      | 474,516.00            |
|                   | Cooperative Seal | -                        | 600             | 2.18                    | 2011 | 1,305.36              |
| 100A<br>KWh       | ERC Seal         | -                        | 300             | 17.64                   |      | 5,292.00              |
| meters            | KWh meter        | Class 100, 15/100A, 240V | 300             | 1,581.72                |      | 474,516.00            |
|                   | Cooperative Seal | -                        | 600             | 2.18                    | 2012 | 1,305.36              |
|                   | ERC Seal         | •                        | 300             | 17.64                   |      | 5,292.00              |

|                       |                               |                                       |            |                  | I    |              |
|-----------------------|-------------------------------|---------------------------------------|------------|------------------|------|--------------|
|                       | ERC Seal                      | -                                     | 5          | 17.64            |      | 88.20        |
|                       | Cooperative Seal              | -                                     | 10         | 2.18             | 2015 | 21.76        |
| meters                | KWh meter                     | electronic 3-phase, 50A, 120-480V     | 5          | 28,000.00        |      | 140,000.00   |
|                       | ERC Seal                      | -                                     | 5          | 17.64            | 1    | 88.20        |
|                       | Cooperative Seal              | -                                     | 10         | 2.18             | 2014 | 21.76        |
|                       | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5          | 28,000.00        |      | 140,000.00   |
| KWh                   | ERC Seal                      |                                       | 5          | 17.64            | 2010 | 88.20        |
| electronic            | Cooperative Seal              | -                                     | 10         | 2.18             | 2013 | 21.76        |
| 3-phase               | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5          | 28,000.00        |      | 140,000.00   |
|                       | ERC Seal                      |                                       | 5          | 17.64            |      | 88.20        |
|                       | Cooperative Seal              | -                                     | 10         | 2.18             | 2012 | 21.76        |
|                       | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5          | 28,000.00        |      | 140,000.00   |
|                       | ERC Seal                      | -                                     | 5          | 17.64            |      | 88.20        |
|                       | Cooperative Seal              | -                                     | 10         | 2.18             | 2011 | 21.76        |
|                       | KWh meter                     | electronic 3-phase, 50A,120-480V      | 5,000      | 28,000.00        |      | 140,000.00   |
|                       | ERC Seal                      |                                       | 5,000      | 17.64            |      | 88,200.00    |
| meters                | Cooperative Seal              | -                                     | 10,000     | 2.18             | 2014 | 21,756.00    |
| KWh                   | KWh meter                     | Electronic 1-ph, 15A, 240V            | 5,000      | 1,852.82         |      | 9,264,116.40 |
| 1-phase<br>electronic | ERC Seal                      | · · · · · · · · · · · · · · · · · · · | 5,000      | 17.64            |      | 88,200.00    |
|                       | Cooperative Seal              | -                                     | 10,000     | 2.18             | 2012 | 21,756.00    |
|                       | KWh meter                     | Electronic 1-ph, 15A, 240V            | 5.000      | 1,852.82         |      | 9,264,116.40 |
|                       | ERC Seal                      |                                       | 300        | 17.64            |      | 5,292.00     |
|                       | Cooperative Seal              | -                                     | 600        | 2.18             | 2015 | 1,305.36     |
|                       | KWh meter                     | Class 100, 15/100A, 240V              | 300        | 1,581.72         |      | 474,516.00   |
|                       | ERC Seal                      |                                       | 300        | 17.64            | 2014 | 5,292.00     |
|                       | Cooperative Seal              |                                       | 600        | 2.18             | 2014 | 1,305.36     |
|                       | KWh meter                     | -<br>Class 100, 15/100A, 240V         | 300        | 1,581.72         |      | 474,516.00   |
|                       | ERC Seal                      |                                       | 300        | 17.64            | 2015 | 5,292.00     |
|                       | KWh meter<br>Cooperative Seal | Class 100, 15/100A, 240V              | 300<br>600 | 1,581.72<br>2.18 | 2013 | 474,516.00   |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed                          |              |
| Project to continue with REVISED Capital Expenditure     | $\checkmark$ |
| Project to continue with Technical Amendments            | $\checkmark$ |
| Project to be deferred which may be included in its next |              |
| application with additional justification                |              |

| Approved C   | APEX Cost (   | (PhP)        |               |              |               |
|--------------|---------------|--------------|---------------|--------------|---------------|
| 2011         | 2012          | 2013         | 2014          | 2015         | Total         |
| 1,041,503.92 | 10,415,576.32 | 1,041,503.92 | 10,415,576.32 | 1,041,503.92 | 23,955,664.38 |

| Project Nos.     | 32 & 33  |
|------------------|--|
| Project Title    | Replacement of aging poles with concrete poles and steel poles preferably along 3-phase system |
| Project Code     | OCR-06 & OCR-07  |
| Project Type     | Safety   |
| Priority Rank    | 1  |
| Project Category | Primary Distribution Line Project  |

| Project Description   | Duration     |
|---|--------------|
| <ul> <li>Aging wood poles shall be replaced with the following specifications, to wit:         <ul> <li>a) New steel poles with length varying from 30 to 40 feet; and</li> <li>b) New concrete poles with length varying from 35 up to 55 feet.</li> </ul> </li> </ul> | 2011 to 2015 |

| Proposed C   | APEX Cost (  | PhP)         |              |              |               |
|--------------|--------------|--------------|--------------|--------------|---------------|
| 2011         | 2012         | 2013         | 2014         | 2015         | Total         |
| 3,807,569.43 | 3,807,569.43 | 3,807,569.43 | 3,807,569.43 | 3,807,569.43 | 19,037,847.15 |

 CEBECO I intends to replace its existing old and damaged poles in order to maintain a safe, efficient and reliable distribution system.

#### **Technical Analysis**

- Based on CEBECO I site survey, it was determined that some of the existing poles within the distribution system are already aged, decaying, and damaged. These distribution network assets are threat to public safety and a contributing factor to the inefficiency and unreliability of the distribution system. It also contributes to the distribution system's continuous amplification of unaccounted losses or non-technical losses.
- The proposed projects will provide an assurance of eliminating hazard and reducing nuisance interruptions caused by these assets. It will also provide efficiency and reliability improvement in the distribution system.

#### Cost Analysis

- CEBECO I determined the quantity of poles which requires replacement based on the actual inventory done by the cooperative. The determination of the proposed project costs includes contingency factor and VAT of 5% and 12%, respectively. It also includes labor costs allotting 19% for both proposed projects.
- The following is the proposed project cost breakdown:

| No. | Activity       | Materials | Specifications  | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-----|----------------|-----------|-----------------|-----------------|-------------------------|------|-----------------------|
|     |                | Pole      | 35 ft. concrete | 15              | 21,168.00               |      | 378,000.00            |
|     |                | Pole      | 40 ft. concrete | 30              | 25,872.00               |      | 924,000.00            |
|     |                | Pole      | 45 ft. concrete | 15              | 31,620.29               | 2011 | 564,648.00            |
|     |                | Pole      | 50 ft. concrete | 10              | 33,122.17               |      | 394,311.54            |
|     |                | Pole      | 55 ft. concrete | 7               | 38,205.89               |      | 318,382.40            |
|     |                | Pole      | 35 ft. concrete | 15              | 21,168.00               |      | 378,000.00            |
|     |                | Pole      | 40 ft. concrete | 30              | 25,872.00               |      | 924,000.00            |
|     |                | Pole      | 45 ft. concrete | 15              | 31,620.29               | 2012 | 564,648.00            |
|     |                | Pole      | 50 ft. concrete | 10              | 33,122.17               |      | 394,311.54            |
|     |                | Pole      | 55 ft. concrete | 7               | 38,205.89               |      | 318,382.40            |
|     |                | Pole      | 35 ft. concrete | 15              | 21,168.00               |      | 378,000.00            |
|     | Damaged poles  | Pole      | 40 ft. concrete | 30              | 25,872.00               |      | 924,000.00            |
| 1   | replaced with  | Pole      | 45 ft. concrete | 15              | 31,620.29               | 2013 | 564,648.00            |
|     | concrete poles | Pole      | 50 ft. concrete | 10              | 33,122.17               |      | 394,311.54            |
|     |                | Pole      | 55 ft. concrete | 7               | 38,205.89               |      | 318,382.40            |
|     |                | Pole      | 35 ft. concrete | 15              | 21,168.00               |      | 378,000.00            |
|     |                | Pole      | 40 ft. concrete | 30              | 25,872.00               |      | 924,000.00            |
|     |                | Pole      | 45 ft. concrete | 15              | 31,620.29               | 2014 | 564,648.00            |
|     |                | Pole      | 50 ft. concrete | 10              | 33,122.17               |      | 394,311.54            |
|     |                | Pole      | 55 ft. concrete | 7               | 38,205.89               |      | 318,382.40            |
|     |                | Pole      | 35 ft. concrete | 15              | 21,168.00               |      | 378,000.00            |
|     |                | Pole      | 40 ft. concrete | 30              | 25,872.00               | 2015 | 924,000.00            |
|     |                | Pole      | 45 ft. concrete | 15              | 31,620.29               |      | 564,648.00            |
|     |                | Pole      | 50 ft. concrete | 10              | 33,122.17               |      | 394,311.54            |
|     |                | Pole      | 55 ft. concrete | 7               | 38,205.89               |      | 318,382.40            |
|     |                | Pole      | 30 ft. steel    | 30              | 11,617.96               |      | 414,927.24            |
|     |                | Pole      | 35 ft. steel    | 20              | 18,816.00               | 2011 | 448,000.00            |
|     |                | Pole      | 40 ft. steel    | 15              | 20,456.81               |      | 365,300.25            |
|     |                | Pole      | 30 ft. steel    | 30              | 11,617.96               |      | 414,927.24            |
|     |                | Pole      | 35 ft. steel    | 20              | 18,816.00               | 2012 | 448,000.00            |
|     |                | Pole      | 40 ft. steel    | 15              | 20,456.81               |      | 365,300.25            |
|     | Damaged poles  | Pole      | 30 ft. steel    | 30              | 11,617.96               |      | 414,927.24            |
| 2   | replaced with  | Pole      | 35 ft. steel    | 20              | 18,816.00               | 2013 | 448,000.00            |
|     | steel poles    | Pole      | 40 ft. steel    | 15              | 20,456.81               |      | 365,300.25            |
|     |                | Pole      | 30 ft. steel    | 30              | 11,617.96               |      | 414,927.24            |
|     |                | Pole      | 35 ft. steel    | 20              | 18,816.00               | 2014 | 448,000.00            |
|     |                | Pole      | 40 ft. steel    | 15              | 20,456.81               |      | 365,300.25            |
|     |                | Pole      | 30 ft. steel    | 30              | 11,617.96               |      | 414,927.24            |
|     |                | Pole      | 35 ft. steel    | 20              | 18,816.00               | 2015 | 448,000.00            |
|     |                | Pole      | 40 ft. steel    | 15              | 20,456.81               |      | 365,300.25            |
|     |                |           |                 |                 | Grand To                |      | 19,037,847.15         |

- The Commission approved the reduction of the proposed costs of the projects based on its review. The said assessment involves adjusting of the required major materials' unit costs in reference with the 2012 NEA price index. The said NEA price benchmark already included 5% contingency and 12% Value Added Tax (VAT). Moreover, the assessment also includes the exclusion of the associated manpower or labor costs considering that the activity should be done by the administration.
- The following is the approved cumulative project cost breakdown:

| No. | Activity                        | Materials | Specifications  | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-----|---------------------------------|-----------|-----------------|-----------------|-------------------------|------|-----------------------|
|     |                                 | Pole      | 35 ft. concrete | 15              | 12,303.89               | 2011 | 184,558.35            |
| 4   | Damaged poles                   | Pole      | 40 ft. concrete | 30              | 19,622.00               |      | 588,660.00            |
| 1   | replaced with<br>concrete poles | Pole      | 45 ft. concrete | 15              | 20,420.75               |      | 306,311.25            |
|     | concrete poles                  | Pole      | 50 ft. concrete | 10              | 24,522.32               |      | 245,223.20            |

|   | T             | Pole | 55 ft. concrete | 7        | 26,843.44 |      | 187,904.08 |
|---|---------------|------|-----------------|----------|-----------|------|------------|
|   |               | Pole | 35 ft. concrete | 15       | 12.303.89 |      | 184,558.35 |
|   |               | Pole | 40 ft. concrete |          |           |      |            |
|   |               |      |                 | 30<br>15 | 19,622.00 | 2012 | 588,660.00 |
|   |               | Pole | 45 ft. concrete |          | 20,420.75 | 2012 | 306,311.25 |
|   |               | Pole | 50 ft. concrete | 10       | 24,522.32 |      | 245,223.20 |
|   |               | Pole | 55 ft. concrete | 7        | 26,843.44 |      | 187,904.08 |
|   |               | Pole | 35 ft. concrete | 15       | 12,303.89 |      | 184,558.35 |
|   |               | Pole | 40 ft. concrete | 30       | 19,622.00 |      | 588,660.00 |
|   |               | Pole | 45 ft. concrete | 15       | 20,420.75 | 2013 | 306,311.25 |
|   |               | Pole | 50 ft. concrete | 10       | 24,522.32 |      | 245,223.20 |
|   |               | Pole | 55 ft. concrete | 7        | 26,843.44 |      | 187,904.08 |
|   |               | Pole | 35 ft. concrete | 15       | 12,303.89 |      | 184,558.35 |
|   |               | Pole | 40 ft. concrete | 30       | 19,622.00 |      | 588,660.00 |
|   |               | Pole | 45 ft. concrete | 15       | 20,420.75 | 2014 | 306,311.25 |
|   |               | Pole | 50 ft. concrete | 10       | 24,522.32 |      | 245,223.20 |
|   |               | Pole | 55 ft. concrete | 7        | 26,843.44 |      | 187,904.08 |
|   |               | Pole | 35 ft. concrete | 15       | 12,303.89 |      | 184,558.35 |
|   |               | Pole | 40 ft. concrete | 30       | 19,622.00 |      | 588,660.00 |
|   |               | Pole | 45 ft. concrete | 15       | 20,420.75 | 2015 | 306,311.25 |
|   |               | Pole | 50 ft. concrete | 10       | 24,522.32 |      | 245,223.20 |
|   |               | Pole | 55 ft. concrete | 7        | 26,843.44 |      | 187,904.08 |
|   |               | Pole | 30 ft. steel    | 30       | 10,204.05 |      | 306,121.50 |
|   |               | Pole | 35 ft. steel    | 20       | 12,716.92 | 2011 | 254,338.40 |
|   |               | Pole | 40 ft. steel    | 15       | 17,395.25 |      | 260,928.75 |
|   |               | Pole | 30 ft. steel    | 30       | 10,204.05 |      | 306,121.50 |
|   |               | Pole | 35 ft. steel    | 20       | 12,716.92 | 2012 | 254,338.40 |
|   |               | Pole | 40 ft. steel    | 15       | 17,395.25 |      | 260,928.75 |
|   | Damaged poles | Pole | 30 ft. steel    | 30       | 10,204.05 |      | 306,121.50 |
| 2 | replaced with | Pole | 35 ft. steel    | 20       | 12,716.92 | 2013 | 254,338.40 |
|   | steel poles   | Pole | 40 ft. steel    | 15       | 17,395.25 | 2014 | 260,928.75 |
|   |               | Pole | 30 ft. steel    | 30       | 10,204.05 |      | 306,121.50 |
|   |               | Pole | 35 ft. steel    | 20       | 12,716.92 |      | 254,338.40 |
|   |               | Pole | 40 ft. steel    | 15       | 17,395.25 |      | 260,928.75 |
|   |               | Pole | 30 ft. steel    | 30       | 10,204.05 |      | 306,121.50 |
|   |               | Pole | 35 ft. steel    | 20       | 12,716.92 | 2015 | 254,338.40 |
|   |               | Pole | 40 ft. steel    | 15       | 17,395.25 |      | 260,928.75 |
|   |               |      |                 |          |           |      |            |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed  |              |
| Project to continue with REVISED Capital Expenditure   | $\checkmark$ |
| Project to continue with Technical Amendments  |              |
| Project to be deferred which may be included in its next application with additional justification |              |

| Approved C   | APEX Cost (  | PhP)         |              |              |               |
|--------------|--------------|--------------|--------------|--------------|---------------|
| 2011         | 2012         | 2013         | 2014         | 2015         | Total         |
| 2,334,045.53 | 2,334,045.53 | 2,334,045.53 | 2,334,045.53 | 2,334,045.53 | 11,670,227.65 |

.

| Project No.      | 34                                  |
|------------------|-------------------------------------|
| Project Title    | Rural Electrification Project       |
| Project Code     | -                                   |
| Project Type     | Rural Electrification               |
| Priority Rank    | 2                                   |
| Project Category | Secondary Distribution Line Project |

| Project Description   | Duration |
|---|----------|
| <ul> <li>CEBECO I will construct secondary distribution line<br/>extension in far-flung areas within its franchise. A<br/>potential 313 locations with approximately 3,178<br/>customers are expected to be served through this<br/>project.</li> </ul> |          |

| Proposed CAPEX Cost (PhP) |               |               |               |               |               |  |
|---------------------------|---------------|---------------|---------------|---------------|---------------|--|
| 2011                      | 2012          | 2013          | 2014          | 2015          | Total         |  |
| 10,543,000.00             | 19,372,000.00 | 19,372,000.00 | 13,702,000.00 | 28,408,000.00 | 91,397,000.00 |  |

 The construction of distribution line extension to energize customers located at far-flung areas or sitios is a mandate of the cooperative.

#### **Technical Analysis**

 The project shall execute the said obligation through providing missionary electrification within the remotest and the countryside areas of the franchise.

#### **Economic and Cost Analysis**

- The project shall be subsidized by the Department of Energy (DOE), Congressional funds, concerned LGU, and NEA.
- The proposed project cost is approved considering that the required material unit costs are close with the NEA price benchmark.
- The following is the proposed project cost breakdown:

| Year  |        | Line Le | ngth (kn | ר)        | Project Cost (PhP) |               |               |               |  |
|-------|--------|---------|----------|-----------|--------------------|---------------|---------------|---------------|--|
| rear  | 1-Ph   | OS      | UB       | Sub-total | 1-Ph               | OS            | UB            | Sub-total     |  |
| 2011  | 9.44   | 18.66   | 8.74     | 36.85     | 6,266,911.49       | 2,971,334.36  | 1,304,754.15  | 10,543,000.00 |  |
| 2012  | 29.04  | 22.66   | 24.43    | 76.13     | 12,119,726.45      | 3,606,900.28  | 3,645,373.26  | 19,372,000.00 |  |
| 2013  | 12.31  | 22.86   | 11.64    | 46.80     | 13,996,967.79      | 3,638,742.26  | 1,736,289.94  | 19,372,000.00 |  |
| 2014  | 14.13  | 27.75   | 10.83    | 52.71     | 7,667,297.44       | 4,418,233.93  | 1,616,468.63  | 13,702,000.00 |  |
| 2015  | 45.62  | 28.93   | 38.10    | 112.65    | 18,116,886.85      | 4,605,942.41  | 5,685,170.75  | 28,408,000.00 |  |
| Total | 110.54 | 120.85  | 93.74    | 325.13    | 58,167,790.01      | 19,241,153.25 | 13,988,056.73 | 91,397,000.00 |  |

| Approved   | Remarks |
|--|---------|
| Project to continue as proposed                      | ✓       |
| Project to continue with REVISED Capital Expenditure |         |
| Project to continue with Technical Amendments        |         |

Project to be deferred which may be included in its next application with additional justification

| Approved CAPEX Cost (PhP) |               |               |               |               |               |  |
|---------------------------|---------------|---------------|---------------|---------------|---------------|--|
| 2011                      | 2012          | 2013          | 2014          | 2015          | Total         |  |
| 10,543,000.00             | 19,372,000.00 | 19,372,000.00 | 13,702,000.00 | 28,408,000.00 | 91,397,000.00 |  |

# III. NON-NETWORK PROJECTS

| Project No.      | 35                             |
|------------------|--------------------------------|
| Project Title    | Communication System Equipment |
| Project Code     | СОМ                            |
| Project Type     | Customer Efficiency            |
| Priority Rank    | 4                              |
| Project Category | Non-Network Requirements       |

#### **Project Description**

|   | Daradon      |
|---|--------------|
| <ul> <li>CEBECO I intends to acquire a new communication</li> </ul> |              |
| equipment and installation of two (2) radio                         | 2011 to 2015 |
| communication repeater facilities.                                  |              |

| Proposed CAPEX Cost (PhP) |            |            |            |            |           |            |
|---------------------------|------------|------------|------------|------------|-----------|------------|
|                           | 2011       | 2012       | 2013       | 2014       | 2015      | Total      |
|                           | 334,500.00 | 112,500.00 | 112,500.00 | 226,500.00 | 76,500.00 | 862,500.00 |

#### **Project Justification**

- The communication system is one of the key factors in providing the best consumer services. Acquisition of equipment to create said system shall speed up the coordination of field personnel that lead to prompt actions to consumer requests, complaints and line services, thus, enhancing the EC's existing communication system. Generally, the communication system makes the DU's operation more efficient.
- Considering that the DU's distribution lines are extended even on mountainous part of its franchise area, additional radio equipments are needed to communicate with the field personnel. And the installations of the two radio repeater facilities will ensure that there is communication coverage in the entire franchise area.

#### **Cost Analysis**

 The proposed cost is comparable with the existing market price and available price reference in the internet. The following is the proposed project cost breakdown:

| No.      | Materials                     | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year       | Project Cost<br>(PhP) |
|----------|-------------------------------|-----------------|-------------------------|------------|-----------------------|
|          | Handheld VHF Radio (portable) | 3               | 13,500.00               |            | 40,500.00             |
| 1        | Mobile Radio w/ accessories   | 8               | 18,000.00               | 2011       | 144,000.00            |
|          | VHF Radio Repeater System     | 1               | 150,000.00              |            | 150,000.00            |
|          | Handheld VHF Radio (portable) | 3               | 13,500.00               | 2012       | 40,500.00             |
| 2        | Mobile Radio w/ accessories   | 4               | 18,000.00               | 2012       | 72,000.00             |
| <u> </u> | Handheld VHF Radio (portable) | 3               | 13,500.00               | 2013       | 40,500.00             |
| 3        | Mobile Radio w/ accessories   | 4               | 18,000.00               | 2013       | 72,000.00             |
|          | Handheld VHF Radio (portable) | 3               | 13,500.00               |            | 40,500.00             |
| 4        | Mobile Radio w/ accessories   | 2               | 18,000.00               | 2014       | 36,000.00             |
|          | VHF Radio Repeater System     | 1               | 150,000.00              |            | 150,000.00            |
| 5        | Handheld VHF Radio (portable) | 3               | 13,500.00               | 2015       | 40,500.00             |
| 5        | Mobile Radio w/ accessories   | 2               | 18,000.00               | 2015       | 36,000.00             |
|          |                               | Grand To        | tal                     | 862,500.00 |                       |

Duration

| Approved   | Remarks   |
|--|-----------|
| Project to continue as proposed                          | · · · · · |
| Project to continue with REVISED Capital Expenditure     |           |
| Project to continue with Technical Amendments            |           |
| Project to be deferred which may be included in its next |           |
| application with additional justification                |           |

| Approved C | APEX Cost ( | (PhP)      |            |           |            |
|------------|-------------|------------|------------|-----------|------------|
| 2011       | 2012        | 2013       | 2014       | 2015      | Total      |
| 334,500.00 | 112,500.00  | 112,500.00 | 226,500.00 | 76,500.00 | 862,500.00 |

| Project No.      | 36  |
|------------------|---|
| Project Title    | Geographical Information System (hardware & software) |
| Project Code     | GIS   |
| Project Type     | Customer Efficiency                                   |
| Priority Rank    | 4   |
| Project Category | Non-Network Asset Project                             |

| Project Description   | Duration    |
|---|-------------|
| <ul> <li>CEBECO I intends to acquire computer software and</li> </ul> | 2011 & 2014 |
| equipment specifically 10 units of GPS portable units.                | 2011 & 2014 |

| Proposed CAPEX Cost (PhP) |      |      |            |      |            |
|---------------------------|------|------|------------|------|------------|
| 2011                      | 2012 | 2013 | 2014       | 2015 | Total      |
| 180,000.00                | -    | -    | 120,000.00 | -    | 300,000.00 |

- Automated Mapping/Facilities Management (AM/FM) is a subset of Geographic Information System (GIS) software which allows utility users to manage and analyze the network system. The data is stored in GIS database which maintains the associations between the graphical entities and the attributes.
- The data and information is being gathered through a hardware called Global Positioning System (GPS) portable units which is then being transferred to the said GIS software.
- The software contributes in distribution system planning and other potential information and engineering applications can also be identified. The data gathered will be utilized by the engineering software to provide a better and wider view of the distribution system. This will help the DU to further understand and analyze the system efficiently.
- The acquisition of this software will give the cooperative an opportunity to improve accurate gathering of data, create automated system map and real time computation of its distribution system loss.

#### **Cost Analysis**

The following is the proposed project cost breakdown:

| No. | Materials                             | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-----|---------------------------------------|-----------------|-------------------------|------|-----------------------|
| 1   | GPS Portable Unit                     | 6               | 30,000.00               | 2011 | 180,000.00            |
| 2   | GPS Portable Unit                     | 4               | 30,000.00               | 2014 | 120,000.00            |
|     | · · · · · · · · · · · · · · · · · · · |                 | Grand Total             |      | 300,000.00            |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed                      | $\checkmark$ |
| Project to continue with REVISED Capital Expenditure |              |

|  | , |
|--|---|
|  |   |
|  |   |
| Project to continue with Technical Amendments            |   |
| Project to be deferred which may be included in its next |   |
| application with additional justification                |   |

| Approved C | APEX Cost ( | PhP) |            |      |            |
|------------|-------------|------|------------|------|------------|
| 2011       | 2012        | 2013 | 2014       | 2015 | Total      |
| 180,000.00 | -           |      | 120,000.00 | -    | 300,000.00 |

-

• •

| Project Nos.     | 37 & 38   |
|------------------|---|
| Project Title    | Meter Reading, Billing, Collection (hardware &  |
|                  | software) & Management Information System (MIS) |
| Project Code     | MRBS & MIS                                      |
| Project Type     | Customer Efficiency                             |
| Priority Rank    | 4   |
| Project Category | Non-Network Asset Project                       |

| Project Description   | Duration     |
|---|--------------|
| <ul> <li>CEBECO I intends to acquire new equipment for its</li> </ul> | 2011 to 2015 |
| meter reading, billing and collection system.                         | 2011 (0 2013 |

| Proposed CAPEX Cost (PhP) |              |              |            |              |              |  |  |  |
|---------------------------|--------------|--------------|------------|--------------|--------------|--|--|--|
| 2011                      | 2012         | 2013         | 2014       | 2015         | Total        |  |  |  |
| 1,392,900.00              | 1,989,600.00 | 1,020,500.00 | 771,000.00 | 2,664,000.00 | 7,838,000.00 |  |  |  |

- CEBECO I deems it appropriate to acquire additional and upgrade its existing meter reading, billing, collection and management information system in order to meet the fast growing demand of consumers with regard to its customer services. Considering the availability of modern day technology, the cooperative would likewise take the opportunity to utilize such in order to provide its customers adequate services it rightfully deserves.
- The upgraded new system will significantly improve the performance of the meter readers' capability. Posting and printing of materials for billing will take less time thus, ensuring a timely billing of its consumers. Moreover, the technology includes interfacing the entire devices which eventually transforms into fast, reliable and efficient way of collecting the payment.

| Matariala                          |      |      | No. of Units |      |      | Unit Cost  |
|------------------------------------|------|------|--------------|------|------|------------|
| Materials                          | 2011 | 2012 | 2013         | 2014 | 2015 | (PhP/unit) |
| Billing/Collection System          |      |      |              |      |      |            |
| Desktop Computer                   | -    | -    | 10           | 10   | 10   | 25,000.00  |
| Computer Servers                   | 2    | 4    | -            | -    | 2    | 40,000.00  |
| Laptop                             | -    | 5    | 5            | -    | -    | 30,000.00  |
| Printers, LX-300                   | 4    | 5    | 3            | 2    | 2    | 18,000.00  |
| Printers, desk-jet                 | 3    | -    | 9            | -    | -    | 3,500.00   |
| Printer, high-speed, dot matrix    | -    | 1    | -            | -    | -    | 200,000.00 |
| Routers                            | -    | 3    | -            | -    | -    | 8,000.00   |
| Central Processing Unit            | 5    | 5    | 5            | 5    | 5    | 17,000.00  |
| Uninterruptible Power<br>Supply    | 3    | 3    | -            | -    | -    | 25,000.00  |
| Meter Reading Facilities           |      |      |              |      |      |            |
| Meter Reading Equipment            | 4    | 6    | -            | -    | 5    | 42,600.00  |
| Meter Reading Equipment<br>Printer | 20   | -    | -            | -    | 20   | 45,000.00  |

| Meter Reading Equipment,<br>Infrared | -            | 2            | -            | 2          | -            | 50,000.00    |
|--------------------------------------|--------------|--------------|--------------|------------|--------------|--------------|
| Software                             | ]            |              |              |            |              |              |
| Licensed Microsoft Server 2008       | -            | 1            | -            | -          | 1            | 800,000.00   |
| Anti-Virus                           | -            | -            | -            | 1          | 1            | 300,000.00   |
| Trainings/Seminars                   | ]            |              |              |            |              |              |
| Visual Studio 2010<br>Programming    | -            | -            | _ 1          | -          | -            | 50,000.00    |
| SQL Server Administration            |              | 1            | -            | -          | -            | 50,000.00    |
| MIS                                  | ]            |              |              |            |              |              |
| Interconnection fees                 | -            | -            | 1            | -          | -            | 400,000.00   |
| Project Cost (PhP)                   | 1,392,900.00 | 1,989,600.00 | 1,020,500.00 | 771,000.00 | 2,664,000.00 | 7,838,000.00 |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed  | $\checkmark$ |
| Project to continue with REVISED Capital Expenditure   |              |
| Project to continue with Technical Amendments  |              |
| Project to be deferred which may be included in its next application with additional justification |              |

| Approved CAPEX Cost (PhP) |              |              |            |              |              |  |  |  |
|---------------------------|--------------|--------------|------------|--------------|--------------|--|--|--|
| 2011                      | 2012         | 2013         | 2014       | 2015         | Total        |  |  |  |
| 1,392,900.00              | 1,989,600.00 | 1,020,500.00 | 771,000.00 | 2,664,000.00 | 7,838,000.00 |  |  |  |

| Project No.      | 39                                  |
|------------------|-------------------------------------|
| Project Title    | Tools, Instruments & Test Equipment |
| Project Code     | TTE                                 |
| Project Type     | Customer Efficiency                 |
| Priority Rank    | 4                                   |
| Project Category | Non-Network Asset Project           |

| Project Description  | Duration     |
|--|--------------|
| <ul> <li>CEBECO I proposed the acquisition of several tools,<br/>devices and equipment, as detailed in the cost<br/>analysis.</li> </ul> | 2011 to 2015 |

| Proposed CAPEX Cost (PhP) |              |              |              |              |               |  |  |  |
|---------------------------|--------------|--------------|--------------|--------------|---------------|--|--|--|
| 2011                      | 2012         | 2013         | 2014         | 2015         | Total         |  |  |  |
| 9,203,736.00              | 3,882,693.80 | 8,911,342.80 | 5,116,743.80 | 2,120,743.80 | 29,235,260.20 |  |  |  |

 The project is essential in order to improve the DU's performance in terms of efficiency, reliability while maintaining a safe distribution system. The proposed procurements are categorized as follows:

| Line Tools                              | The addition of line maintenance tools for line personnel is crucial in order to meet the demand with regard to customer service.   |
|---|---|
| Testing<br>Equipment                    | The equipments shall be used for the testing, commissioning<br>and maintaining the network assets of CEBECO I as a<br>compliance to the monitoring and technical standard<br>requirements of the Philippine Grid and Distribution Codes<br>(PGDC).  |
| Line<br>Monitoring<br>Equipment         | The equipment shall be used as a tool to monitor and gather<br>essential data within the distribution system in order to construct<br>technical planning and ensure the best electric service to its<br>customers.  |
| Consumer<br>Services<br>Equipment       | The equipment shall be used as a tool to communicate<br>information to the member consumers in a more presentable<br>way. Documentation of important events will be easier. Relaying<br>of important information and messages through audio-visuals will<br>be the most efficient and presentable way in providing better<br>services to consumers. |
| Engineering<br>Software<br>and Training | The software shall serve as a tool to aid the engineers in solving<br>and analyzing distribution system while the training shall<br>enhance their technical capabilities.   |
| Motor Pool<br>Equipment                 | Acquisition of new motor pool equipment shall shorten the repair time of vehicles during maintenance operation.   |

 The Commission, on the other hand, believes that the customer services equipment and trainings should form part of CEBECO I's operations and maintenance (O&M) expenditures.  The proposed project is hereby approved to be re-aligned to form part of CEBECO I's O&M budget.

# Cost Analysis

• The following is the proposed project cost breakdown, to wit:

| Materials                             |      | ¥    | No. of Units |      |      | Unit Cost   |
|---------------------------------------|------|------|--------------|------|------|-------------|
| Waterials                             | 2011 | 2012 | 2013         | 2014 | 2015 | (PhP/unit)  |
| Testing Equipment                     |      |      |              |      |      |             |
| Earth Resistance Tester               | 1    | -    | -            | -    | -    | 300,000.0   |
| 70kV Hi-Pot Tester                    | -    | 1    | -            | -    | -    | 1,200,000.0 |
| Insulation Power Factor<br>Tester     | -    | -    | 1            | -    | -    | 1,825,000.0 |
| 10kV Insulation Tester                | -    | -    | -            | 1    | -    | 850,000.0   |
| Transformer Turns Ratio<br>Tester     | -    | -    | 1            | -    | -    | 1,100,000.0 |
| Burden Tester (CT & PT)               | 1    | -    | -            | -    | -    | 1,250,000.0 |
| Norking Meter Standards               | -    | -    | 1            | -    | -    | 2,507,599.0 |
| Portable Meter Standards              | 1    | -    | -            | -    | -    | 1,205,456.0 |
| Line Monitoring<br>Equipment          |      |      |              |      |      |             |
| Load Profiler                         | 2    | -    | -            | 4    | -    | 550,000.0   |
| Voltage Recorder                      | 4    | -    | -            | 2    | •    | 80,000.0    |
| Line Tool                             |      |      |              |      |      |             |
| 15kV Wireless Ammeter                 | 4    | -    | -            | 2    | -    | 100,000.0   |
| Ampact Tool                           | 2    | -    | -            | -    | 2    | 120,000.0   |
| Chain Saw                             | 3    | -    | -            | 2    | -    | 45,000.0    |
| 6-ton Hydraulic<br>Compression Tool   | 3    | -    | -            | -    | -    | 84,160.0    |
| 10kV Conductor Cover                  | -    | -    | 12           | -    | -    | 50,000.0    |
| Construction Tools Set                | -    | 10   | 10           | 10   | 10   | 23,469.3    |
| Crimping Tool                         | 5    | 1    | 1            | 1    | 4    | 25,000.0    |
| Grounding Cluster                     | -    | 1    | -            | -    | -    | 150,000.0   |
| 10ft. Hot Stick                       | 5    | 4    | -            | -    | -    | 28,650.0    |
| Hot Stick Telescopic                  | 4    | 2    | -            | 2    | -    | 35,500.0    |
| Hot Stick, Grip-all clamp<br>stick    | 6    | 3    | 1            | 1    | 1    | 33,800.0    |
| adder, Fiber Glass                    |      | 1    | 1            | -    | 1    | 20,000.0    |
| ineman Climbers Set                   | 15   | -    | 25           | 5    | 5    | 43,450.0    |
| _oad Buster                           |      | -    | 3            | -    | 3    | 165,000.0   |
| Clamp Digital Multi Tester            | 2    | 2    | 2            | 2    | 2    | 40,000.0    |
| 10kV Pole Top Cover                   | 9    | -    | -            | -    | -    | 45,000.0    |
| Rangefinder                           | 6    | -    | -            | 3    | -    | 15,000.0    |
| Sling, Webbing                        | -    | 6    | -            | -    | 2    | 8,000.0     |
| Fransit Surveying Tool,<br>Theodolite | 2    | -    | -            | -    | -    | 150,000.0   |
| Consumer Services<br>Equipment        |      |      |              |      |      |             |
| Camera, still                         | 4    | ľ1   | 2            | 1    | 1    | 15,000.0    |
| (professional)<br>Camera, video       | 2    | 2    | 3            | 1    | 1    | 45,000.0    |
| Gen Set 5 KVA                         | 2    | 1    | 1            | 2    | 1    | 61,000.0    |
| Monitor, LCD                          | 1    | 2    | 2            | 2    | 1    | 9,000.0     |
| Photocopier                           | 1    | 2    | 1            | 2    | 1    | 80,000.0    |
| Printer, desk-jet with scanner        | 4    | 2    | 2            | 2    | 3    | · 9,000.0   |
| Printer, heavy duty                   | 2    | 1    | 1            | 1    | 1    | 17,000.0    |
| Projector, multi-media                | 2    | 1    | 1            | 2    | 1    | 85,000.0    |
| Public Address System                 | -    | 1    | -            | -    | -    | 384,000.0   |
| Engineering Software &<br>Training    |      |      |              |      |      |             |
| Engineering Software                  | 1    | -    | -            | - [  | -    | 800,000.0   |
| Trainings for Engineers               | 4    | 4    | 4            | 3    | 3    | 115,000.0   |

| Motor Pool Equipment    |              |              |              |              |              |               |
|-------------------------|--------------|--------------|--------------|--------------|--------------|---------------|
| Electric Tire Changer   | -            | 1            | •            | -            | -            | 80,000.00     |
| Electric Vehicle Lifter | -            | 2            | -            | -            | -            | 150,000.00    |
| Pneumatic torque gun    | -            | 1            | -            | -            | -            | 150,000.00    |
| Project Cost (PhP)      | 9,203,736.00 | 3.882.693.80 | 8.911.342.80 | 5,116,743,80 | 2.120.743.80 | 29,235,260.20 |

 With the above cited technical approval, the total project cost should be reduced. The breakdown of the approved project cost should be as follows:

| Matariala                             |              |              | No. of Units |              |              | Unit Cost    |
|---------------------------------------|--------------|--------------|--------------|--------------|--------------|--------------|
| Materials                             | 2011         | 2012         | 2013         | 2014         | 2015         | (PhP/unit)   |
| Testing Equipment                     | ]            |              |              |              |              |              |
| Earth Resistance                      | 1            | -            | -            | -            | _            | 300,000.00   |
| Tester<br>70kV Hi-Pot Tester          | -            | 1            |              |              | -            | 1,200,000.00 |
| Insulation Power                      |              | ·            |              |              |              |              |
| Factor Tester                         | -            | -            | 1            | -            | -            | 1,825,000.0  |
| 10kV Insulation Tester                | -            | -            | -            | 1            | -            | 850,000.0    |
| Transformer Turns<br>Ratio Tester     | -            | -            | 1            | -            | -            | 1,100,000.0  |
| Burden Tester (CT & PT)               | 1            | -            | -            | -            | -            | 1,250,000.0  |
| Working Meter<br>Standards            | -            | -            | 1            | -            | -            | 2,507,599.0  |
| Portable Meter<br>Standards           | 1            | -            | -            | -            | -            | 1,205,456.0  |
| Line Monitoring<br>Equipment          | ]            |              |              |              |              |              |
| Load Profiler                         | 2            | -            | -            | 4            | -            | 550,000.0    |
| Voltage Recorder                      | 4            | -            | -            | 2            | -            | 80,000.0     |
| Line Tool                             | , <u> </u>   | ı            | L            |              |              |              |
| 15kV Wireless                         |              |              | 1            | <u> </u>     |              |              |
| Ammeter                               | 4            | -            | -            | 2            | -            | 100,000.0    |
| Ampact Tool                           | 2            | -            | -            | -            | 2            | 120,000.0    |
| Chain Saw                             | 3            | -            | -            | 2            | -            | 45,000.0     |
| 6-ton Hydraulic<br>Compression Tool   | 3            | -            | -            | •            | -            | 84,160.0     |
| 10kV Conductor Cover                  | -            | -            | 12           | -            | -            | 50,000.0     |
| Construction Tools Set                | -            | 10           | 10           | 10           | 10           | 23,469.3     |
| Crimping Tool                         | 5            | 1            | 1            | 1            | 4            | 25,000.0     |
| Grounding Cluster                     | -            | 1            | -            | -            | -            | 150,000.0    |
| 10ft. Hot Stick                       | 5            | 4            | -            | -            | -            | 28,650.0     |
| Hot Stick Telescopic                  | 4            | 2            | -            | 2            | -            | 35,500.0     |
| Hot Stick, Grip-all<br>clamp stick    | 6            | 3            | 1            | 1            | 1            | 33,800.0     |
| Ladder, Fiber Glass                   | -            | 1            | 1            | -            | 1            | 20,000.0     |
| Lineman Climbers Set                  | 15           | -            | 25           | 5            | 5            | 43,450.0     |
| Load Buster                           | -            | -            | 3            |              | 3            | 165,000.0    |
| Clamp Digital Multi<br>Tester         | 2            | 2            | 2            | 2            | 2            | 40,000.0     |
| 10kV Pole Top Cover                   | 9            | -            | -            | -            | -            | 45,000.0     |
| Rangefinder                           | 6            |              | -            | 3            | -            | 15,000.0     |
| Sling, Webbing                        | -            | 6            | -            | -            | 2            | 8,000.0      |
| Transit Surveying Tool,<br>Theodolite | 2            | -            | -            | -            | -            | 150,000.0    |
| Engineering Software<br>& Training    |              |              |              |              |              |              |
| Engineering Software                  | 1            | -            | -            | -            | -            | 800,000.0    |
| Motor Pool<br>Equipment               |              |              |              |              |              |              |
| Electric Tire Changer                 | -            | 1            | -            | -            | -            | 80,000.0     |
| Electric Vehicle Lifter               | -            | 2            | -            | -            | -            | 150,000.0    |
| Pneumatic torque gun                  | -            | 1            | -            | -            |              | 150,000.0    |
| Project Cost (PhP)                    | 8,142,736.00 | 2,574,693.80 | 8,007,342.80 | 4,206,743.80 | 1,436,743.80 | 24,368,260.2 |

| Approved   | Remarks                               |
|--|---------------------------------------|
| Project to continue as proposed                          |                                       |
| Project to continue with REVISED Capital Expenditure     |                                       |
| Project to continue with Technical Amendments            | ✓                                     |
| Project to be deferred which may be included in its next | · · · · · · · · · · · · · · · · · · · |
| application with additional justification                | ·                                     |

| Approved C   |              |              |              |              |               |
|--------------|--------------|--------------|--------------|--------------|---------------|
| 2011         | 2012         | 2013         | 2014         | 2015         | Total         |
| 8,142,736.00 | 2,574,693.80 | 8,007,342.80 | 4,206,743.80 | 1,436,743.80 | 24,368,260.20 |

| Project No.      | 40                        |  |
|------------------|---------------------------|--|
| Project Title    | Vehicles                  |  |
| Project Code     | VHL                       |  |
| Project Type     | Customer Efficiency       |  |
| Priority Rank    | 4                         |  |
| Project Category | Non-Network Asset Project |  |

| Project Description   | Duration     |
|---|--------------|
| <ul> <li>CEBECO I intends to acquire utility and service</li> </ul> | 2011 to 2015 |
| vehicles for operation and maintenance.                             | 2011 (0 2013 |

| Proposed CAPEX Cost (PhP) |              |               |               |              |               |  |
|---------------------------|--------------|---------------|---------------|--------------|---------------|--|
| 2011                      | 2012         | 2013          | 2014          | 2015         | Total         |  |
| 13,170,000.00             | 9,050,000.00 | 15,705,000.00 | 10,080,000.00 | 5,050,000.00 | 53,055,000.00 |  |

## Project Justification / Cost Analysis

- CEBECO I intends to augment its existing fleet of vehicles and also to replace the ones that are already beyond its standard asset life.
- CEBECO I deems the project necessary in order to meet the growing demand of consumers. The continuous increase in the distribution lines, the power demand and the number of customers should definitely require an expansion of service vehicles in order to maintain these assets appropriately and responding to customer demands more efficiently.
- The following table shows the proposed number and type of vehicles for the entire applied CAPEX years:

| Vehicle Type            | Cargo<br>truck | Pick-up<br>truck | Boom<br>truck | Van | Jeep | Motorcycle | Forklift | Mini-<br>Bus | TOTAL |
|-------------------------|----------------|------------------|---------------|-----|------|------------|----------|--------------|-------|
| Proposed Qty.<br>(Unit) | 9              | 10               | 8             | 1   | 6    | 35         | 1        | 1            | 71    |

# • The following table is the proposed project cost breakdown, to wit:

| Vohiele Tunc                      |               | No. of Units |               |               |              |              |  |  |
|-----------------------------------|---------------|--------------|---------------|---------------|--------------|--------------|--|--|
| Vehicle Type                      | 2011          | 2012         | 2013          | 2014          | 2015         | (PhP)        |  |  |
| Jeep                              | 2             | 1            | 1             | 1             | 1            | 300,000.00   |  |  |
| Motorcycle                        | 11            | 5            | 5             | 9             | 5            | 70,000.00    |  |  |
| Boom truck, 6-<br>wheel           | 2             | 1            | 1             | 1             | 1            | 1,250,000.00 |  |  |
| Boom truck, Bucket                | 1             | -            | -             | -             | -            | 5,850,000.00 |  |  |
| Boom truck,<br>Palfinger / Fascii | -             | -            | 1             | -             | -            | 7,355,000.0  |  |  |
| Cargo Truck, 4x4                  | 1             | 1            | -             | 1             | -            | 1,750,000.00 |  |  |
| Forklift truck                    | •             | 1            | •             | -             | -            | 2,250,000.00 |  |  |
| Cargo Truck, light                | 1             | 1            | 2             | 1             | 1            | 500,000.00   |  |  |
| Mini-bus                          | -             | -            | -             | 1             | -            | 3,000,000.00 |  |  |
| Pick-up truck                     | 1             | 1            | 2             | 1             | 1            | 1,200,000.0  |  |  |
| Pick-up truck                     | -             | 1            | 1             | 1             | 1            | 1,450,000.0  |  |  |
| Van                               | -             |              | 1             | -             | -            | 1,600,000.0  |  |  |
| Project Cost (PhP)                | 13,170,000.00 | 9,050,000.00 | 15,705,000.00 | 10,080,000.00 | 5,050,000.00 | 53,055,000.0 |  |  |

The Commission, however, deferred the proposed project considering that CEBECO I failed to provide any proof or justification on each of the vehicle type's purpose in its operation. Moreover, it failed to justify the required number of vehicles that the EC should possess in order to satisfy the demand in terms of customer services. CEBECO I should properly determine the required number of vehicles, corresponding to its use, that will serve and satisfy the entire franchise or for each municipality.

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed  |              |
| Project to continue with REVISED Capital Expenditure   |              |
| Project to continue with Technical Amendments  |              |
| Project to be deferred which may be included in its next application with additional justification | $\checkmark$ |

| Approved C | APEX Cost ( | (PhP) |      |      |       |
|------------|-------------|-------|------|------|-------|
| 2011       | 2012        | 2013  | 2014 | 2015 | Total |
| -          | -           | -     | -    | -    | -     |

| Project No.      | 41                          |  |
|------------------|-----------------------------|--|
| Project Title    | Computers & Other Equipment |  |
| Project Code     | COMP                        |  |
| Project Type     | Customer Efficiency         |  |
| Priority Rank    | 4                           |  |
| Project Category | Non-Network Asset Project   |  |

| Project Description  | Duration     |
|--|--------------|
| <ul> <li>The project consists of replacing some of the existing<br/>computer set-up of the cooperative with brand new<br/>computers. The replacement shall be prioritized<br/>according to units with outdated systems and<br/>incapable of performing at its expected level.</li> </ul> | 2011 to 2015 |

| Proposed C | APEX Cost ( | (PhP)      |            |            |              |
|------------|-------------|------------|------------|------------|--------------|
| 2011       | 2012        | 2013       | 2014       | 2015       | Total        |
| 600,000.00 | 530,850.00  | 530,850.00 | 575,850.00 | 571,850.00 | 2,809,400.00 |

- CEBECO I intends to offer the best possible services to its customers through this project. The acquisition of new computer units for the distribution utility personnel shall further extend their capabilities in terms of performing customer services.
- Obsolete units shall be replaced with the latest unit in order for the personnel to cope up with the modern technology which in effect, achieves the goal of the cooperative as stated above.
- However, it failed to justify the proposed units of laptops to be acquired as well as its detailed designation to its personnel.
- The Commission, thereby, approved the reduction of laptop units to be procured. The Commission considered allotting the said devices to the existing number of head officials of CEBECO I considering that these personnel require additional tasks and field works.

## Cost Analysis

The following is the proposed project cost breakdown:

| Materials                |            | No. of Units |            |            |            |              |
|--------------------------|------------|--------------|------------|------------|------------|--------------|
| waterials                | 2011       | 2012         | 2013       | 2014       | 2015       | (PhP/unit)   |
| Computers, desktop       | 6          | 6            | 6          | 6          | 6          | 30,000.00    |
| Hard-disk, portable, USB | -          | 4            | 4          | 4          | 3          | 4,000.00     |
| Laptop1                  | 4          | 4            | 4          | 4          | 4          | 60,000.00    |
| Laptop2                  | 4          | 2            | 2          | 3          | 3          | 45,000.00    |
| UPS                      | -          | 1            | 1          | 1          | 1          | 4,850.00     |
| Project Cost (PhP)       | 600,000.00 | 530,850.00   | 530,850.00 | 575,850.00 | 571,850.00 | 2,809,400.00 |

- The Commission approved the reduction of the proposed project cost and the adjustment of the unit cost of the laptop consistent with the initial proposal for its unit cost which was also included in the other projects.
- The following is the approved project cost breakdown:

| Materials                |                |            | Unit Cost  |            |            |              |
|--------------------------|----------------|------------|------------|------------|------------|--------------|
| waterials                | 2011 2012 2013 |            | 2014       | 2015       | (PhP/unit) |              |
| Computers, desktop       | 6              | 6          | 6          | 6          | 6          | 25,000.00    |
| Hard-disk, portable, USB | -              | 4          | 4          | 4          | 3          | 2,000.00     |
| Laptop                   | 4              | 4          | 4          | 4          | 4          | 30,000.00    |
| UPS                      | -              | 1          | 1          | 1          | 1          | 2,500.00     |
| Project Cost (PhP)       | 270,000.00     | 280,500.00 | 280,500.00 | 280,500.00 | 278,500.00 | 1,390,000.00 |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed  |              |
| Project to continue with REVISED Capital Expenditure   | $\checkmark$ |
| Project to continue with Technical Amendments  | $\checkmark$ |
| Project to be deferred which may be included in its next application with additional justification |              |

| Approved C | APEX Cost ( | PhP)       |            |            |              |
|------------|-------------|------------|------------|------------|--------------|
| 2011       | 2012        | 2013       | 2014       | 2015       | Total        |
| 270,000.00 | 280,500.00  | 280,500.00 | 280,500.00 | 278,500.00 | 1,390,000.00 |

| Project No.      | 42                        |  |
|------------------|---------------------------|--|
| Project Title    | Buildings & Lots          |  |
| Project Code     | BLDG                      |  |
| Project Type     | Customer Efficiency       |  |
| Priority Rank    | 4                         |  |
| Project Category | Non-Network Asset Project |  |

| Project Description   | Duration     |
|---|--------------|
| <ul> <li>The location of the proposed area office building shall<br/>be constructed at the municipalities of Carcar, Argao,<br/>Ginatilan and Moalboal. The said sub-offices shall<br/>serve as the collection and payment center and the<br/>headquarters for each specified area's technical crew<br/>intended for line maintenance routine and customer<br/>services.</li> </ul> | 2011 to 2015 |
| <ul> <li>The project also includes the construction of covered<br/>storage and customer's assembly buildings/multi-<br/>purpose building. The Multi-purpose building design<br/>shall have a capacity of 4,000 persons and will be<br/>constructed with a stage and comfort rooms.</li> </ul>   |              |

| Proposed CAPEX Cost (PhP) |              |              |              |              |               |  |
|---------------------------|--------------|--------------|--------------|--------------|---------------|--|
| 2011                      | 2012         | 2013         | 2014         | 2015         | Total         |  |
| 19,350,057.00             | 1,289,715.57 | 1,310,307.57 | 7,550,164.00 | 7,738,293.42 | 37,238,537.56 |  |

- The existing sub-offices in the municipalities of Carcar, Argao, Ginatilan and Moalboal are being rented by CEBECO I. These suboffices are generally where transactions take place such as customer payments, monetary and material collections, data processing, and other necessary customer services.
- The proposed construction of sub-offices and storage building in the main office shall address the following problems being encountered particularly by the customers with the existing conditions and location of the said sub-offices:
  - a) The location of Carcar and Argao sub-offices are within city proper wherein traffic is normally congested. The said situation provides difficulty for the customers during their billing payments as well as for the area crew during line and customer emergency responses;
  - b) The location of Ginatilan and Moalboal sub-offices compromises safety considering that it is located near the highway road wherein collection activities inside the office can easily be seen from the outside;
  - c) The location of Ginatilan and Moalboal sub-offices also provides physical difficulties for the customers, such as sun exposure and exhaustion, due to insufficient customer lounge;

- d) The parking space of these sub-offices are limited; and
- e) The storage area for the required materials and other significant equipment are very limited. It is crucial for the cooperative to have more than enough storage area considering that the demand for said materials is continuously increasing.
- It shall provide great positive impact for both the customers and the cooperative's staff and crew in terms of safe and conducive place for the necessary transactions. The DU shall also achieve its goal of providing a better service performance to its customers.
- The proposed multi-purpose building, located in the main office, shall be used as a place for annual general membership meetings, anniversaries and other programs of the cooperative.

# Cost Analysis

• The following is the proposed project cost breakdown:

| No. | Project                               | Lot / Building<br>Area (sq. m.) | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-----|---------------------------------------|---------------------------------|-----------------|-------------------------|------|-----------------------|
|     | Carcar Area Office                    | 127.31                          | 1 set           | 4,350,057.00            | 2011 | 4,350,057.00          |
| 1   | Lot acquisition at Carcar, Cebu       | 3,000.00                        | 3,000           | 5,000.00                | 2011 | 15,000,000.00         |
| 2   | Argao Area Office                     | 127.31                          | 1 set           | 1,289,715.57            | 2012 | 1,289,715.57          |
| 3   | Covered Storage Bldg. at main office  | 150.00                          | 1 set           | 1,310,307.57            | 2013 | 1,310,307.57          |
| _   | Ginatilan Area Office                 | 127.31                          | 1 set           | 1,550,164.00            | 2014 | 1,550,164.00          |
| 4   | Lot acquisition at Moalboal, Cebu     | 2,000.00                        | 2,000           | 3,000.00                | 2014 | 6,000,000.00          |
| ~   | Multi-purpose Building at main office | 960.00                          | 1 set           | 6,448,577.85            | 2015 | 6,448,577.85          |
| 5   | Moalboal Area Office                  | 127.31                          | 1 set           | 1,289,715.57            | 2015 | 1,289,715.57          |
|     |                                       |                                 |                 | Crond To                | 4-1  | 27 229 527 56         |

- Grand Total 37,238,537.56
- The Commission approved the reduction of the proposed costs of the projects based on its review. It can be noted that there are inconsistencies in the proposed cost for the construction of sub-offices. The proposed costs should have been the same considering that based on the submitted designs, the dimensions and land area of the buildings are exactly the same. CEBECO I did not provide further justification. The Commission, therefore, adjusted and set a consistent cost for the said activity.
- The following is the approved project cost breakdown:

| No. | Project                               | Lot / Building<br>Area (sq. m.) | No. of<br>Units | Unit Cost<br>(PhP/unit) | Year | Project Cost<br>(PhP) |
|-----|---------------------------------------|---------------------------------|-----------------|-------------------------|------|-----------------------|
|     | Carcar Area Office                    | 127.31                          | 1 set           | 1,289,715.57            | 2011 | 1,289,715.57          |
| 1   | Lot acquisition at Carcar, Cebu       | 3,000.00                        | 3,000           | 5,000.00                | 2011 | 15,000,000.00         |
| 2   | Argao Area Office                     | 127.31                          | 1 set           | 1,289,715.57            | 2012 | 1,289,715.57          |
| 3   | Covered Storage Bldg. at main office  | 150.00                          | 1 set           | 1,310,307.57            | 2013 | 1,310,307.57          |
|     | Ginatilan Area Office                 | 127.31                          | 1 set           | 1,289,715.57            | 2014 | 1,289,715.57          |
| 4   | Lot acquisition at Moalboal, Cebu     | 2,000.00                        | 2,000           | 3,000.00                | 2014 | 6,000,000.00          |
| -   | Multi-purpose Building at main office | 960.00                          | 1 set           | 6,448,577.85            | 2015 | 6,448,577.85          |
| 5   | Moalboal Area Office                  | 127.31                          | 1 set           | 1,289,715.57            | 2015 | 1,289,715.57          |
|     |                                       |                                 |                 | Grand To                | tal  | 33,917,747.70         |

| Approved   | Remarks      |
|--|--------------|
| Project to continue as proposed  |              |
| Project to continue with REVISED Capital Expenditure   | $\checkmark$ |
| Project to continue with Technical Amendments  | $\checkmark$ |
| Project to be deferred which may be included in its next application with additional justification |              |

| Approved CAPEX Cost (PhP) |              |              |              |              |               |
|---------------------------|--------------|--------------|--------------|--------------|---------------|
| 2011                      | 2012         | 2013         | 2014         | 2015         | Total         |
| 16,289,715.57             | 1,289,715.57 | 1,310,307.57 | 7,289,715.57 | 7,738,293.42 | 33,917,747.70 |